

CALL ORDER : 420

CONTRACT ID : B -29503-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-52710 SIDEWALK, CONCRETE, REMOVE	220.000	SYS
12	203-02000 EXCAVATION, COMMON	7,490.000	CYS
13	203-02010 EXCAVATION, ROCK	100.000	CYS
14	203-02070 BORROW	10,084.000	CYS
15	205-03371 SEDIMENT, REMOVE	83.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	88.000	TON
17	205-06933 TEMPORARY INLET PROTECTION	2.000	EACH
18	205-06936 TEMPORARY SEDIMENT TRAP	68.000	TON
19	205-06937 TEMPORARY SILT FENCE	2,765.000	LFT
20	206-51220 EXCAVATION, WET	885.000	CYS
21	206-51225 EXCAVATION, DRY	1,095.000	CYS
22	206-51235 COFFERDAM	LUMP	LUMP
23	207-08265 SUBGRADE TREATMENT, TYPE IIA	4,962.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	177.000	SYS
25	211-02050 B BORROW	545.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	185.000	CYS
27	211-09266 STRUCTURAL BACKFILL, TYPE 3	2,839.000	CYS
28	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	2.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,654.000	TON
30	302-07455 DENSE GRADED SUBBASE	28.000	CYS
31	303-01180 COMPACTED AGGREGATE, NO. 53	5.000	TON
32	306-08036 MILLING, ASPHALT, 2 IN	1,520.000	SYS
33	306-08043 MILLING, TRANSITION	1,060.000	SYS
34	401-10258 JOINT ADHESIVE, SURFACE	2,060.000	LFT
35	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,060.000	LFT
36	402-07433 HMA SURFACE, TYPE B	532.000	TON
37	402-07438 HMA INTERMEDIATE, TYPE B	1,333.000	TON
38	406-05520 ASPHALT FOR TACK COAT	1.000	TON
39	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
40	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
42	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	275.000	LFT
43	602-06729 BARRIER DELINEATOR	14.000	EACH
44	604-06070 SIDEWALK, CONCRETE	220.000	SYS
45	604-07901 CURB RAMP, CONCRETE, G	10.000	SYS
46	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	168.000	SYS
47	610-07487 HMA FOR APPROACHES, TYPE B	15.000	TON
48	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
49	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH

CALL ORDER : 420

CONTRACT ID : B -29503-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	615-06490 RIGHT OF WAY MARKER	24.000	EACH
51	615-06505 MONUMENT, B	14.000	EACH
52	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
53	616-02320 GEOTEXTILES	2,750.000	SYS
54	616-05688 RIPRAP, CLASS 1	1,535.000	TON
55	616-06405 RIPRAP, REVETMENT	115.000	TON
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
57	621-01743 SEED MIXTURE, GRASS, 2	154.000	LBS
58	621-01743 SEED MIXTURE, GRASS, 2	17.000	LBS
59	621-03787 SEED MIXTURE, D	7.000	LBS
60	621-06545 FERTILIZER	1.000	TON
61	621-06553 SEED MIXTURE, R	149.000	LBS
62	621-06557 SEED MIXTURE, T	386.000	LBS
63	621-06565 MULCHING MATERIAL	2.000	TON
64	621-06567 WATER	46.000	KGAL
65	621-06574 SODDING	737.000	SYS
66	621-06575 SODDING, NURSERY	1,243.000	SYS
67	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	150.000	EACH
68	622-52436 SIGN, DO NOT MOW OR SPRAY	16.000	EACH
69	622-98200 SIGN, DO NOT DISTURB	16.000	EACH
70	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
71	628-09402 FIELD OFFICE, B	18.000	MOS
72	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	54.000	MOS
73	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
74	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
75	701-09557 TEST PILE, DYNAMIC, PRODUCTION	33.000	LFT
76	701-09557 TEST PILE, DYNAMIC, PRODUCTION	36.000	LFT
77	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
78	701-09739 PILE SHOE, HP 12 X 53	20.000	EACH
79	701-09770 PILE SHOE, HP 14 X 73	34.000	EACH
80	701-09779 PREBORED HOLE, 15"	152.000	LFT
81	701-51195 PILE, STEEL H, HP 12 IN X 53	615.000	LFT
82	701-93575 PILE, STEEL H, HP 14 IN X 73	858.000	LFT
83	702-51005 CONCRETE, A, SUBSTRUCTURE	86.000	CYS
84	702-51015 CONCRETE, B, FOOTINGS	152.000	CYS
85	702-92857 CONCRETE, C, SUBSTRUCTURE	215.000	CYS
86	703-06028 REINFORCING BARS	11,042.000	LBS
87	703-06029 REINFORCING BARS, EPOXY COATED	126,096.000	LBS
88	704-51002 CONCRETE, C, SUPERSTRUCTURE	277.000	CYS
89	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
90	706-51020 RAILING, CONCRETE, C	40.000	CYS
91	707-09332 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 66 IN X 48 IN	836.000	LFT
92	709-51821 SURFACE SEAL	LUMP	LUMP
93	713-04509 TEMPORARY PIPE	LUMP	LUMP
94	714-99072 TIEBACK WALL	LUMP	LUMP
95	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	106.000	LFT
96	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	50.000	LFT
97	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
98	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH

CALL ORDER : 420

CONTRACT ID : B -29503-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
100	720-45030 INLET, E7	1.000	EACH
101	731-07016 FACE PANELS, WIRE	2,880.000	SFT
102	731-93946 WALL ERECTION	2,880.000	SFT
103	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
104	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
105	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,000.000	LFT
106	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
107	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
108	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
109	801-07118 BARRICADE, III-A	60.000	LFT
110	801-07119 BARRICADE, III-B	48.000	LFT
111	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	224.000	LFT
112	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	11.000	LFT
113	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
114	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	62.000	SFT
115	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	48.000	SFT
116	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	250.000	LFT
117	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	6,334.000	LFT
118	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	5,334.000	LFT
119	808-75035 LINE, PAINT, SOLID, WHITE, 24 IN	49.000	LFT
120	211-06467 AGGREGATE FOR END BENT BACKFILL	40.000	CYS
121	715-05407 PIPE, END BENT DRAIN, 6 IN	58.000	LFT
122	203-08279 EXPANDED POLYSTYRENE FILL	179.000	CYS