

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	2,590.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	1,096.000	LFT
13	202-02637 PIPE, ABANDON AND GROUT FILL	13.000	LFT
14	202-02928 CATCH BASIN, REMOVE	15.000	EACH
15	202-52710 SIDEWALK, CONCRETE, REMOVE	2,335.000	SYS
16	202-86946 HANDHOLE, REMOVE	2.000	EACH
17	202-91385 INLET, REMOVE	2.000	EACH
18	202-93047 MANHOLE, REMOVE	2.000	EACH
19	202-93995 SIGNAL POLE FOUNDATION, REMOVE	2.000	EACH
20	202-93999 SIGNAL POLE, REMOVE	2.000	EACH
21	202-96133 PIPE, REMOVE	2,850.000	LFT
22	203-02000 EXCAVATION, COMMON	4,372.500	CYS
23	205-06933 TEMPORARY INLET PROTECTION	112.000	EACH
24	205-06937 TEMPORARY SILT FENCE	13,121.000	LFT
25	205-09543 NO 2 STONE	100.000	TON
26	207-08263 SUBGRADE TREATMENT, TYPE IA	33,977.800	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,127.100	SYS
28	211-09264 STRUCTURAL BACKFILL, TYPE 1	5,117.700	CYS
29	214-07202 GEOGRID, TYPE I	500.000	SYS
30	303-01180 COMPACTED AGGREGATE, NO. 53	1,097.700	TON
31	304-07491 HMA PATCHING, TYPE C	639.400	TON
32	304-07494 WIDENING WITH HMA, TYPE C	813.500	TON
33	306-08034 MILLING, ASPHALT, 1 1/2 IN	7,510.000	SYS
34	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,889.400	TON
35	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	619.600	TON
36	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,149.000	TON
37	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	1,032.600	TON
38	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	5,038.400	TON
39	402-07432 HMA SURFACE, TYPE A	332.200	TON
40	402-07433 HMA SURFACE, TYPE B	11.300	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	553.600	TON
42	402-07438 HMA INTERMEDIATE, TYPE B	26.400	TON
43	402-07440 HMA BASE, TYPE A	275.800	TON
44	405-05517 ASPHALT FOR PRIME COAT	85.100	TON
45	406-05520 ASPHALT FOR TACK COAT	2.800	TON
46	601-02241 GUARDRAIL, REMOVE	688.000	LFT
47	604-06070 SIDEWALK, CONCRETE	2,096.700	SYS
48	604-07894 CURB RAMP, CONCRETE, A	33.000	SYS
49	604-07897 CURB RAMP, CONCRETE, C	44.000	SYS

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
50	604-07898 CURB RAMP, CONCRETE, D	14.000	SYS
51	604-07900 CURB RAMP, CONCRETE, F	15.000	SYS
52	604-07901 CURB RAMP, CONCRETE, G	77.000	SYS
53	604-07902 CURB RAMP, CONCRETE, H	64.000	SYS
54	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	11,698.000	LFT
55	610-08446 PCCP FOR APPROACHES, 6 IN	1,496.900	SYS
56	610-09108 PCCP FOR APPROACHES, 9 IN	1,647.000	SYS
57	611-06497 MAILBOX ASSEMBLY, SINGLE	23.000	EACH
58	611-06498 MAILBOX ASSEMBLY, DOUBLE	3.000	EACH
59	615-06505 MONUMENT, B	10.000	EACH
60	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
61	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
62	621-06575 SODDING, NURSERY	3,282.000	SYS
63	621-06626 MULCHED SEEDING, D	15,464.000	SYS
64	628-09402 FIELD OFFICE, B	14.000	MOS
65	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	28.000	MOS
66	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	82.000	LFT
67	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	3,484.000	LFT
68	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,235.000	LFT
69	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	401.000	LFT
70	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	608.000	LFT
71	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	750.000	LFT
72	715-05155 PIPE, TYPE 2 CIRCULAR 27 IN	255.000	LFT
73	715-06696 PIPE, PVC, 10 IN	15.000	LFT
74	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	239.900	TON
75	715-09475 STORMWATER QUALITY STRUCTURE	1.000	EACH
76	715-46000 PIPE END SECTION, DIA 12"	10.000	EACH
77	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
78	715-46010 PIPE END SECTION, DIA 18"	1.000	EACH
79	715-46025 PIPE END SECTION, DIA 27"	1.000	EACH
80	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
81	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
82	720-44000 CASTING, ADJUST TO GRADE	14.000	EACH
83	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	7.000	EACH
84	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
85	720-44296 INLET, CAP	4.000	EACH
86	720-45030 INLET, E7	3.000	EACH
87	720-45035 INLET, F7	7.000	EACH
88	720-45045 INLET, J10	38.000	EACH
89	720-45055 INLET, M10	44.000	EACH
90	720-45270 PIPE CATCH BASIN, 18 IN	23.000	EACH
91	720-45410 MANHOLE, C4	21.000	EACH
92	720-45425 MANHOLE, F4	1.000	EACH
93	720-90984 MANHOLE, C2	4.000	EACH
94	720-91973 MANHOLE, H4	3.000	EACH
95	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
96	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	11,550.000	LFT
97	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	47.000	LFT
98	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
99	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
100	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
101	801-07118 BARRICADE, III-A	534.000	LFT
102	801-07119 BARRICADE, III-B	72.000	LFT
103	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	16.000	LFT
104	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	450.500	LFT
105	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	4.000	EACH
106	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	33.000	EACH
107	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	256.750	SFT
108	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	167.000	SFT
109	802-76235 INSTALL OVERHEAD SIGN	8.000	EACH
110	805-01842 HANDHOLE, SIGNAL	3.000	EACH
111	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	350.000	LFT
112	805-02065 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 7 FT	2.000	EACH
113	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	4.000	EACH
114	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	6.000	EACH
115	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
116	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	3.000	EACH
117	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12"	5.000	EACH
118	805-78370 PEDESTRIAN PUSH BUTTON	4.000	EACH
119	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
120	805-78420 DISCONNECT HANGER	4.000	EACH
121	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,230.000	LFT
122	805-78485 SIGNAL CABLE, 5C/14GA	1,730.000	LFT
123	805-78490 SIGNAL CABLE, 7C/14GA	820.000	LFT
124	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	3,370.000	LFT
125	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
126	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	380.000	LFT
127	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
128	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	2.000	EACH
129	807-01603 SERVICE POINT, TYPE II	2.000	EACH
130	807-01878 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	32.000	EACH
131	807-02191 HANDHOLE, LIGHTING	6.000	EACH
132	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	32.000	EACH
133	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,151.000	LFT
134	807-83752 LIGHT POLE, 40FT E.M.H., 10FT MAST ARM, ANCHOR BASE	32.000	EACH
135	807-86805 SERVICE POINT, I	6.000	EACH
136	807-86955 CABLE-DUCT MARKER	6.000	EACH
137	807-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	9,085.000	LFT
138	808-03439 TRANSVERSE MARKING THERMOPLASTIC	220.000	LFT
139	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,835.000	LFT
140	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
141	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,860.000	LFT
142	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	17,233.000	LFT
143	808-75274 TRANSVERSE MARKING, THERMOPLASTIC,	342.000	LFT
144	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	346.000	LFT
145	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	705.000	LFT
146	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	30.000	EACH
147	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	6.000	EACH

SCHEDULE OF PAY ITEMS

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
148 805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH