

CALL ORDER : 120

CONTRACT ID : R -29082-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02271 HEADWALL, REMOVE	4.000	EACH
11	203-02000 EXCAVATION, COMMON	300.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	18.000	TON
13	205-06937 TEMPORARY SILT FENCE	74.000	LFT
14	206-51220 EXCAVATION, WET	63.000	CYS
15	207-09935 SUBGRADE TREATMENT, TYPE 1C	414.400	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	21.100	CYS
17	211-09265 STRUCTURAL BACKFILL, TYPE 2	70.700	CYS
18	211-09268 STRUCTURAL BACKFILL, TYPE 5	81.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	230.500	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	40.200	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN	605.300	SYS
22	402-07434 HMA SURFACE, TYPE C	84.100	TON
23	402-07439 HMA INTERMEDIATE, TYPE C	57.000	TON
24	402-07442 HMA BASE, TYPE C	17.600	TON
25	406-05520 ASPHALT FOR TACK COAT	0.300	TON
26	601-01701 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
27	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
28	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
30	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
31	615-06490 RIGHT OF WAY MARKER	8.000	EACH
32	615-06505 MONUMENT, B	2.000	EACH
33	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
34	615-06530 BENCH MARK POST	1.000	EACH
35	616-02320 GEOTEXTILES	101.800	SYS
36	616-06405 RIPRAP, REVETMENT	51.400	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
38	621-06545 FERTILIZER	0.100	TON
39	621-06553 SEED MIXTURE, R	46.000	LBS
40	621-06557 SEED MIXTURE, T	40.000	LBS
41	621-06565 MULCHING MATERIAL	0.500	TON
42	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
43	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	3.000	MOS
44	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
45	714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	50.000	LFT
46	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	43.000	LFT
47	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	44.000	LFT
48	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
49	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH

CALL ORDER : 120

CONTRACT ID : R -29082-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
51	801-06625 DETOUR ROUTE MARKER ASSEMBLY	54.000	EACH
52	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
53	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
54	801-07118 BARRICADE, III-A	48.000	LFT
55	801-07119 BARRICADE, III-B	48.000	LFT
56	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	32.000	LFT
57	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	12.000	SFT
58	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	494.000	LFT
59	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	61.700	LFT

CALL ORDER : 170

CONTRACT ID : R -30497-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	9,530.000	SYS
14	202-93741 GUARDRAIL END TREATMENT, REMOVE	8.000	EACH
15	202-96133 PIPE, REMOVE	82.000	LFT
16	203-02000 EXCAVATION, COMMON	7,606.000	CYS
17	203-08607 LINEAR GRADING	300.000	LFT
18	205-03371 SEDIMENT, REMOVE	508.000	CYS
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	19.000	TON
20	205-06932 TEMPORARY CHECK DAM, STRAW BALES	600.000	LFT
21	205-06933 TEMPORARY INLET PROTECTION	3.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	94.000	TON
23	205-06937 TEMPORARY SILT FENCE	800.000	LFT
24	205-09543 NO 2 STONE	100.000	TON
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	110.000	SYS
26	207-09935 SUBGRADE TREATMENT, TYPE 1C	29,670.000	SYS
27	211-09265 STRUCTURAL BACKFILL, TYPE 2	69.000	CYS
28	211-09268 STRUCTURAL BACKFILL, TYPE 5	107.000	CYS
29	303-01180 COMPACTED AGGREGATE, NO. 53	1,271.000	TON
30	304-07783 HMA PATCHING, TYPE D	400.000	TON
31	306-08034 MILLING, ASPHALT, 1 1/2 IN	37,200.000	SYS
32	306-08036 MILLING, ASPHALT, 2 IN	1,050.000	SYS
33	306-08432 MILLING, APPROACH	15,200.000	SYS
34	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
35	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	5,805.000	TON
36	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	5,034.000	TON
37	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	9,128.000	TON
38	401-10258 JOINT ADHESIVE, SURFACE	22,000.000	LFT
39	406-05520 ASPHALT FOR TACK COAT	40.300	TON
40	412-09355 FOG SEAL	4,900.000	SYS
41	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
42	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	4.000	EACH
43	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
44	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	3.000	EACH
45	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
46	601-95300 CONNECTOR, A S	4.000	EACH
47	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	275.000	LFT
48	606-09729 MILLED CENTERLINE CORRUGATIONS	22,000.000	LFT
49	610-07487 HMA FOR APPROACHES, TYPE B	77.000	TON

CALL ORDER : 170

CONTRACT ID : R -30497-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	610-07788 HMA FOR APPROACHES, TYPE D	2,300.000	TON
51	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
52	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	17.100	TON
53	612-60410 DRILLED HOLE FOR UNDERSEAL	288.000	EACH
54	615-06490 RIGHT OF WAY MARKER	17.000	EACH
55	615-06505 MONUMENT, B	2.000	EACH
56	615-06527 MONUMENT, SECTION CORNER	7.000	EACH
57	616-02320 GEOTEXTILES	498.000	SYS
58	616-05688 RIPRAP, CLASS 1	179.000	TON
59	616-06405 RIPRAP, REVETMENT	42.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
61	621-02356 SEEDING, WETLAND	1.000	LBS
62	621-06559 MULCHED SEEDING, R	2,726.000	SYS
63	621-06560 MULCHED SEEDING, U	519.000	SYS
64	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
65	628-09402 FIELD OFFICE, B	6.000	MOS
66	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
67	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
68	714-11634 STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS,	52.000	LFT
69	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	140.000	LFT
70	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	52.000	LFT
71	715-06357 CONCRETE ANCHOR, 72 IN	1.000	EACH
72	715-11325 PIPE, TYPE 3, CIRCULAR, 72 IN.	38.000	LFT
73	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
74	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
75	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
77	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	8,400.000	LFT
78	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,200.000	LFT
79	801-06625 DETOUR ROUTE MARKER ASSEMBLY	54.000	EACH
80	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
82	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
83	801-07118 BARRICADE, III-A	96.000	LFT
84	801-07119 BARRICADE, III-B	72.000	LFT
85	802-04089 SIGN, SHEET, REMOVE	2.000	EACH
86	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	21.000	LFT
87	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
88	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	15.000	SFT
89	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,900.000	LFT
90	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	800.000	LFT
91	808-06716 LINE, REMOVE	77,633.000	LFT
92	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
93	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	43,714.000	LFT
94	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	10,421.000	LFT
95	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	19,315.000	LFT
96	808-10099 TRANSVERSE MARKINGS, MULTI-COMPONENT,	50.000	LFT
97	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	397.000	EACH

CALL ORDER : 180

CONTRACT ID : R -31407-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01261 TESTING FOR ASBESTOS	10.000	EACH
12	202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE	45.000	CYS
13	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
14	202-91385 INLET, REMOVE	15.000	EACH
15	202-92222 TESTING FOR CONTAMINATED MATERIALS,	1.000	EACH
16	202-96133 PIPE, REMOVE	2,335.000	LFT
17	203-02000 EXCAVATION, COMMON	13,790.000	CYS
18	203-02070 BORROW	3,729.000	CYS
19	205-03371 SEDIMENT, REMOVE	50.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	104.000	TON
21	205-06933 TEMPORARY INLET PROTECTION	11.000	EACH
22	205-06937 TEMPORARY SILT FENCE	8,579.000	LFT
23	205-09543 NO 2 STONE	100.000	TON
24	207-08263 SUBGRADE TREATMENT, TYPE IA	33,108.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,028.000	SYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	5,716.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,452.000	TON
28	303-01180 COMPACTED AGGREGATE, NO. 53	197.000	TON
29	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	124.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	161.000	SYS
31	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,877.000	TON
32	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,127.000	TON
33	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	3,669.000	TON
34	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	3,633.000	TON
35	401-10258 JOINT ADHESIVE, SURFACE	14,400.000	LFT
36	401-10259 JOINT ADHESIVE, INTERMEDIATE	14,400.000	LFT
37	402-07432 HMA SURFACE, TYPE A	14.000	TON
38	406-05520 ASPHALT FOR TACK COAT	18.000	TON
39	415-11527 BASE SEAL	19.000	TON
40	604-06070 SIDEWALK, CONCRETE	4,353.000	SYS
41	604-07901 CURB RAMP, CONCRETE, G	117.000	SYS
42	604-07902 CURB RAMP, CONCRETE, H	9.000	SYS
43	604-95344 HAND RAIL, PEDESTRIAN	142.000	LFT
44	605-06125 CURB, CONCRETE, MODIFIED	152.000	LFT
45	605-06140 CURB AND GUTTER, CONCRETE	9,472.000	LFT
46	610-07486 HMA FOR APPROACHES, TYPE A	393.000	TON
47	610-07487 HMA FOR APPROACHES, TYPE B	249.000	TON
48	610-08446 PCCP FOR APPROACHES, 6 IN	1,773.000	SYS
49	610-09108 PCCP FOR APPROACHES, 9 IN	544.000	SYS

CALL ORDER : 180

CONTRACT ID : R -31407-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	611-06497 MAILBOX ASSEMBLY, SINGLE	14.000	EACH
51	611-06498 MAILBOX ASSEMBLY, DOUBLE	28.000	EACH
52	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
53	615-06505 MONUMENT, B	6.000	EACH
54	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
55	616-02320 GEOTEXTILES	4,886.000	SYS
56	616-06405 RIPRAP, REVETMENT	4,461.000	TON
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
58	621-02770 EROSION CONTROL BLANKET	1,207.000	SYS
59	621-06545 FERTILIZER	1.500	TON
60	621-06554 SEED MIXTURE, U	488.000	LBS
61	621-06557 SEED MIXTURE, T	488.000	LBS
62	621-06565 MULCHING MATERIAL	10.000	TON
63	621-06567 WATER	44.000	kgAL
64	621-06575 SODDING, NURSERY	10,890.000	SYS
65	628-09402 FIELD OFFICE, B	16.000	MOS
66	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	16.000	MOS
67	702-90915 CONCRETE, CLASS A	33.000	CYS
68	703-06028 REINFORCING BARS	624.000	LBS
69	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	619.000	LFT
70	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	8,879.000	LFT
71	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	100.000	LFT
72	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,141.000	LFT
73	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	700.000	LFT
74	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	438.000	LFT
75	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,697.000	LFT
76	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	1,393.000	LFT
77	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	305.000	LFT
78	715-05209 PIPE, TYPE 4 CIRCULAR 18 IN	53.000	LFT
79	715-05233 PIPE, TYPE 1 DEFORMED MIN AREA 3.3 SFT	173.000	LFT
80	715-05234 PIPE, TYPE 1 DEFORMED MIN AREA 4.1 SFT	108.000	LFT
81	715-05237 PIPE, TYPE 1 DEFORMED MIN AREA 6.4 SFT	91.000	LFT
82	715-05331 PIPE, TYPE 2 DEFORMED MIN AREA 3.3 SFT	504.000	LFT
83	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	4.000	EACH
84	715-08181 PIPE END SECTION, MIN AREA 4.1 SFT	2.000	EACH
85	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	49.000	TON
86	715-09064 VIDEO INSPECTION FOR PIPE	6,754.000	LFT
87	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
88	715-46005 PIPE END SECTION, DIA 15"	23.000	EACH
89	715-46030 PIPE END SECTION, DIA 30"	1.000	EACH
90	715-46040 PIPE END SECTION, DIA 36 IN	1.000	EACH
91	715-46095 PIPE END SECTION, MIN AREA 6.4 SFT	2.000	EACH
92	718-06528 OUTLET PROTECTOR, 1	4.000	EACH
93	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
94	718-52610 AGGREGATE FOR UNDERDRAINS	704.000	CYS
95	718-99153 GEOTEXTILES FOR UNDERDRAIN	6,083.000	SYS
96	720-08617 INLET, INTAKE RISER	2.000	EACH
97	720-45030 INLET, E7	8.000	EACH
98	720-45035 INLET, F7	2.000	EACH

CALL ORDER : 180

CONTRACT ID : R -31407-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99	720-45410 MANHOLE, C4	14.000	EACH
100	720-95422 MANHOLE, J4	16.000	EACH
101	720-98174 INLET, B15	22.000	EACH
102	720-98555 INLET, C15	1.000	EACH
103	720-99417 CATCH BASIN, C15	23.000	EACH
104	721-43000 AUTOMATIC DRAINAGE GATE, 12 IN	2.000	EACH
105	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
106	801-04308 ROAD CLOSURE SIGN ASSEMBLY	18.000	EACH
107	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	4,805.000	LFT
108	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8,515.000	LFT
109	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	1.000	EACH
110	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	1.000	EACH
111	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	28.000	LFT
112	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
113	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
114	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
115	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
116	801-07118 BARRICADE, III-A	444.000	LFT
117	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	323.000	LFT
118	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	184.000	SFT
119	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	58.000	SFT
120	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	42.000	SFT
121	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
122	805-01842 HANDHOLE, SIGNAL	7.000	EACH
123	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	497.000	LFT
124	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
125	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
126	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
127	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
128	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
129	805-78420 DISCONNECT HANGER	4.000	EACH
130	805-78445 SIGNAL SERVICE	1.000	EACH
131	805-78467 SIGNAL CABLE, 3C/8GA	60.000	LFT
132	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	5,400.000	LFT
133	805-78480 SIGNAL CABLE, 3C/14GA	1,142.000	LFT
134	805-78485 SIGNAL CABLE, 5C/14GA	885.000	LFT
135	805-78490 SIGNAL CABLE, 7C/14GA	486.000	LFT
136	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	1,579.000	LFT
137	805-78785 SIGNAL DETECTOR HOUSING	9.000	EACH
138	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,800.000	LFT
139	805-78900 PEDESTAL FOUNDATION, A	2.000	EACH
140	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	1.000	EACH
141	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
142	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	1.000	EACH
143	805-90005 SIGNAL PEDESTAL, 10 FT	2.000	EACH
144	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	5.000	EACH
145	807-01878 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	23.000	EACH
146	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	23.000	EACH
147	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	524.000	LFT

CALL ORDER : 180

CONTRACT ID : R -31407-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
148	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	3,876.000	LFT
149	807-84762 LIGHT POLE, 40 FT E.M.H., 15.0 FT MAST ARM, TRANSFORMER BASE	23.000	EACH
150	807-86615 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	23.000	EACH
151	807-86810 SERVICE POINT, II	1.000	EACH
152	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	1,968.000	LFT
153	807-86905 TRANSITION FITTINGS, GALVANIZED STEEL CONDUIT TO PLASTIC	34.000	EACH
154	807-86910 CONNECTOR KIT, UNFUSED	23.000	EACH
155	807-86915 CONNECTOR KIT, FUSED	23.000	EACH
156	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	63.000	EACH
157	807-86930 INSULATION LINK, NON-WATERPROOFED	46.000	EACH
158	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	524.000	LFT
159	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.000	LFT
160	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,809.000	LFT
161	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	7,838.000	LFT
162	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	149.000	LFT
163	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	257.000	LFT
164	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,379.000	LFT
165	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	26.000	EACH
166	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	26.000	EACH
167	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	118.000	EACH
168	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	348.000	LFT



CALL ORDER : 210

CONTRACT ID : R -31722-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01261 TESTING FOR ASBESTOS	2.000	EACH
13	202-02240 PAVEMENT REMOVAL	320.000	SYS
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
16	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	52,715.000	CYS
19	203-02070 BORROW	67,768.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	334.000	TON
21	205-06933 TEMPORARY INLET PROTECTION	32.000	EACH
22	205-06934 TEMPORARY MULCH	162.000	TON
23	205-06935 TEMPORARY SEDIMENT BASIN	4.000	EACH
24	205-06936 TEMPORARY SEDIMENT TRAP	445.000	TON
25	205-06937 TEMPORARY SILT FENCE	3,640.000	LFT
26	205-09543 NO 2 STONE	100.000	TON
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,206.000	SYS
28	207-09934 SUBGRADE TREATMENT, TYPE 1B	52,461.000	SYS
29	211-02050 B BORROW	4,135.000	CYS
30	211-06467 AGGREGATE FOR END BENT BACKFILL	93.000	CYS
31	211-09264 STRUCTURAL BACKFILL, TYPE 1	969.000	CYS
32	211-09265 STRUCTURAL BACKFILL, TYPE 2	235.000	CYS
33	215-07043 CHEMICAL MODIFICATION, SOILS	11,000.000	SYS
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,207.000	TON
35	302-07455 DENSE GRADED SUBBASE	74.400	CYS
36	303-01180 COMPACTED AGGREGATE, NO. 53	1,077.000	TON
37	303-07449 COMPACTED AGGREGATE, NO. 73	16.000	TON
38	306-08043 MILLING, TRANSITION	693.000	SYS
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3,721.000	TON
41	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	7,469.000	TON
42	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	7,433.000	TON
43	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,858.000	TON
44	401-10258 JOINT ADHESIVE, SURFACE	30,217.000	LFT
45	401-10259 JOINT ADHESIVE, INTERMEDIATE	30,217.000	LFT
46	402-07432 HMA SURFACE, TYPE A	222.000	TON
47	402-07435 HMA INTERMEDIATE, TYPE A	373.000	TON
48	402-07441 HMA BASE, TYPE B	139.000	TON
49	402-07451 HMA WEDGE AND LEVEL, TYPE B	35.000	TON

CALL ORDER : 210

CONTRACT ID : R -31722-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	406-05520 ASPHALT FOR TACK COAT	24.000	TON
51	415-11527 BASE SEAL	45.000	TON
52	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
53	601-02241 GUARDRAIL, REMOVE	581.000	LFT
54	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
55	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	50.000	LFT
56	602-06729 BARRIER DELINEATOR	4.000	EACH
57	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	8,175.000	LFT
58	607-06175 GUTTER, CONCRETE, A	154.000	LFT
59	607-06335 PAVED SIDE DITCH, A	354.000	LFT
60	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	483.000	SYS
61	610-07487 HMA FOR APPROACHES, TYPE B	94.000	TON
62	610-08446 PCCP FOR APPROACHES, 6 IN	945.000	SYS
63	610-09108 PCCP FOR APPROACHES, 9 IN	253.000	SYS
64	611-06497 MAILBOX ASSEMBLY, SINGLE	14.000	EACH
65	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
66	615-06490 RIGHT OF WAY MARKER	60.000	EACH
67	615-06505 MONUMENT, B	8.000	EACH
68	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
69	615-06530 BENCH MARK POST	1.000	EACH
70	616-02320 GEOTEXTILES	4,913.300	SYS
71	616-05688 RIPRAP, CLASS 1	946.000	TON
72	616-06405 RIPRAP, REVETMENT	1,962.600	TON
73	616-07210 FIBER ROLL	490.000	LFT
74	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
75	621-02770 EROSION CONTROL BLANKET	35,175.000	SYS
76	621-06545 FERTILIZER	14.000	TON
77	621-06553 SEED MIXTURE, R	5,508.000	LBS
78	621-06557 SEED MIXTURE, T	9,720.000	LBS
79	621-06565 MULCHING MATERIAL	65.000	TON
80	621-06567 WATER	83.000	KGAL
81	621-06574 SODDING	8,936.000	SYS
82	621-06575 SODDING, NURSERY	11,793.000	SYS
83	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
84	628-09402 FIELD OFFICE, B	24.000	MOS
85	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	48.000	MOS
86	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	48.000	MOS
87	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
88	701-06011 DYNAMIC PILE LOAD TEST	1.000	EACH
89	701-09557 TEST PILE, DYNAMIC, PRODUCTION	46.000	LFT
90	701-09559 TEST PILE, DYNAMIC, RESTRIKE	1.000	EACH
91	701-09739 PILE SHOE, HP 12 X 53	8.000	EACH
92	701-51195 PILE, STEEL H, HP 12 IN X 53	252.000	LFT
93	702-90915 CONCRETE, CLASS A	1.000	CYS
94	703-06028 REINFORCING BARS	54.000	LBS
95	703-06029 REINFORCING BARS, EPOXY COATED	84,995.000	LBS
96	704-09031 ARTICULATING CONCRETE MATTRESS	208.000	SYS
97	704-51002 CONCRETE, C, SUPERSTRUCTURE	247.600	CYS
98	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH

CALL ORDER : 210

CONTRACT ID : R -31722-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
99	706-51020 RAILING, CONCRETE, C	13.000	CYS
100	707-11428 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 33 IN X 48 IN	474.000	LFT
101	709-51821 SURFACE SEAL	LUMP	LUMP
102	714-11414 STRUCTURE, COATED REINFORCED CONCRETE,	42.000	LFT
103	714-11654 STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS,	36.000	LFT
104	715-04555 PIPE END SECTION, MIN AREA 5.1 SFT	1.000	EACH
105	715-04611 SAFETY METAL END SECTION 4:1 DIA 12"	1.000	EACH
106	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	122.000	LFT
107	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	19,711.000	LFT
108	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	50.000	LFT
109	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	50.000	LFT
110	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	1,749.000	LFT
111	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	193.000	LFT
112	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	955.000	LFT
113	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	459.000	LFT
114	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	680.000	LFT
115	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	207.000	LFT
116	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	122.000	LFT
117	715-05175 PIPE, TYPE 3 CIRCULAR 30 IN	93.000	LFT
118	715-05177 PIPE, TYPE 3 CIRCULAR 36 IN	160.000	LFT
119	715-05188 PIPE, TYPE 3 CIRCULAR 60 IN	66.000	LFT
120	715-05335 PIPE, TYPE 2 DEFORMED MIN AREA 5.1 SFT	411.000	LFT
121	715-05407 PIPE, END BENT DRAIN, 6 IN	182.000	LFT
122	715-05841 CONCRETE ANCHOR 60 IN	2.000	EACH
123	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	6.000	EACH
124	715-07536 CONCRETE ANCHOR MIN AREA 12.9 SFT	4.000	EACH
125	715-08243 PIPE, TYPE 3 DEFORMED MIN AREA 3.3 SFT	118.000	LFT
126	715-09064 VIDEO INSPECTION FOR PIPE	3,190.000	LFT
127	715-11528 PIPE, TYPE 3, DEFORMED, MIN. AREA 12.9 SFT.	112.000	LFT
128	715-46005 PIPE END SECTION, DIA 15"	8.000	EACH
129	715-46030 PIPE END SECTION, DIA 30"	6.000	EACH
130	715-46040 PIPE END SECTION, DIA 36 IN	8.000	EACH
131	718-06529 OUTLET PROTECTOR, 2	20.000	EACH
132	718-06531 OUTLET PROTECTOR, 3	6.000	EACH
133	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
134	718-52610 AGGREGATE FOR UNDERDRAINS	1,663.000	CYS
135	718-99153 GEOTEXTILES FOR UNDERDRAIN	18,777.000	SYS
136	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	50.000	LFT
137	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	50.000	LFT
138	719-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN	50.000	LFT
139	720-04682 INLET	3.000	EACH
140	720-45035 INLET, F7	1.000	EACH
141	720-45405 MANHOLE, B4	2.000	EACH
142	720-92025 MANHOLE, D2	3.000	EACH
143	720-98174 INLET, B15	9.000	EACH
144	720-98555 INLET, C15	14.000	EACH
145	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
146	801-04308 ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
147	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,000.000	LFT

CALL ORDER : 210

CONTRACT ID : R -31722-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
148	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	500.000	LFT
149	801-06625 DETOUR ROUTE MARKER ASSEMBLY	32.000	EACH
150	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
151	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
152	801-07119 BARRICADE, III-B	240.000	LFT
153	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	209.000	LFT
154	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	24.000	EACH
155	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	116.000	SFT
156	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	10.000	SFT
157	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	19,135.000	LFT
158	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	268.000	LFT
159	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	30.000	LFT
160	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,760.000	LFT
161	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,498.000	LFT
162	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	844.000	LFT
163	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	148.000	LFT
164	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
165	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
166	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	4,326.000	LFT

CALL ORDER : 230

CONTRACT ID : R -33351-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	460.000	SYS
12	202-91385 INLET, REMOVE	2.000	EACH
13	202-93047 MANHOLE, REMOVE	1.000	EACH
14	202-96133 PIPE, REMOVE	364.000	LFT
15	203-02000 EXCAVATION, COMMON	555.000	CYS
16	205-03371 SEDIMENT, REMOVE	11.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	28.000	TON
18	205-06933 TEMPORARY INLET PROTECTION	5.000	EACH
19	205-06936 TEMPORARY SEDIMENT TRAP	93.000	TON
20	205-06937 TEMPORARY SILT FENCE	398.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	100.000	SYS
23	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,040.000	SYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	87.000	CYS
25	211-09265 STRUCTURAL BACKFILL, TYPE 2	52.000	CYS
26	211-09268 STRUCTURAL BACKFILL, TYPE 5	140.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	250.000	TON
28	306-08036 MILLING, ASPHALT, 2 IN	420.000	SYS
29	306-08043 MILLING, TRANSITION	700.000	SYS
30	402-07434 HMA SURFACE, TYPE C	168.000	TON
31	402-07439 HMA INTERMEDIATE, TYPE C	228.000	TON
32	402-07442 HMA BASE, TYPE C	240.000	TON
33	406-05521 ASPHALT FOR TACK COAT	4,380.000	SYS
34	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
35	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
36	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
38	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	125.000	LFT
39	604-92237 HAND RAIL, STEEL	58.000	LFT
40	610-07487 HMA FOR APPROACHES, TYPE B	27.000	TON
41	615-06490 RIGHT OF WAY MARKER	17.000	EACH
42	615-06500 MONUMENT, A	4.000	EACH
43	616-02320 GEOTEXTILES	489.000	SYS
44	616-05688 RIPRAP, CLASS 1	125.000	TON
45	616-06405 RIPRAP, REVETMENT	93.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
47	621-06560 MULCHED SEEDING, U	1,147.000	SYS
48	621-06567 WATER	15.000	KGAL
49	621-06575 SODDING, NURSERY	257.000	SYS

CALL ORDER : 230

CONTRACT ID : R -33351-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	714-11087 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	48.000	LFT
51	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	221.000	LFT
52	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	30.000	LFT
53	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
54	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
55	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
56	720-97865 MANHOLE, C2, MODIFIED	3.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	33.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	96.000	LFT
62	801-07119 BARRICADE, III-B	96.000	LFT
63	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	10.000	LFT
64	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	5.000	SFT
65	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,070.000	LFT
66	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	134.000	LFT
67	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.000	EACH
68	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	7.000	EACH

CALL ORDER : 270

CONTRACT ID : R -33790-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
6	201-02255 TREE, 18 IN, REMOVE	3.000	EACH
7	201-02260 TREE, 30 IN, REMOVE	3.000	EACH
8	202-02240 PAVEMENT REMOVAL	320.000	SYS
9	202-02278 CURB, CONCRETE, REMOVE	85.000	LFT
10	202-02928 CATCH BASIN, REMOVE	2.000	EACH
11	202-03875 CONCRETE STEPS, REMOVE	7.000	EACH
12	202-06542 RELOCATE	1.000	EACH
13	202-52710 SIDEWALK, CONCRETE, REMOVE	350.000	SYS
14	202-91922 STUMP, REMOVE	1.000	EACH
15	202-96133 PIPE, REMOVE	33.000	LFT
16	203-08607 LINEAR GRADING	35.000	LFT
17	203-09937 SLOPE	LUMP	LUMP
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	75.000	CYS
19	303-01180 COMPACTED AGGREGATE, NO. 53	50.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	25.000	TON
21	304-07490 HMA PATCHING, TYPE B	88.000	TON
22	603-03398 FENCE, RELOCATE	24.000	LFT
23	604-06070 SIDEWALK, CONCRETE	1,616.000	SYS
24	604-07896 CURB RAMP, CONCRETE, B	8.000	SYS
25	604-07897 CURB RAMP, CONCRETE, C	8.000	SYS
26	604-07899 CURB RAMP, CONCRETE, E	4.000	SYS
27	604-07901 CURB RAMP, CONCRETE, G	21.000	SYS
28	604-07902 CURB RAMP, CONCRETE, H	39.000	SYS
29	604-07903 CURB RAMP, CONCRETE, K	5.000	SYS
30	605-06120 CURB, CONCRETE	2,549.000	LFT
31	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	5.000	EACH
32	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
33	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
34	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	36.000	LFT
35	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
36	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
37	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
38	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
39	720-92240 CATCH BASIN, W4	2.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	802-07060 SIGN, SHEET, RELOCATE	8.000	EACH
42	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	77.000	SFT
43	802-76055 SIGN POST, A	988.000	LFT
44	805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY	4.000	EACH
45	808-03439 TRANSVERSE MARKING THERMOPLASTIC	816.000	LFT
46	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	3.000	EACH

CALL ORDER : 310

CONTRACT ID : R -34119-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	247.000	LFT
12	203-02000 EXCAVATION, COMMON	1,068.000	CYS
13	205-03371 SEDIMENT, REMOVE	12.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	37.000	TON
15	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
16	205-06936 TEMPORARY SEDIMENT TRAP	125.000	TON
17	205-06937 TEMPORARY SILT FENCE	500.000	LFT
18	205-09543 NO 2 STONE	100.000	TON
19	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,109.000	SYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	35.000	CYS
21	211-09265 STRUCTURAL BACKFILL, TYPE 2	337.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	310.000	TON
23	303-01180 COMPACTED AGGREGATE, NO. 53	360.000	TON
24	306-08036 MILLING, ASPHALT, 2 IN	940.000	SYS
25	306-08043 MILLING, TRANSITION	860.000	SYS
26	402-07433 HMA SURFACE, TYPE B	230.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	335.000	TON
28	406-05521 ASPHALT FOR TACK COAT	3,750.000	SYS
29	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
30	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
31	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
33	615-06490 RIGHT OF WAY MARKER	14.000	EACH
34	615-06505 MONUMENT, B	2.000	EACH
35	616-02320 GEOTEXTILES	409.000	SYS
36	616-05688 RIPRAP, CLASS 1	154.000	TON
37	616-06405 RIPRAP, REVETMENT	14.000	TON
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-02770 EROSION CONTROL BLANKET	137.000	SYS
40	621-03909 SEED MIXTURE, NATIVE	5.000	LBS
41	621-06559 MULCHED SEEDING, R	1,950.000	SYS
42	621-06567 WATER	25.000	KGAL
43	621-06574 SODDING	430.000	SYS
44	628-09402 FIELD OFFICE, B	3.000	MOS
45	714-11183 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	76.000	LFT
46	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	42.000	LFT
47	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	166.000	LFT
48	715-46005 PIPE END SECTION, DIA 15"	7.000	EACH
49	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH



CALL ORDER : 310

CONTRACT ID : R -34119-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	801-06625 DETOUR ROUTE MARKER ASSEMBLY	32.000	EACH
51	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-07118 BARRICADE, III-A	96.000	LFT
54	801-07119 BARRICADE, III-B	96.000	LFT
55	802-04893 REFERENCE POST	1.000	EACH
56	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	11.000	LFT
57	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
58	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,425.000	LFT
59	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	160.000	LFT
60	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	9.000	EACH

CALL ORDER : 320

CONTRACT ID : R -34122-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	30.000	LFT
12	203-02000 EXCAVATION, COMMON	734.000	CYS
13	205-03371 SEDIMENT, REMOVE	6.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	9.000	TON
15	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
16	205-06936 TEMPORARY SEDIMENT TRAP	32.000	TON
17	205-06937 TEMPORARY SILT FENCE	230.000	LFT
18	205-09543 NO 2 STONE	100.000	TON
19	207-08265 SUBGRADE TREATMENT, TYPE IIA	800.000	SYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	30.000	CYS
21	211-09265 STRUCTURAL BACKFILL, TYPE 2	241.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	229.000	TON
23	303-01180 COMPACTED AGGREGATE, NO. 53	873.000	TON
24	306-08036 MILLING, ASPHALT, 2 IN	420.000	SYS
25	306-08043 MILLING, TRANSITION	480.000	SYS
26	402-07433 HMA SURFACE, TYPE B	134.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	192.000	TON
28	406-05521 ASPHALT FOR TACK COAT	2,100.000	SYS
29	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
30	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
31	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	206.000	LFT
34	615-06490 RIGHT OF WAY MARKER	15.000	EACH
35	615-06505 MONUMENT, B	2.000	EACH
36	616-02320 GEOTEXTILES	574.000	SYS
37	616-05688 RIPRAP, CLASS 1	184.000	TON
38	616-06405 RIPRAP, REVETMENT	108.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
40	621-06559 MULCHED SEEDING, R	1,165.000	SYS
41	621-06567 WATER	15.000	KGAL
42	621-06574 SODDING	216.000	SYS
43	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
44	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
45	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
46	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
47	714-11178 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	76.000	LFT
48	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	99.000	LFT
49	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	26.000	LFT

CALL ORDER : 320

CONTRACT ID : R -34122-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	110.000	LFT
51	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
52	715-46010 PIPE END SECTION, DIA 18"	2.000	EACH
53	715-46020 PIPE END SECTION, DIA 24"	2.000	EACH
54	801-04308 ROAD CLOSURE SIGN ASSEMBLY	9.000	EACH
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	50.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	801-07118 BARRICADE, III-A	96.000	LFT
59	801-07119 BARRICADE, III-B	132.000	LFT
60	802-04089 SIGN, SHEET, REMOVE	1.000	EACH
61	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	11.000	LFT
62	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	6.000	SFT
63	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	960.000	LFT
64	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	120.000	LFT
65	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	6.000	EACH

CALL ORDER : 394

CONTRACT ID : R -35511-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTION AND PARK ROAD MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	306-08034 MILLING, ASPHALT, 1 1/2 IN	13,184.000	SYS
11	402-07432 HMA SURFACE, TYPE A	1,088.000	TON
12	406-05520 ASPHALT FOR TACK COAT	3.300	TON
13	615-97768 PARKING BARRIER, RESET	148.000	EACH
14	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
15	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	2.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	5,714.000	LFT
21	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN	331.000	LFT
22	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	5.000	EACH

CALL ORDER : 420

CONTRACT ID : R -35718-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DEMOLITION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-02255 TREE, 18 IN, REMOVE	1.000	EACH
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	45.000	SFT
12	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	100.000	LFT
13	205-06937 TEMPORARY SILT FENCE	157.000	LFT
14	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
15	621-06559 MULCHED SEEDING, R	3,000.000	SYS
16	801-03290 CONSTRUCTION SIGN, C	2.000	EACH

CALL ORDER : 460

CONTRACT ID : RS-34143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
13	203-02000 EXCAVATION, COMMON	71.000	CYS
14	205-09543 NO 2 STONE	858.000	TON
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	682.000	SYS
16	207-09935 SUBGRADE TREATMENT, TYPE 1C	4,482.000	SYS
17	211-09264 STRUCTURAL BACKFILL, TYPE 1	211.000	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	127.000	TON
19	302-07455 DENSE GRADED SUBBASE	747.000	CYS
20	303-07449 COMPACTED AGGREGATE, NO. 73	6,188.000	TON
21	304-07490 HMA PATCHING, TYPE B	200.000	TON
22	304-07491 HMA PATCHING, TYPE C	821.000	TON
23	304-07493 WIDENING WITH HMA, TYPE B	192.000	TON
24	304-07783 HMA PATCHING, TYPE D	14.000	TON
25	306-08033 MILLING, ASPHALT, 1 IN	12,777.000	SYS
26	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,788.000	SYS
27	306-08036 MILLING, ASPHALT, 2 IN	10,606.000	SYS
28	306-08042 MILLING, SCARIFICATION/PROFILE	162,159.000	SYS
29	306-08043 MILLING, TRANSITION	22,320.000	SYS
30	306-08599 MILLING ASPHALT, 1/2 IN	1,525.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	4,050.000	TON
33	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,054.000	TON
34	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	11,208.000	TON
35	401-07354 QC/QA-HMA, 5, 76, SURFACE, 12.5 mm	1,167.000	TON
36	401-07361 QC/QA-HMA, 2, 70, INTERMEDIATE, 9.5 mm	3,804.000	TON
37	401-07427 QC/QA-HMA, 2, 70, BASE, 19.0 mm	7,161.000	TON
38	401-10258 JOINT ADHESIVE, SURFACE	93,586.000	LFT
39	401-10259 JOINT ADHESIVE, INTERMEDIATE	84,162.000	LFT
40	401-11724 QC/QA-HMA, 5, 70, INTERMEDIATE, 25.0 mm	31,431.000	TON
41	406-05520 ASPHALT FOR TACK COAT	145.000	TON
42	412-09355 FOG SEAL	37,463.000	SYS
43	503-05240 D-1 CONTRACTION JOINT	907.000	LFT
44	506-06333 PCCP PATCHING, FULL DEPTH	4,482.000	SYS
45	601-02241 GUARDRAIL, REMOVE	2,328.000	LFT
46	601-06035 GUARDRAIL, RESET	33,523.000	LFT
47	601-91147 GUARDRAIL END TREATMENT, RESET	27.000	EACH
48	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,913.000	LFT
49	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	1,525.000	LFT

CALL ORDER : 460

CONTRACT ID : RS-34143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	601-99123 GUARDRAIL, TRANSITION, GP	3.000	EACH
51	606-07484 MILLED HMA SHOULDER CORRUGATIONS	92,980.000	LFT
52	610-07487 HMA FOR APPROACHES, TYPE B	232.000	TON
53	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	20.000	TON
54	612-60410 DRILLED HOLE FOR UNDERSEAL	405.000	EACH
55	616-02320 GEOTEXTILES	2,467.000	SYS
56	616-06451 RIPRAP, UNIFORM	2,244.000	TON
57	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
58	621-06559 MULCHED SEEDING, R	256.000	SYS
59	627-09331 SAFETY TERMINAL, TYPE TL-4	2.000	EACH
60	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
61	628-09402 FIELD OFFICE, B	8.000	MOS
62	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
63	628-11007 CELLULAR TELEPHONE/RADIO SERVICE, 750 MINUTES	48.000	MOS
64	628-11068 CELLULAR TELEPHONE/RADIO	6.000	EACH
65	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	3,890.000	LFT
66	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	43,999.000	LFT
67	718-06526 HMA FOR UNDERDRAINS	1,651.000	TON
68	718-06529 OUTLET PROTECTOR, 2	220.000	EACH
69	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	5,000.000	LFT
70	718-08308 UNDERDRAIN, PATCHING	4,600.000	LFT
71	718-52610 AGGREGATE FOR UNDERDRAINS	14,502.000	CYS
72	718-99153 GEOTEXTILES FOR UNDERDRAIN	17,685.000	SYS
73	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
74	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	6.000	EACH
75	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
76	801-03291 CONSTRUCTION SIGN, D	12.000	EACH
77	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	382,210.000	LFT
78	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN	12,031.000	LFT
79	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN	470.000	LFT
80	801-06640 CONSTRUCTION SIGN, A	82.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
82	801-06710 FLASHING ARROW SIGN	180.000	DAY
83	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
84	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	48.000	LFT
85	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	10.000	EACH
86	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	468.000	LFT
87	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	352.000	SFT
88	804-06740 DELINEATOR WITH POST, D2	4.000	EACH
89	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	12,411.000	LFT
90	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	49,863.000	LFT
91	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,700.000	LFT
92	808-06716 LINE, REMOVE	50,000.000	LFT
93	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
94	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	4,339.000	LFT
95	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	4,339.000	LFT
96	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	1,085.000	LFT
97	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	49,190.000	LFT
98	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	200.000	LFT

CALL ORDER : 460

CONTRACT ID : RS-34143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
99 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	48.000	LFT
100 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	470.000	LFT
101 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	11.000	EACH
102 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	795.000	EACH
103 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	795.000	EACH



CALL ORDER : 470

CONTRACT ID : RS-35615-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180 COMPACTED AGGREGATE, NO. 53	1,052.000	TON
11	306-08043 MILLING, TRANSITION	1,413.000	SYS
12	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
13	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	9,508.000	TON
14	401-09970 QC/QA-HMA, 2, 64, SURFACE, 4.75 mm	295.000	TON
15	401-10258 JOINT ADHESIVE, SURFACE	46,276.000	LFT
16	406-05520 ASPHALT FOR TACK COAT	34.000	TON
17	610-07487 HMA FOR APPROACHES, TYPE B	869.000	TON
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09403 FIELD OFFICE, C	6.000	MOS
20	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
21	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
22	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	12.000	MOS
23	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	11,185.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	54.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	9,519.000	LFT
28	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	89,838.000	LFT
29	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	23,917.000	LFT
30	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
31	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	39.000	LFT
32	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	73.000	LFT
33	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	634.000	EACH

CALL ORDER : 480

CONTRACT ID : RS-35628-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT, ULTRATHIN BONDED WEARING COURSE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-90277 DETECTOR HOUSING, REMOVE	4.000	EACH
10	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,100.000	SYS
11	306-08041 MILLING, PCCP	1,587.000	SYS
12	306-08043 MILLING, TRANSITION	1,436.000	SYS
13	412-09355 FOG SEAL	1,378.000	SYS
14	414-11469 ULTRATHIN BONDED WEARING COURSE, 12.5 mm	10,960.000	SYS
15	503-03489 RETROFITTED TIE BARS	275.000	EACH
16	503-05240 D-1 CONTRACTION JOINT	250.000	LFT
17	506-06333 PCCP PATCHING, FULL DEPTH	1,100.000	SYS
18	507-07479 HMA PARTIAL DEPTH PATCH	100.000	TON
19	507-07480 PROFILING PCCP	7,939.000	SYS
20	507-07482 CRACKS IN PCCP, ROUT AND SEAL	500.000	LFT
21	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
22	628-09401 FIELD OFFICE, A	6.000	MOS
23	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
24	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
25	720-01355 INLET, CLEAN EXISTING	5.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
27	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	857.000	LFT
28	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
29	801-06710 FLASHING ARROW SIGN	60.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	805-02328 SIGNAL CABLE, 1C/14 GA	1,400.000	LFT
32	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	500.000	LFT
34	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	8.500	SYS
35	808-06368 TRANSVERSE MARKING, REMOVE	80.000	LFT
36	808-06716 LINE, REMOVE	9,270.000	LFT
37	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	720.000	LFT
38	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	4,170.000	LFT
39	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	4,400.000	LFT
40	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	15.000	LFT
41	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	142.000	LFT
42	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	8.000	EACH
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	100.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	100.000	EACH

CALL ORDER : 530

CONTRACT ID : B -30492-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	10,322.000	CYS
13	203-02020 EXCAVATION, UNCLASSIFIED	190.000	CYS
14	203-02070 BORROW	68,598.000	CYS
15	205-06933 TEMPORARY INLET PROTECTION	3.000	EACH
16	205-06934 TEMPORARY MULCH	6.000	TON
17	205-06936 TEMPORARY SEDIMENT TRAP	50.000	TON
18	205-06937 TEMPORARY SILT FENCE	5,590.000	LFT
19	205-09543 NO 2 STONE	100.000	TON
20	207-08262 SUBGRADE TREATMENT, TYPE I	15,504.400	SYS
21	211-02050 B BORROW	13,205.000	CYS
22	211-09266 STRUCTURAL BACKFILL, TYPE 3	20,863.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,427.380	TON
24	302-07455 DENSE GRADED SUBBASE	48.000	CYS
25	306-08043 MILLING, TRANSITION	373.330	SYS
26	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	770.880	TON
27	401-07356 QC/QA-HMA, 2, 64, INTERMEDIATE, 9.5 mm	1,801.000	TON
28	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	2,590.500	TON
29	402-07433 HMA SURFACE, TYPE B	470.120	TON
30	402-07438 HMA INTERMEDIATE, TYPE B	1,121.680	TON
31	402-07441 HMA BASE, TYPE B	1,658.360	TON
32	406-05520 ASPHALT FOR TACK COAT	2.000	TON
33	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
34	601-02241 GUARDRAIL, REMOVE	2,900.000	LFT
35	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,550.000	LFT
37	602-06729 BARRIER DELINEATOR	20.000	EACH
38	607-06335 PAVED SIDE DITCH, A	1,977.410	LFT
39	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	263.100	SYS
40	615-06490 RIGHT OF WAY MARKER	15.000	EACH
41	615-06505 MONUMENT, B	2.000	EACH
42	616-02320 GEOTEXTILES	98.000	SYS
43	616-06405 RIPRAP, REVETMENT	110.000	TON
44	621-02770 EROSION CONTROL BLANKET	1,500.000	SYS
45	621-06545 FERTILIZER	5.200	TON
46	621-06553 SEED MIXTURE, R	2,210.000	LBS
47	621-06557 SEED MIXTURE, T	450.000	LBS
48	621-06565 MULCHING MATERIAL	26.000	TON
49	621-06567 WATER	251.600	KGAL

CALL ORDER : 530

CONTRACT ID : B -30492-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
51	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
52	628-09402 FIELD OFFICE, B	12.000	MOS
53	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	36.000	MOS
54	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
55	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
56	701-09557 TEST PILE, DYNAMIC, PRODUCTION	200.000	LFT
57	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
58	701-09663 PILE, STEEL PIPE, 0.312 IN, 14 IN	1,183.000	LFT
59	701-09679 CONICAL PILE TIP, 14 IN	14.000	EACH
60	701-11344 PILE, STEEL PIPE, 0.5", 16" DIA	2,319.000	LFT
61	701-11345 CONICAL PILE TIP, 16 IN.	28.000	EACH
62	702-51005 CONCRETE, A, SUBSTRUCTURE	187.200	CYS
63	702-51015 CONCRETE, B, FOOTINGS	75.000	CYS
64	703-06028 REINFORCING BARS	45,558.000	LBS
65	703-06029 REINFORCING BARS, EPOXY COATED	126,516.000	LBS
66	704-51002 CONCRETE, C, SUPERSTRUCTURE	485.500	CYS
67	706-11455 BRIDGE RAILING PEDESTRIAN FENCE	560.000	LFT
68	706-11600 RAILING, CONCRETE, FC	54.500	CYS
69	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
70	707-08643 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 60 IN X 48 IN	1,701.000	LFT
71	709-51821 SURFACE SEAL	LUMP	LUMP
72	731-93945 FACE PANELS, CONCRETE	44,645.000	SFT
73	731-93946 WALL ERECTION	44,645.000	SFT
74	731-93947 LEVELING PAD, CONCRETE	2,241.530	LFT
75	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
76	801-06625 DETOUR ROUTE MARKER ASSEMBLY	24.000	EACH
77	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
78	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
79	801-07118 BARRICADE, III-A	162.000	LFT
80	801-07119 BARRICADE, III-B	162.000	LFT
81	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	780.000	LFT
82	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	6,170.000	LFT
83	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	4,385.000	LFT
84	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,195.000	LFT
85	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	87.000	EACH
86	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	87.000	EACH

CALL ORDER : 540

CONTRACT ID : B -34797-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	205-06934 TEMPORARY MULCH	2.300	TON
12	205-06937 TEMPORARY SILT FENCE	830.000	LFT
13	205-08517 ROCK FILTER BERM	150.000	TON
14	206-51225 EXCAVATION, DRY	8.000	CYS
15	302-07455 DENSE GRADED SUBBASE	16.200	CYS
16	306-08033 MILLING, ASPHALT, 1 IN	260.000	SYS
17	406-05521 ASPHALT FOR TACK COAT	260.000	SYS
18	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
19	601-02241 GUARDRAIL, REMOVE	203.000	LFT
20	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
21	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	118.750	LFT
22	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	100.000	SYS
23	610-07486 HMA FOR APPROACHES, TYPE A	15.000	TON
24	616-07210 FIBER ROLL	280.000	LFT
25	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
26	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
27	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
28	621-06545 FERTILIZER	0.600	TON
29	621-06553 SEED MIXTURE, R	240.000	LBS
30	621-06557 SEED MIXTURE, T	135.000	LBS
31	621-06565 MULCHING MATERIAL	2.800	TON
32	622-91786 SEEDLING	30.000	EACH
33	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
34	628-09401 FIELD OFFICE, A	15.000	MOS
35	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
36	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	30.000	MOS
37	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
38	702-51005 CONCRETE, A, SUBSTRUCTURE	4.000	CYS
39	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,072.000	LBS
40	702-51863 FIELD DRILLED HOLE IN CONCRETE	80.000	EACH
41	702-90915 CONCRETE, CLASS A	0.400	CYS
42	703-06029 REINFORCING BARS, EPOXY COATED	26,151.000	LBS
43	704-51002 CONCRETE, C, SUPERSTRUCTURE	128.200	CYS
44	706-11405 RAILING, STEEL, PF-2	607.500	LFT
45	706-11603 RAILING, CONCRETE, PF-2	5.600	CYS
46	709-51821 SURFACE SEAL	LUMP	LUMP
47	710-09158 PATCHING CONCRETE STRUCTURES	305.000	SFT
48	711-11696 STRUCTURAL STEEL MEMBER	58.000	LFT
49	711-11697 STRUCTURAL STEEL MEMBER	244.000	EACH

CALL ORDER : 540

CONTRACT ID : B -34797-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
50	711-11697 STRUCTURAL STEEL MEMBER	18.000	EACH
51	711-11697 STRUCTURAL STEEL MEMBER	200.000	EACH
52	711-11697 STRUCTURAL STEEL MEMBER	9.000	EACH
53	711-11697 STRUCTURAL STEEL MEMBER	12.000	EACH
54	711-11697 STRUCTURAL STEEL MEMBER	12.000	EACH
55	713-04643 TEMPORARY ACCESS LANE	LUMP	LUMP
56	715-91361 PIPE, PVC, 6 IN	49.000	LFT
57	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	41.000	LFT
58	727-90308 EPOXY INJECTION, CRACK PREPARATION	90.000	LFT
59	727-90309 EPOXY INJECTION, EPOXY MATERIAL	6.000	GAL
60	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
61	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
62	801-06625 DETOUR ROUTE MARKER ASSEMBLY	25.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	17.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	801-07118 BARRICADE, III-A	48.000	LFT
66	801-07119 BARRICADE, III-B	48.000	LFT
67	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	910.000	LFT
68	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	910.000	LFT

CALL ORDER : 550

CONTRACT ID : M -35755-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8 628-10246	CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	4.000	MOS
9 628-11068	CELLULAR TELEPHONE/RADIO	1.000	EACH
10 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 560

CONTRACT ID : M -35756-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8 628-10246	CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
9 628-11068	CELLULAR TELEPHONE/RADIO	2.000	EACH
10 801-03290	CONSTRUCTION SIGN, C	4.000	EACH



CALL ORDER : 570

CONTRACT ID : M -35757-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 610

CONTRACT ID : T -35161-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH NEW SIGNALS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	964.000	SYS
11	202-74035 SIGN, REMOVE	5.000	EACH
12	202-75997 PRISMATIC REFLECTOR, REMOVE	13.000	EACH
13	202-93615 CONCRETE, REMOVE	1,757.000	SYS
14	203-02000 EXCAVATION, COMMON	295.000	CYS
15	203-02070 BORROW	238.000	CYS
16	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
17	205-06937 TEMPORARY SILT FENCE	478.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	1,064.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	0.300	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	65.000	TON
21	303-01180 COMPACTED AGGREGATE, NO. 53	100.000	TON
22	304-07491 HMA PATCHING, TYPE C	129.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	11,389.000	SYS
24	401-10258 JOINT ADHESIVE, SURFACE	1,060.000	LFT
25	401-10259 JOINT ADHESIVE, INTERMEDIATE	565.000	LFT
26	402-07434 HMA SURFACE, TYPE C	184.000	TON
27	402-07439 HMA INTERMEDIATE, TYPE C	129.000	TON
28	402-07442 HMA BASE, TYPE C	310.000	TON
29	406-05520 ASPHALT FOR TACK COAT	1.700	TON
30	605-02493 CURB ISLAND, CONCRETE	34.200	SYS
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06559 MULCHED SEEDING, R	850.000	SYS
33	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
34	628-09402 FIELD OFFICE, B	10.000	MOS
35	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	20.000	MOS
36	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
37	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	554.000	LFT
38	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	12.000	LFT
39	718-52610 AGGREGATE FOR UNDERDRAINS	41.300	CYS
40	718-99153 GEOTEXTILES FOR UNDERDRAIN	375.000	SYS
41	720-45069 INLET, P12	1.000	EACH
42	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.000	EACH
43	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
44	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
45	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,106.000	LFT
46	801-06640 CONSTRUCTION SIGN, A	29.000	EACH
47	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
48	801-06710 FLASHING ARROW SIGN	150.000	DAY
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 610

CONTRACT ID : T -35161-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH NEW SIGNALS		
50	801-07118 BARRICADE, III-A	148.000	LFT
51	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	30.000	LFT
52	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
53	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	45.000	SFT
54	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	2.000	SFT
55	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	78.000	SFT
56	805-01842 HANDHOLE, SIGNAL	10.000	EACH
57	805-02328 SIGNAL CABLE, 1C/14 GA	2,995.000	LFT
58	805-02658 CABLE, COAXIAL	75.000	LFT
59	805-04973 CONDUIT	1,405.000	LFT
60	805-08244 CELLULAR MODEM KIT	1.000	EACH
61	805-09089 RADIO, YAGI ANTENNA	1.000	EACH
62	805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN	4.000	EACH
63	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	6.000	EACH
64	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
65	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
66	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	2.000	EACH
67	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
68	805-78420 DISCONNECT HANGER	4.000	EACH
69	805-78445 SIGNAL SERVICE	1.000	EACH
70	805-78467 SIGNAL CABLE, 3C/8GA	50.000	LFT
71	805-78485 SIGNAL CABLE, 5C/14GA	255.000	LFT
72	805-78490 SIGNAL CABLE, 7C/14GA	1,355.000	LFT
73	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	3,390.000	LFT
74	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
75	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	970.000	LFT
76	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
77	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	4.000	EACH
78	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
79	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	250.000	LFT
80	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,111.000	LFT
81	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	450.000	LFT
82	808-06716 LINE, REMOVE	250.000	LFT
83	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	178.000	LFT
84	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
85	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
86	808-75994 PRISMATIC REFLECTOR	13.000	EACH
87	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.000	EACH
88	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	16.000	EACH
89	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	156.000	LFT
90	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN	53.000	LFT

CALL ORDER : 620

CONTRACT ID : T -35363-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
8	628-09403 FIELD OFFICE, C	8.000	MOS
9	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
10	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	16.000	MOS
11	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
12	805-02728 CONDUIT, PVC, 1 IN.	570.000	LFT
13	805-06595 CONDUIT, PVC, 2 IN	8,320.000	LFT
14	805-11686 CONDUIT FLEXIBLE 1"	1,065.000	LFT
15	805-90267 CONDUIT, STEEL, GALVANIZED, 3 IN	156.000	LFT
16	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN	340.000	LFT
17	805-95568 CONDUIT, PVC, 4"	800.000	LFT
18	807-02191 HANDHOLE, LIGHTING	1.000	EACH
19	807-02191 HANDHOLE, LIGHTING	24.000	EACH
20	807-02191 HANDHOLE, LIGHTING	8.000	EACH
21	807-02191 HANDHOLE, LIGHTING	38.000	EACH
22	807-02191 HANDHOLE, LIGHTING	1.000	EACH
23	807-02191 HANDHOLE, LIGHTING	1.000	EACH
24	807-02191 HANDHOLE, LIGHTING	60.000	EACH
25	807-02191 HANDHOLE, LIGHTING	22.000	EACH
26	807-02191 HANDHOLE, LIGHTING	2.000	EACH
27	807-02194 SERVICE POINT, II, MODIFIED	1.000	EACH
28	807-04866 LUMINAIRE,	52.000	EACH
29	807-11566 LUMINAIRE, ROADWAY, METAL HALIDE, 150 WATT	9.000	EACH
30	807-11688 LUMINAIRE, ROADWAY, METAL HALIDE, 70 WATT	2.000	EACH
31	807-11704 LUMINAIRE ORNAMENTAL, LED RAIL LIGHTING	2,680.000	LFT
32	807-86842 WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL RESISTANT,	150.000	LFT
33	807-95888 WIRE, NO 8 COPPER, 1/C	12,000.000	LFT
34	807-95889 WIRE, NO 10 COPPER, 1/C	22,550.000	LFT
35	807-95890 WIRE, NO 12 COPPER, 1/C	1,925.000	LFT

