

CALL ORDER : 114

CONTRACT ID : IR-34599-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	107-09358 INSPECTION HOLE, GREATER THAN 3'	5.000	EACH
4	107-09367 INSPECTION HOLE, 3 FT DEPTH OR LESS	5.000	EACH
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02637 PIPE, ABANDON AND GROUT FILL	265.000	LFT
16	203-02000 EXCAVATION, COMMON	7,140.000	CYS
17	203-02070 BORROW	2,120.000	CYS
18	205-06933 TEMPORARY INLET PROTECTION	9.000	EACH
19	205-09543 NO 2 STONE	179.000	TON
20	207-08263 SUBGRADE TREATMENT, TYPE IA	11,913.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,230.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,617.000	CYS
23	211-09265 STRUCTURAL BACKFILL, TYPE 2	109.000	CYS
24	215-07043 CHEMICAL MODIFICATION, SOILS	1,187.000	SYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,201.000	TON
26	302-06464 SUBBASE FOR PCCP	76.000	CYS
27	304-07494 WIDENING WITH HMA, TYPE C	251.000	TON
28	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,146.000	TON
29	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,910.000	TON
30	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,166.000	TON
31	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,404.000	TON
32	402-07432 HMA SURFACE, TYPE A	376.000	TON
33	402-07435 HMA INTERMEDIATE, TYPE A	590.000	TON
34	406-05520 ASPHALT FOR TACK COAT	9.000	TON
35	502-11564 PCCP, 7 IN	304.000	SYS
36	503-05240 D-1 CONTRACTION JOINT	190.000	LFT
37	604-06070 SIDEWALK, CONCRETE	43.000	SYS
38	604-07897 CURB RAMP, CONCRETE, C	71.000	SYS
39	604-07901 CURB RAMP, CONCRETE, G	30.000	SYS
40	604-07904 CURB RAMP, CONCRETE, L	101.000	SYS
41	604-08086 CURB RAMP, CONCRETE	5.000	SYS
42	605-06090 CURB, INTEGRAL, CONCRETE	238.000	LFT
43	605-06120 CURB, CONCRETE	1,221.000	LFT
44	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	5,580.000	LFT
45	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	329.000	LFT
46	605-06255 CENTER CURB, D, CONCRETE	565.000	SYS
47	607-06335 PAVED SIDE DITCH, A	132.000	LFT
48	610-07487 HMA FOR APPROACHES, TYPE B	56.000	TON
49	610-08446 PCCP FOR APPROACHES, 6 IN	630.000	SYS

CALL ORDER : 114

CONTRACT ID : IR-34599-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
50	610-09108 PCCP FOR APPROACHES, 9 IN	84.000	SYS
51	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
52	615-06490 RIGHT OF WAY MARKER	39.000	EACH
53	615-06505 MONUMENT, B	5.000	EACH
54	615-06510 MONUMENT, C	1.000	EACH
55	615-06530 BENCH MARK POST	1.000	EACH
56	616-02320 GEOTEXTILES	578.000	SYS
57	616-06451 RIPRAP, UNIFORM	113.000	TON
58	616-07210 FIBER ROLL	1,945.000	LFT
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
60	621-06557 SEED MIXTURE, T	971.000	LBS
61	621-06560 MULCHED SEEDING, U	417.000	SYS
62	621-06565 MULCHING MATERIAL	13.000	TON
63	621-06567 WATER	61.000	KGAL
64	621-06574 SODDING	2,057.000	SYS
65	621-06575 SODDING, NURSERY	13,081.000	SYS
66	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
67	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
68	628-09402 FIELD OFFICE, B	12.000	MOS
69	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	36.000	MOS
70	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
71	715-02961 WATER MAIN 16 IN	412.000	LFT
72	715-03487 SAFETY METAL END SECTION 4:1 DIA 30"	1.000	EACH
73	715-04612 PIPE	411.000	LFT
74	715-04612 PIPE	240.000	LFT
75	715-04612 PIPE	51.000	LFT
76	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	5,804.000	LFT
77	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	232.000	LFT
78	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,917.000	LFT
79	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	151.000	LFT
80	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	159.000	LFT
81	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	57.000	LFT
82	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	562.000	LFT
83	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	126.000	LFT
84	715-05233 PIPE, TYPE 1 DEFORMED MIN AREA 3.3 SFT	71.000	LFT
85	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	2.000	EACH
86	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	39.000	TON
87	715-46000 PIPE END SECTION, DIA 12"	4.000	EACH
88	715-46005 PIPE END SECTION, DIA 15"	8.000	EACH
89	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
90	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
91	718-52610 AGGREGATE FOR UNDERDRAINS	427.000	CYS
92	720-02442 PIPE, PLUG EXISTING	8.000	EACH
93	720-07309 TRENCH DRAIN	60.000	LFT
94	720-45270 PIPE CATCH BASIN, 18 IN	9.000	EACH
95	720-45410 MANHOLE, C4	12.000	EACH
96	720-94612 MANHOLE, K4	1.000	EACH
97	720-95422 MANHOLE, J4	4.000	EACH
98	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH

CALL ORDER : 114

CONTRACT ID : IR-34599-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
99	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	1.000	EACH
100	720-98174 INLET, B15	18.000	EACH
101	720-98555 INLET, C15	12.000	EACH
102	732-05538 TESTING AND DISINFECTION	LUMP	LUMP
103	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
104	801-03291 CONSTRUCTION SIGN, D	1.000	EACH
105	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
106	801-06625 DETOUR ROUTE MARKER ASSEMBLY	41.000	EACH
107	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
108	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
109	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
110	801-07119 BARRICADE, III-B	256.000	LFT
111	801-09282 TEMPORARY PANEL SIGNS	195.000	SFT
112	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	613.000	LFT
113	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	97.000	LFT
114	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	118.000	SFT
115	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	247.000	SFT
116	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	20.000	SFT
117	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
118	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
119	807-01603 SERVICE POINT, TYPE II	1.000	EACH
120	807-02191 HANDHOLE, LIGHTING	3.000	EACH
121	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	17.000	EACH
122	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	475.000	LFT
123	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	3,750.000	LFT
124	807-83752 LIGHT POLE, 40FT E.M.H., 10FT MAST ARM, ANCHOR BASE	17.000	EACH
125	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	17.000	EACH
126	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	2,040.000	LFT
127	807-86910 CONNECTOR KIT, UNFUSED	17.000	EACH
128	807-86915 CONNECTOR KIT, FUSED	17.000	EACH
129	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	33.000	EACH
130	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
131	807-86930 INSULATION LINK, NON-WATERPROOFED	34.000	EACH
132	807-86935 INSULATION LINK, WATERPROOFED	12.000	EACH
133	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
134	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	7,731.000	LFT
135	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	6,893.000	LFT
136	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	16.000	EACH
137	808-11401 TRANSVERSE MARKING, PREFORMED PLASTIC,	91.000	LFT
138	808-11481 LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	108.000	LFT
139	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	550.000	LFT
140	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	35.000	EACH

