

CALL ORDER : 112

CONTRACT ID : IR-34537-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ADDED TRAVEL LANES PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	2,035.000	SYS
12	203-02000 EXCAVATION, COMMON	2,529.000	CYS
13	205-06930 SPLASHPAD	17.000	TON
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	72.000	TON
15	207-08263 SUBGRADE TREATMENT, TYPE IA	3,814.000	SYS
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	216.000	SYS
17	207-09935 SUBGRADE TREATMENT, TYPE 1C	163.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	43.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	659.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	697.000	TON
21	306-08042 MILLING, SCARIFICATION/PROFILE	4,092.000	SYS
22	306-08043 MILLING, TRANSITION	544.000	SYS
23	306-08159 MILLING ASPHALT	920.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	402-07432 HMA SURFACE, TYPE A	214.000	TON
26	402-07433 HMA SURFACE, TYPE B	14.000	TON
27	402-07434 HMA SURFACE, TYPE C	523.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	356.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	23.000	TON
30	402-07439 HMA INTERMEDIATE, TYPE C	227.000	TON
31	402-07442 HMA BASE, TYPE C	257.000	TON
32	406-05520 ASPHALT FOR TACK COAT	3.600	TON
33	610-09108 PCCP FOR APPROACHES, 9 IN	216.000	SYS
34	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
35	615-06490 RIGHT OF WAY MARKER	13.000	EACH
36	615-06505 MONUMENT, B	4.000	EACH
37	616-02320 GEOTEXTILES	419.000	SYS
38	616-06405 RIPRAP, REVETMENT	233.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
40	621-06545 FERTILIZER	0.400	TON
41	621-06553 SEED MIXTURE, R	189.000	LBS
42	621-06557 SEED MIXTURE, T	167.000	LBS
43	621-06565 MULCHING MATERIAL	5.000	TON
44	621-06567 WATER	0.600	KGAL
45	621-06574 SODDING	151.000	SYS
46	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
47	628-09402 FIELD OFFICE, B	9.000	MOS
48	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	9.000	MOS
49	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH

CALL ORDER : 112

CONTRACT ID : IR-34537-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES PROJECT		
50	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	477.000	LFT
51	715-46005 PIPE END SECTION, DIA 15"	12.000	EACH
52	715-91742 WATER METER, RELOCATE	1.000	EACH
53	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
54	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	11,067.000	LFT
55	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
56	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	24.000	LFT
59	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	26.000	LFT
60	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
61	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	25.000	SFT
62	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,569.000	LFT
63	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	41.000	LFT
64	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,468.000	LFT
65	808-75290 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT
66	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
67	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH