

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	107-09358 INSPECTION HOLE, GREATER THAN 3'	10.000	EACH
3	107-09367 INSPECTION HOLE, 3 FT DEPTH OR LESS	10.000	EACH
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
14	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02240 PAVEMENT REMOVAL	86,631.000	SYS
17	203-02000 EXCAVATION, COMMON	1,735.000	CYS
18	203-11844 VIBRO-COMPACTION	223,878.000	CYS
19	205-03371 SEDIMENT, REMOVE	1,000.000	CYS
20	205-06930 SPLASHPAD	17.000	TON
21	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	65.000	TON
22	205-06933 TEMPORARY INLET PROTECTION	139.000	EACH
23	205-06936 TEMPORARY SEDIMENT TRAP	18.000	TON
24	205-06937 TEMPORARY SILT FENCE	5,066.000	LFT
25	205-06938 TEMPORARY SLOPE DRAIN	419.000	LFT
26	205-09543 NO 2 STONE	608.000	TON
27	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	2,443.000	CYS
28	207-08263 SUBGRADE TREATMENT, TYPE IA	144,321.000	SYS
29	207-08266 SUBGRADE TREATMENT, TYPE III	4,940.000	SYS
30	207-08267 SUBGRADE TREATMENT, TYPE IIIA	25,187.000	SYS
31	211-02050 B BORROW	9,036.000	CYS
32	211-06467 AGGREGATE FOR END BENT BACKFILL	189.000	CYS
33	211-09264 STRUCTURAL BACKFILL, TYPE 1	45,191.000	CYS
34	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,007.000	CYS
35	211-09266 STRUCTURAL BACKFILL, TYPE 3	10,865.000	CYS
36	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	114.000	CYS
37	302-07455 DENSE GRADED SUBBASE	98.000	CYS
38	303-05738 AGGREGATE, NO. 5	345.000	TON
39	304-07494 WIDENING WITH HMA, TYPE C	444.000	TON
40	306-08043 MILLING, TRANSITION	4,483.000	SYS
41	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
42	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	603.000	TON
43	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,392.000	TON
44	402-10084 HMA FOR TEMPORARY PAVEMENT, B	1,053.000	TON
45	402-10087 HMA FOR TEMPORARY PAVEMENT, D	2,159.000	TON
46	502-03289 QUALITY ASSURANCE ADJUSTMENT	1.000	DOL
47	601-01522 GUARDRAIL, TRANSITION TYPE TGB	6.000	EACH
48	601-02241 GUARDRAIL, REMOVE	5,110.000	LFT
49	601-06234 IMPACT ATTENUATOR, R1, W1, TL-2	10.000	EACH

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
50	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	2.000	EACH
51	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	4.000	EACH
52	601-09146 IMPACT ATTENUATOR, CR1, W1, TL-2	5.000	EACH
53	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
54	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
55	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,119.000	LFT
56	602-01064 CONCRETE BARRIER	9,015.000	LFT
57	602-01064 CONCRETE BARRIER	1,981.000	LFT
58	602-06729 BARRIER DELINEATOR	641.000	EACH
59	603-06045 FENCE, CHAIN LINK, 48 IN	6,764.000	LFT
60	603-97283 FENCE GATE, CHAIN LINK, 48 IN X 24 FT	1.000	EACH
61	604-05528 HMA FOR SIDEWALK	803.000	TON
62	604-06070 SIDEWALK, CONCRETE	2,045.000	SYS
63	604-07900 CURB RAMP, CONCRETE, F	278.000	SYS
64	604-95344 HAND RAIL, PEDESTRIAN	628.000	LFT
65	605-06120 CURB, CONCRETE	267.000	LFT
66	605-06140 CURB AND GUTTER, CONCRETE	4,947.000	LFT
67	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	39.000	LFT
68	605-06205 CENTER CURB, B, CONCRETE	20.000	LFT
69	607-06175 GUTTER, CONCRETE, A	239.000	LFT
70	607-06175 GUTTER, CONCRETE, A	356.000	LFT
71	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	31.000	SYS
72	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	569.600	SYS
73	610-07487 HMA FOR APPROACHES, TYPE B	157.000	TON
74	610-08446 PCCP FOR APPROACHES, 6 IN	198.000	SYS
75	610-09108 PCCP FOR APPROACHES, 9 IN	543.000	SYS
76	615-06490 RIGHT OF WAY MARKER	64.000	EACH
77	615-06505 MONUMENT, B	13.000	EACH
78	615-06510 MONUMENT, C	19.000	EACH
79	615-06515 MONUMENT, D	75.000	EACH
80	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
81	616-02320 GEOTEXTILES	1,817.000	SYS
82	616-06405 RIPRAP, REVETMENT	208.000	TON
83	616-06451 RIPRAP, UNIFORM	49.000	TON
84	616-51367 SLOPEWALL, CONCRETE, 4 IN	1,520.000	SYS
85	620-08426 SOUND BARRIER DESIGN AND LAYOUT	LUMP	LUMP
86	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
87	621-04258 SEED MIXTURE	66.000	LBS
88	621-04258 SEED MIXTURE	14.000	LBS
89	621-06545 FERTILIZER	100.000	TON
90	621-06554 SEED MIXTURE, U	3,750.000	LBS
91	621-06557 SEED MIXTURE, T	1,875.000	LBS
92	621-06565 MULCHING MATERIAL	50.000	TON
93	621-06567 WATER	32.000	KGAL
94	621-06574 SODDING	6,889.000	SYS
95	621-06575 SODDING, NURSERY	1,918.000	SYS
96	621-09908 SOIL	9.000	CYS
97	621-98038 MULCH, HARDWOOD SHREDDED BARK	35.000	CYS
98	622-05625 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	33.000	EACH

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
99	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	27.000	EACH
100	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	86.000	EACH
101	628-09403 FIELD OFFICE, C	30.000	MOS
102	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
103	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
104	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
105	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
106	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	120.000	MOS
107	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
108	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
109	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
110	701-09557 TEST PILE, DYNAMIC, PRODUCTION	334.000	LFT
111	701-09558 TEST PILE, INDICATOR, PRODUCTION	190.000	LFT
112	701-09559 TEST PILE, DYNAMIC, RESTRIKE	4.000	EACH
113	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
114	701-09683 PILE SHOE, HP 12 X 74	116.000	EACH
115	701-95780 PILE, STEEL H, HP 12 IN X 74	7,704.000	LFT
116	702-04325 TEMPORARY SHORING	LUMP	LUMP
117	702-51005 CONCRETE, A, SUBSTRUCTURE	424.700	CYS
118	702-51015 CONCRETE, B, FOOTINGS	311.200	CYS
119	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	322.000	LBS
120	702-92857 CONCRETE, C, SUBSTRUCTURE	141.000	CYS
121	703-06028 REINFORCING BARS	143,378.000	LBS
122	703-06029 REINFORCING BARS, EPOXY COATED	481,520.000	LBS
123	703-96512 BAR SPLICE	288.000	EACH
124	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,402.700	CYS
125	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	1,911.000	SYS
126	706-09545 COARSE AGGREGATE, NO 8	7.000	CYS
127	706-09959 RAILING, CONCRETE, FT	750.000	LFT
128	706-09959 RAILING, CONCRETE, FT	929.000	LFT
129	706-09960 RAILING, CONCRETE, FC	1,066.000	LFT
130	706-09960 RAILING, CONCRETE, FC	512.000	LFT
131	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	4.000	EACH
132	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	4.000	EACH
133	706-51020 RAILING, CONCRETE, C	178.000	CYS
134	707-09921 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 54 IN X 49 IN	3,738.000	LFT
135	711-96800 STUD SHEAR CONNECTORS	288.000	EACH
136	712-03862 PREFABRICATED BRIDGE	LUMP	LUMP
137	715-01902 WATER SERVICE LINE 2 IN	29.000	LFT
138	715-02745 GATE VALVE WITH VALVE BOXES, 8 IN	10.000	EACH
139	715-04596 WATER SERVICE	1.000	EACH
140	715-04836 GATE VALVE	7.000	EACH
141	715-04836 GATE VALVE	1.000	EACH
142	715-04836 GATE VALVE	9.000	EACH
143	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	1,835.000	LFT
144	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	40,241.000	LFT
145	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,923.000	LFT
146	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	3,420.000	LFT
147	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,252.000	LFT

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
148	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,290.000	LFT
149	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	258.000	LFT
150	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	367.000	LFT
151	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	1,128.000	LFT
152	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	1,051.000	LFT
153	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	2,655.000	LFT
154	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	923.000	LFT
155	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	291.000	LFT
156	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	407.000	LFT
157	715-05164 PIPE, TYPE 2 CIRCULAR 66 IN	722.000	LFT
158	715-05164 PIPE, TYPE 2 CIRCULAR 66 IN	565.000	LFT
159	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	62.000	LFT
160	715-05407 PIPE, END BENT DRAIN, 6 IN	316.000	LFT
161	715-05422 PIPE, SLOTTED DRAIN, 12 IN	1,323.000	LFT
162	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	309.000	TON
163	715-09064 VIDEO INSPECTION FOR PIPE	16,714.000	LFT
164	715-09811 AUTOMATIC FLUSHING DEVICE	1.000	EACH
165	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	1.000	EACH
166	715-46000 PIPE END SECTION, DIA 12"	5.000	EACH
167	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
168	715-46010 PIPE END SECTION, DIA 18"	2.000	EACH
169	715-91739 WATER SERVICE LINE, 0.75 IN	442.000	LFT
170	715-91742 WATER METER, RELOCATE	12.000	EACH
171	715-93403 WATER SERVICE CONNECTION, 0.75 IN.	12.000	EACH
172	715-93912 WATER MAIN, 6 IN	512.000	LFT
173	715-93913 WATER MAIN, 8 IN	175.000	LFT
174	715-96669 WATER MAIN, DUCTILE IRON, 16 IN	1,470.000	LFT
175	715-98165 WATER MAIN, 12 IN	20.000	LFT
176	716-01382 AIR RELEASE VALVE	2.000	EACH
177	716-07630 PIPE INSTALLATION, TRENCHLESS, 12 IN	39.000	LFT
178	716-07632 PIPE INSTALLATION, TRENCHLESS, 18 IN	31.000	LFT
179	716-07635 PIPE INSTALLATION, TRENCHLESS, 36 IN	162.000	LFT
180	716-07637 PIPE INSTALLATION, TRENCHLESS, 48 IN	104.000	LFT
181	716-07637 PIPE INSTALLATION, TRENCHLESS, 48 IN	29.000	LFT
182	716-09822 PIPE INSTALLATION, TRENCHLESS, 66 IN	185.000	LFT
183	718-06528 OUTLET PROTECTOR, 1	23.000	EACH
184	718-06529 OUTLET PROTECTOR, 2	30.000	EACH
185	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
186	718-52610 AGGREGATE FOR UNDERDRAINS	6,394.000	CYS
187	718-99153 GEOTEXTILES FOR UNDERDRAIN	35,842.000	SYS
188	719-93923 DUCTILE IRON FITTINGS	8,580.000	LBS
189	720-02442 PIPE, PLUG EXISTING	10.000	EACH
190	720-07299 INLET, H	27.000	EACH
191	720-07301 INLET, TYPE HA	15.000	EACH
192	720-08658 MANHOLE, J5	1.000	EACH
193	720-10138 MANHOLE, L7	1.000	EACH
194	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
195	720-44000 CASTING, ADJUST TO GRADE	23.000	EACH
196	720-45005 INLET, A2	1.000	EACH

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERCHANGE MODIFICATION		
197	720-45030 INLET, E7	14.000	EACH
198	720-45035 INLET, F7	3.000	EACH
199	720-45040 INLET, G7	2.000	EACH
200	720-45065 INLET, N12	3.000	EACH
201	720-45080 INLET, S14	7.000	EACH
202	720-45085 INLET, T14	2.000	EACH
203	720-45270 PIPE CATCH BASIN, 18 IN	2.000	EACH
204	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
205	720-45410 MANHOLE, C4	14.000	EACH
206	720-45425 MANHOLE, F4	1.000	EACH
207	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	28.000	LFT
208	720-91050 MANHOLE, K7, MODIFIED	1.000	EACH
209	720-93501 MANHOLE, L4	3.000	EACH
210	720-93501 MANHOLE, L4	2.000	EACH
211	720-94612 MANHOLE, K4	18.000	EACH
212	720-94612 MANHOLE, K4	3.000	EACH
213	720-95335 MANHOLE, M4	7.000	EACH
214	720-95335 MANHOLE, M4	2.000	EACH
215	720-95422 MANHOLE, J4	13.000	EACH
216	720-96999 FIRE HYDRANT ASSEMBLY	7.000	EACH
217	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	7.000	EACH
218	720-97962 MANHOLE, G4, MODIFIED	1.000	EACH
219	720-98174 INLET, B15	32.000	EACH
220	720-98555 INLET, C15	6.000	EACH
221	731-93945 FACE PANELS, CONCRETE	26,188.000	SFT
222	731-93946 WALL ERECTION	26,188.000	SFT
223	731-93947 LEVELING PAD, CONCRETE	2,523.000	LFT
224	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	18.000	EACH
225	801-01506 TEMPORARY PAVEMENT MESSAGE MARKING, (RXR)	2.000	EACH
226	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
227	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
228	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	87,224.000	LFT
229	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	59,426.000	LFT
230	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	4.000	EACH
231	801-06213 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	4.000	EACH
232	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	627.000	LFT
233	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
234	801-06640 CONSTRUCTION SIGN, A	107.000	EACH
235	801-06645 CONSTRUCTION SIGN, B	136.000	EACH
236	801-06710 FLASHING ARROW SIGN	1,425.000	DAY
237	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
238	801-07118 BARRICADE, III-A	684.000	LFT
239	801-07118 BARRICADE, III-A	264.000	LFT
240	801-07119 BARRICADE, III-B	144.000	LFT
241	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	547.000	LFT
242	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	4,880.000	LFT
243	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	40.000	LFT
244	801-52817 TEMPORARY CROSSOVER, B	4.000	EACH
245	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERCHANGE MODIFICATION			
246	801-94295	SIGNAL HEAD, RELOCATE	68.000 EACH
247	802-01749	SIGN BRACKET ASSEMBLY, WALL MOUNTED	2.000 EACH
248	802-01749	SIGN BRACKET ASSEMBLY, WALL MOUNTED	4.000 EACH
249	802-03896	BOLLARD	12.000 EACH
250	802-05694	OVERHEAD SIGN STRUCTURE	1.000 EACH
251	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	808.000 LFT
252	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	286.000 LFT
253	802-07057	SIGN, PANEL, WITH LEGEND	4,334.000 SFT
254	802-09221	OVERHEAD SIGN STRUCTURE,BOX TRUSS TYPE A	4.000 EACH
255	802-09223	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE C	1.000 EACH
256	802-09224	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE D	1.000 EACH
257	802-09535	BOX TRUSS SIGN STRUCTURE FOUNDATION, 33 IN.	3.000 EACH
258	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN.	9.000 EACH
259	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	5.000 EACH
260	802-09579	CANTILEVER SIGN SUPPORT FOUNDATION,	1.000 EACH
261	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION,	5.000 EACH
262	802-09838	SIGN, SHEET, WITH LEGEND 0.080"	281.000 SFT
263	802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN	808.000 SFT
264	802-09842	SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	18.000 SFT
265	802-09861	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE I	1.000 EACH
266	802-11649	SIGN FOUNDATION	1.000 EACH
267	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	1.000 EACH
268	802-74055	OVERHEAD SIGN STRUCTURE BOX TRUSS, REMOVE	5.000 EACH
269	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	4.000 EACH
270	802-93388	BARRIER WALL SIGN BRACKET ASSEMBLY, MEDIAN	4.000 EACH
271	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000 EACH
272	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN	8,462.000 LFT
273	805-06595	CONDUIT, PVC, 2 IN	11,851.000 LFT
274	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12"	1.000 EACH
275	807-02191	HANDHOLE, LIGHTING	8.000 EACH
276	807-02428	LIGHTING FOUNDATION, CONCRETE, WITH GROUND	94.000 EACH
277	807-04653	LIGHTING FOUNDATION,	27.000 EACH
278	807-04653	LIGHTING FOUNDATION,	3.000 EACH
279	807-04653	LIGHTING FOUNDATION,	11.000 EACH
280	807-98469	PULL BOX	5.000 EACH
281	808-09381	RETRO-REFLECTIVITY TESTING	LUMP LUMP
282	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	83.000 LFT
283	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,105.000 LFT
284	809-06101	FOUNDATION	12.000 EACH
SECTION NO. 0002 ROAD CONSTRUCTION PCCP			
285	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP LUMP
286	203-02000	EXCAVATION, COMMON	171,816.000 CYS
287	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	11,296.000 TON
288	302-06464	SUBBASE FOR PCCP	32,884.000 CYS
289	303-01180	COMPACTED AGGREGATE, NO. 53	7,926.000 TON
290	401-07320	QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,388.000 TON
291	401-07406	QC/QA-HMA, 1, 64, BASE, 25.0 mm	7,085.000 TON

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 ROAD CONSTRUCTION PCCP			
292	401-10258 JOINT ADHESIVE, SURFACE	1,130.000	LFT
293	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,130.000	LFT
294	401-11785 LIQUID ASPHALT SEALANT	1,130.000	LFT
295	406-05520 ASPHALT FOR TACK COAT	15.580	TON
296	410-09530 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	370.000	TON
297	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
298	501-06322 QC/QA-PCCP, 11 IN	86,974.000	SYS
299	501-09749 QC/QA PCCP, 9.5"	20,962.000	SYS
300	503-05240 D-1 CONTRACTION JOINT	57,057.000	LFT
301	503-05310 TERMINAL JOINT	168.000	LFT
302	605-06095 CURB, INTEGRAL, B, CONCRETE	1,012.000	LFT
303	703-06029 REINFORCING BARS, EPOXY COATED	178,598.000	LBS
304	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	4.000	EACH
305	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	2,513.000	LFT
306	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,138.000	LFT
307	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	7,932.000	LFT
308	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	24,742.000	LFT
309	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	24,131.000	LFT
310	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	11,156.000	LFT
311	808-10053 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	6.000	EACH
312	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	77.000	LFT
313	808-75069 TRANSVERSE MARKING, PREFORMED PLASTIC,	320.000	LFT
314	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	8.000	EACH
315	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,200.000	LFT
316	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	81.000	LFT
317	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	997.000	LFT
318	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	925.000	EACH
SECTION NO. 0003 ROAD CONSTRUCTION HMA			
319	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
320	203-02000 EXCAVATION, COMMON	156,577.000	CYS
321	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	11,079.000	TON
322	303-01180 COMPACTED AGGREGATE, NO. 53	4,308.000	TON
323	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	3,390.000	TON
324	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	4,824.000	TON
325	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2,921.000	TON
326	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	12,006.000	TON
327	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	16,064.000	TON
328	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	38,418.000	TON
329	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	6,975.000	TON
330	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	24,411.000	TON
331	401-10258 JOINT ADHESIVE, SURFACE	62,621.000	LFT
332	401-10259 JOINT ADHESIVE, INTERMEDIATE	60,491.000	LFT
333	401-11785 LIQUID ASPHALT SEALANT	62,621.000	LFT
334	406-05520 ASPHALT FOR TACK COAT	153.450	TON
335	410-09530 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	6,492.000	TON
336	410-10128 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm, - SMA	1,725.000	TON
337	415-11527 BASE SEAL	105.000	TON

CALL ORDER : 141

CONTRACT ID : IR-30624-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 ROAD CONSTRUCTION HMA			
338	503-05240	970.000	LFT
339	605-06145	6,079.000	LFT
340	703-06029	178,066.000	LBS
341	808-06701	10,085.000	LFT
342	808-06703	25,162.000	LFT
343	808-06705	11,156.000	LFT
344	808-10031	360.000	LFT
345	808-10033	718.000	LFT
346	808-10034	718.000	LFT
347	808-75245	26,613.000	LFT
348	808-75272	997.000	LFT
349	808-75297	158.000	LFT
350	808-75300	997.000	LFT
351	808-75320	8.000	EACH
352	808-75325	4.000	EACH
353	808-75340	6.000	EACH
SECTION NO. 0001 INTERCHANGE MODIFICATION			
354	709-51821	LUMP	LUMP
355	709-51821	LUMP	LUMP
356	709-51821	LUMP	LUMP
357	709-51821	LUMP	LUMP
358	709-51821	LUMP	LUMP
359	202-51330	LUMP	LUMP
360	202-51330	LUMP	LUMP
361	202-51330	LUMP	LUMP
362	604-07894	9.000	SYS
363	604-07896	49.000	SYS
364	604-07897	13.000	SYS
365	604-07903	21.000	SYS
366	620-01754	12,416.000	SFT
367	620-01756	12,416.000	SFT
368	621-90853	1.000	EACH
369	713-51334	LUMP	LUMP
370	713-51334	LUMP	LUMP
371	713-51334	LUMP	LUMP
372	713-51334	LUMP	LUMP
373	713-51334	LUMP	LUMP
374	713-51334	LUMP	LUMP
375	713-51334	LUMP	LUMP
376	713-51334	LUMP	LUMP
377	713-51334	LUMP	LUMP
378	713-51334	LUMP	LUMP
379	808-06716	35,994.000	LFT
380	801-06201	300.000	SFT
381	802-76095	728.000	LBS
382	802-07138	4.000	EACH
383	805-78205	7.000	EACH