

CALL ORDER : 171

CONTRACT ID : R -32258-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	5,143.000	SYS
13	203-02000 EXCAVATION, COMMON	3,083.000	CYS
14	205-03371 SEDIMENT, REMOVE	16.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	152.000	TON
16	205-06933 TEMPORARY INLET PROTECTION	80.000	EACH
17	205-06937 TEMPORARY SILT FENCE	2,249.000	LFT
18	205-11586 TEMPORARY FILTER STONE	9.000	TON
19	205-11587 TEMPORARY GEOTEXTILE	460.000	SYS
20	205-11591 TEMPORARY SEED MIXTURE	11,053.000	LBS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	4,750.000	SYS
22	207-09935 SUBGRADE TREATMENT, TYPE IC	10,399.000	SYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	825.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,837.000	TON
25	303-01180 COMPACTED AGGREGATE, NO. 53	2,946.000	TON
26	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	356.000	TON
27	304-07783 HMA PATCHING, TYPE D	1,860.000	TON
28	305-06465 CEMENT CONCRETE PAVEMENT CRACKING AND SEATING	175,508.000	SYS
29	305-07464 PCC BASE PATCHING, 9 IN	1,598.000	SYS
30	305-09888 RELIEF JOINT	500.000	LFT
31	306-08042 MILLING, SCARIFICATION/PROFILE	220,030.000	SYS
32	306-08043 MILLING, TRANSITION	1,518.000	SYS
33	306-08432 MILLING, APPROACH	8,409.000	SYS
34	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
35	401-07338 QC/QA-HMA, 1, 64, SURFACE, 12.5 mm	11,335.000	TON
36	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	6,617.000	TON
37	401-07393 QC/QA-HMA, 4, 64, INTERMEDIATE, 19.0 mm	2,404.000	TON
38	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	20,125.000	TON
39	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	360.000	TON
40	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	911.000	TON
41	401-10258 JOINT ADHESIVE, SURFACE	278,598.000	LFT
42	401-10259 JOINT ADHESIVE, INTERMEDIATE	200,973.000	LFT
43	401-11785 LIQUID ASPHALT SEALANT	278,598.000	LFT
44	402-10084 HMA FOR TEMPORARY PAVEMENT, B	1,764.000	TON
45	406-05520 ASPHALT FOR TACK COAT	162.000	TON
46	410-11777 QC/QA-HMA 4, 76, SURFACE, 12.5 mm - SMA	33,978.000	TON
47	415-11527 BASE SEAL	5.000	TON
48	503-05240 D-1 CONTRACTION JOINT	528.000	LFT
49	503-05310 TERMINAL JOINT	207.000	LFT

CALL ORDER : 171

CONTRACT ID : R -32258-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	601-01522 GUARDRAIL, TRANSITION TYPE TGB	8.000	EACH
51	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	2.000	EACH
52	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
53	601-02206 TEMPORARY GUARDRAIL, W BEAM, 6FT-3 IN SPACING	169.000	LFT
54	601-02241 GUARDRAIL, REMOVE	3,713.000	LFT
55	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
56	601-06855 GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	2.000	EACH
57	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
58	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
59	601-97080 TEMPORARY GUARDRAIL END TREATMENT, OS	1.000	EACH
60	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	4,464.000	LFT
61	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	90.000	LFT
62	606-07484 MILLED HMA CORRUGATIONS	186,385.000	LFT
63	610-07487 HMA FOR APPROACHES, TYPE B	1,477.000	TON
64	616-02320 GEOTEXTILES	155.000	SYS
65	616-05688 RIPRAP, CLASS 1	140.000	TON
66	616-06451 RIPRAP, UNIFORM	5.000	TON
67	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
68	621-06545 FERTILIZER	16.000	TON
69	621-06553 SEED MIXTURE, R	6,268.000	LBS
70	621-06565 MULCHING MATERIAL	220.000	TON
71	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
72	628-09403 FIELD OFFICE, C	12.000	MOS
73	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
74	628-11730 CELLULAR TELEPHONE TYPE B	4.000	EACH
75	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
76	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	48.000	MOS
77	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	90,420.000	LFT
78	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	18,765.000	LFT
79	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	67.000	LFT
80	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	80.000	LFT
81	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	92,676.000	LFT
82	715-09064 VIDEO INSPECTION FOR PIPE	67.000	LFT
83	715-11740 PIPE, TYPE 1 DEFORMED MIN AREA 24.0 SFT	152.000	LFT
84	718-06526 HMA FOR UNDERDRAINS	14,924.000	TON
85	718-06528 OUTLET PROTECTOR, 1	32.000	EACH
86	718-06529 OUTLET PROTECTOR, 2	16.000	EACH
87	718-06531 OUTLET PROTECTOR, 3	218.000	EACH
88	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	13,000.000	LFT
89	718-52610 AGGREGATE FOR UNDERDRAINS	9,815.600	CYS
90	718-99153 GEOTEXTILES FOR UNDERDRAIN	133,158.300	SYS
91	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
92	720-45065 INLET, N12	1.000	EACH
93	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
94	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
95	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
96	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	140,989.000	LFT
97	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	194,933.000	LFT
98	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN	2,923.000	LFT

CALL ORDER : 171

CONTRACT ID : R -32258-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
99	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
100	801-06640 CONSTRUCTION SIGN, A	136.000	EACH
101	801-06645 CONSTRUCTION SIGN, B	93.000	EACH
102	801-06710 FLASHING ARROW SIGN	210.000	DAY
103	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
104	801-07118 BARRICADE, III-A	408.000	LFT
105	801-07119 BARRICADE, III-B	192.000	LFT
106	801-07606 TEMPORARY CROSSOVER DRAINAGE PIPE	580.000	LFT
107	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	156.000	LFT
108	801-52817 TEMPORARY CROSSOVER, B	2.000	EACH
109	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	24,724.000	LFT
110	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	96,238.000	LFT
111	808-06716 LINE, REMOVE	154,275.000	LFT
112	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
113	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	95,244.000	LFT
114	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	176.000	LFT
115	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	34.000	EACH
116	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	34.000	EACH
117	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,164.000	EACH
118	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,164.000	EACH
119	621-06574 SODDING	1,102.000	SYS