

CALL ORDER : 201

CONTRACT ID : R -33673-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	8,405.000	SYS
13	202-02279 CURB AND GUTTER, REMOVE	470.000	LFT
14	202-02637 PIPE, ABANDON AND GROUT FILL	293.000	LFT
15	202-02928 CATCH BASIN, REMOVE	2.000	EACH
16	202-07553 REGULATED MATERIALS, REMOVE, Y	1,950.000	CYS
17	202-07554 REGULATED MATERIALS, TRANSPORT, Y	1,950.000	CYS
18	202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y	1,950.000	CYS
19	202-52710 SIDEWALK, CONCRETE, REMOVE	306.000	SYS
20	202-96022 CONCRETE FOUNDATION, REMOVE	1.000	EACH
21	202-96035 CONCRETE WALL, REMOVE	446.000	LFT
22	202-96133 PIPE, REMOVE	542.000	LFT
23	202-96430 FENCE AND POSTS, REMOVE	LUMP	LUMP
24	203-02000 EXCAVATION, COMMON	7,565.000	CYS
25	203-02100 EXCAVATION, PEAT	325.000	CYS
26	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	20.000	TON
27	205-06933 TEMPORARY INLET PROTECTION	47.000	EACH
28	205-06937 TEMPORARY SILT FENCE	3,471.000	LFT
29	205-09543 NO 2 STONE	100.000	TON
30	207-08263 SUBGRADE TREATMENT, TYPE IA	15,562.000	SYS
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	6,122.000	SYS
32	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,685.000	CYS
33	211-09266 STRUCTURAL BACKFILL, TYPE 3	125.000	CYS
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,729.000	TON
35	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,123.000	SYS
36	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,057.000	TON
37	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,599.000	TON
38	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,811.000	TON
39	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,849.000	TON
40	401-10258 JOINT ADHESIVE, SURFACE	7,273.000	LFT
41	401-10259 JOINT ADHESIVE, INTERMEDIATE	7,273.000	LFT
42	401-11785 LIQUID ASPHALT SEALANT	7,273.000	LFT
43	402-10084 HMA FOR TEMPORARY PAVEMENT, B	1,122.000	TON
44	406-05520 ASPHALT FOR TACK COAT	12.000	TON
45	415-11527 BASE SEAL	10.000	TON
46	603-91714 FENCE, RAIL, WOOD	77.000	LFT
47	604-06070 SIDEWALK, CONCRETE	2,219.000	SYS
48	604-07901 CURB RAMP, CONCRETE, G	30.000	SYS
49	604-07902 CURB RAMP, CONCRETE, H	23.000	SYS

CALL ORDER : 201

CONTRACT ID : R -33673-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHABILITATION		
50	604-07903 CURB RAMP, CONCRETE, K	50.000	SYS
51	604-44251 STEPS, CONCRETE	1.000	CYS
52	605-06120 CURB, CONCRETE	601.000	LFT
53	605-06140 CURB AND GUTTER, CONCRETE	4,191.000	LFT
54	605-06235 CENTER CURB, D, CONCRETE, MODIFIED	58.000	LFT
55	605-96305 CURB AND GUTTER, CONCRETE, DEPRESSED	181.000	LFT
56	607-06175 GUTTER, CONCRETE, A	586.000	LFT
57	610-07487 HMA FOR APPROACHES, TYPE B	452.000	TON
58	610-08446 PCCP FOR APPROACHES, 6 IN	236.000	SYS
59	610-09108 PCCP FOR APPROACHES, 9 IN	1,454.000	SYS
60	611-06497 MAILBOX ASSEMBLY, SINGLE	22.000	EACH
61	615-06505 MONUMENT, B	5.000	EACH
62	616-02320 GEOTEXTILES	41.000	SYS
63	616-06405 RIPRAP, REVETMENT	31.000	TON
64	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
65	621-03787 SEED MIXTURE, D	30.000	LBS
66	621-06545 FERTILIZER	1.000	TON
67	621-06557 SEED MIXTURE, T	410.000	LBS
68	621-06565 MULCHING MATERIAL	8.000	TON
69	621-06567 WATER	13.000	KGAL
70	621-06570 TOPSOIL	360.000	CYS
71	621-06575 SODDING, NURSERY	3,214.000	SYS
72	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
73	628-09402 FIELD OFFICE, B	15.000	MOS
74	715-01898 WATER MAIN, DUCTILE IRON, 10 IN	6.000	LFT
75	715-01902 WATER SERVICE LINE 2 IN	26.000	LFT
76	715-02185 WATER SERVICE LINE, 1.50 IN	40.000	LFT
77	715-02529 VALVE WITH BOX, RESTRAINED, BUTTERFLY, DUCTILE	10.000	EACH
78	715-02532 VALVE WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN	4.000	EACH
79	715-02874 CURB STOP AND BOX	35.000	EACH
80	715-04750 CORPORATION STOP	25.000	EACH
81	715-04750 CORPORATION STOP	2.000	EACH
82	715-04750 CORPORATION STOP	1.000	EACH
83	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	4,463.000	LFT
84	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	100.000	LFT
85	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	100.000	LFT
86	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	100.000	LFT
87	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,312.000	LFT
88	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	54.000	LFT
89	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,226.000	LFT
90	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	633.000	LFT
91	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	573.000	LFT
92	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	100.000	LFT
93	715-05331 PIPE, TYPE 2 DEFORMED MIN AREA 3.3 SFT	55.000	LFT
94	715-07794 WATER MAIN CONNECTIONS	1.000	EACH
95	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	153.000	TON
96	715-09064 VIDEO INSPECTION FOR PIPE	3,853.000	LFT
97	715-11571 WATER MAIN, DUCTILE IRON 8 IN	192.000	LFT
98	715-46000 PIPE END SECTION, DIA 12"	2.000	EACH

CALL ORDER : 201

CONTRACT ID : R -33673-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPAIR OR REHABILITATION		
99	715-46005 PIPE END SECTION, DIA 15"	1.000	EACH
100	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
101	715-96669 WATER MAIN, DUCTILE IRON, 16 IN	2,786.000	LFT
102	715-97873 WATER SERVICE LINE, 1 IN	871.000	EACH
103	716-07634 PIPE INSTALLATION, TRENCHLESS, 30 IN	282.000	LFT
104	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
105	718-52610 AGGREGATE FOR UNDERDRAINS	390.000	CYS
106	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,349.000	SYS
107	719-93923 DUCTILE IRON FITTINGS	17,558.000	LBS
108	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
109	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
110	720-45075 INLET, R13	1.000	EACH
111	720-45410 MANHOLE, C4	21.000	EACH
112	720-45431 MANHOLE, J	10.000	EACH
113	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	10.000	LFT
114	720-94612 MANHOLE, K4	1.000	EACH
115	720-94847 INLET, R13, MODIFIED	10.000	EACH
116	720-95422 MANHOLE, J4	4.000	EACH
117	720-96999 FIRE HYDRANT ASSEMBLY	11.000	EACH
118	720-98174 INLET, B15	2.000	EACH
119	720-98363 CATCH BASIN, MODIFIED	1.000	EACH
120	720-98555 INLET, C15	1.000	EACH
121	720-99416 CATCH BASIN, B15	19.000	EACH
122	720-99417 CATCH BASIN, C15	12.000	EACH
123	732-03944 BACKFLOW PREVENTER	1.000	EACH
124	732-11811 MODULAR BLOCK WALL ERECTION	81.000	SFT
125	732-11812 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	81.000	SFT
126	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
127	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
128	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	28,437.000	LFT
129	801-06213 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	6.000	EACH
130	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	70.000	LFT
131	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
132	801-06645 CONSTRUCTION SIGN, B	9.000	EACH
133	801-06710 FLASHING ARROW SIGN	250.000	DAY
134	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
135	801-07118 BARRICADE, III-A	396.000	LFT
136	801-07119 BARRICADE, III-B	36.000	LFT
137	801-94295 SIGNAL HEAD, RELOCATE	2.000	EACH
138	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	212.000	LFT
139	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	152.000	SFT
140	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
141	805-01815 SIGNAL POLE FOUNDATION, 36 IN X 144 IN	1.000	EACH
142	805-01842 HANDHOLE, SIGNAL, TYPE 1	3.000	EACH
143	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN	5,026.000	LFT
144	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
145	805-02150 PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN	2.000	EACH
146	805-02645 SIGNAL PEDESTAL FOUNDATION, A	1.000	EACH
147	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	1.000	EACH

CALL ORDER : 201

CONTRACT ID : R -33673-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REPAIR OR REHABILITATION			
148	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	2.000	EACH
149	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
150	805-78205 TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN	3.000	EACH
151	805-78230 TRAFFIC SIGNAL HEAD, 5 SECTION, 12"	1.000	EACH
152	805-78370 PEDESTRIAN PUSH BUTTON, NON-APS	2.000	EACH
153	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
154	805-78420 DISCONNECT HANGER	2.000	EACH
155	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	3,126.000	LFT
156	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	350.000	LFT
157	805-78490 SIGNAL CABLE, CONTROL, COPPER 7C/14GA	418.000	LFT
158	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	873.000	LFT
159	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
160	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,307.000	LFT
161	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	1.000	EACH
162	805-90005 SIGNAL POLE, PEDESTAL, 10 FT	1.000	EACH
163	807-02191 HANDHOLE, LIGHTING	4.000	EACH
164	807-02817 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	29.000	EACH
165	807-03950 LUMINAIRE, ORNAMENTAL	29.000	EACH
166	807-03951 LIGHT POLE, ORNAMENTAL	29.000	EACH
167	807-86805 SERVICE POINT, I	2.000	EACH
168	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	1,276.000	LFT
169	807-86910 CONNECTOR KIT, UNFUSED	29.000	EACH
170	807-86915 CONNECTOR KIT, FUSED	29.000	EACH
171	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	63.000	EACH
172	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
173	807-86930 INSULATION LINK, NON-WATERPROOFED	66.000	EACH
174	807-86935 INSULATION LINK, WATERPROOFED	20.000	EACH
175	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, 4 1/C	5,006.000	LFT
176	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	7.000	EACH
177	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,020.000	LFT
178	808-06716 LINE, REMOVE	2,109.000	LFT
179	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	900.000	LFT
180	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,304.000	LFT
181	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	127.000	LFT
182	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	518.000	LFT
183	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	13.000	EACH
184	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	13.000	EACH
185	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
186	808-75350 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH

CALL ORDER : 701

CONTRACT ID : T -33756-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW FLASHER INSTALLATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	46.000	SYS
14	203-02000 EXCAVATION, COMMON	68.000	CYS
15	205-06937 TEMPORARY SILT FENCE	100.000	LFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	23.000	SYS
17	211-09265 STRUCTURAL BACKFILL, TYPE 2	1.000	CYS
18	303-01180 COMPACTED AGGREGATE, NO. 53	134.000	TON
19	304-07490 HMA PATCHING, TYPE B	122.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,445.000	SYS
21	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	120.000	TON
22	406-05520 ASPHALT FOR TACK COAT	0.150	TON
23	604-06070 SIDEWALK, CONCRETE	126.000	SYS
24	604-06070 SIDEWALK, CONCRETE	11.000	SYS
25	604-07823 STAMPED CONCRETE SIDEWALK	296.000	SYS
26	604-07894 CURB RAMP, CONCRETE, A	54.000	SYS
27	604-07896 CURB RAMP, CONCRETE, B	13.000	SYS
28	604-07897 CURB RAMP, CONCRETE, C	30.000	SYS
29	604-07901 CURB RAMP, CONCRETE, G	6.000	SYS
30	604-07901 CURB RAMP, CONCRETE, G	16.000	SYS
31	604-07902 CURB RAMP, CONCRETE, H	6.000	SYS
32	604-07904 CURB RAMP, CONCRETE, L	48.000	SYS
33	605-06120 CURB, CONCRETE	695.000	LFT
34	605-06140 CURB AND GUTTER, CONCRETE	60.000	LFT
35	605-06235 CENTER CURB, D, CONCRETE, MODIFIED	10.000	LFT
36	610-08446 PCCP FOR APPROACHES, 6 IN	23.000	SYS
37	621-06565 MULCHING MATERIAL	0.100	TON
38	621-06570 TOPSOIL	10.000	CYS
39	621-06574 SODDING	20.000	SYS
40	621-06734 WILD FLOWERS PLUG PLANTING	50.000	EACH
41	622-04648 TREE GRATE	4.000	EACH
42	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	4.000	EACH
43	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	15.000	LFT
44	720-44296 INLET, CAP	1.000	EACH
45	720-45030 INLET, E7	1.000	EACH
46	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,350.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
49	801-06645 CONSTRUCTION SIGN, B	29.000	EACH

CALL ORDER : 701

CONTRACT ID : T -33756-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW FLASHER INSTALLATION		
50	801-06710 FLASHING ARROW SIGN	30.000	DAY
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	801-07119 BARRICADE, III-B	132.000	LFT
53	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	160.000	LFT
54	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	3.000	EACH
55	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	8.000	SFT
56	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	94.000	SFT
57	802-11843 SIGN, SHEET, WITH SPEED DISPLAY	1.000	EACH
58	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
59	805-02150 PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN	8.000	EACH
60	805-02645 SIGNAL PEDESTAL FOUNDATION, A	12.000	EACH
61	805-06595 CONDUIT, PVC, 2 IN	40.000	LFT
62	805-11799 RECTANGULAR RAPID FLASHING BEACON	10.000	EACH
63	805-11817 PEDESTRIAN PUSH BUTTON, APS	8.000	EACH
64	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	210.000	LFT
65	805-78480 SIGNAL CABLE, CONTROL, COPPER 3C/14GA	120.000	LFT
66	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	120.000	LFT
67	808-02157 PAVEMENT MESSAGE MARKING, REMOVE	11.000	EACH
68	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	3.000	EACH
69	808-03439 TRANSVERSE MARKING THERMOPLASTIC	208.000	LFT
70	808-06609 PAVEMENT MESSAGE MARKING,	1.000	EACH
71	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	292.000	LFT
72	808-06716 LINE, REMOVE	2,360.000	LFT
73	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	10.000	LFT
74	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,994.000	LFT
75	808-10042 TRANSVERSE MARKING MULTI-COMPONENT,	565.000	LFT
76	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	80.000	LFT
77	808-10097 TRANSVERSE MARKINGS, MULTI-COMPONENT,	32.000	LFT
78	808-10099 TRANSVERSE MARKINGS, MULTI-COMPONENT,	418.000	LFT
79	808-11698 TRANSVERSE MARKINGS, THERMOPLASTIC	56.000	LFT
80	808-74815 TRANSVERSE MARKING, THERMOPLASTIC,	211.000	LFT
81	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	695.000	LFT
82	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT
83	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH