

**Schedule of Pav Items Letting Date September 8, 2021 Letting ID 210908**

Call: 325

Contract: B -43990-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0010	203-02000	EXCAVATION, COMMON	580.00 CYS
0011	207-12498	SUBGRADE TREATMENT, TYPE ID	1320.00 SYS
0012	211-09264	STRUCTURE BACKFILL, TYPE 1	2.00 CYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	218.00 TON
0014	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	111.00 TON
0015	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	270.00 TON
0016	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	447.00 TON
0017	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0018	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1485.00 LFT
0019	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00 LS
0020	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0021	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00 LS
0022	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00 LS
0023	702-51863	FIELD DRILLED HOLE IN CONCRETE	32.00 EACH
0024	703-06029	REINFORCING BARS, EPOXY COATED	8796.00 LBS
0025	704-51002	CONCRETE, C, SUPERSTRUCTURE	27.80 CYS
0026	706-11600	RAILING, CONCRETE FC	9.30 CYS
0027	709-51821	SURFACE SEAL	1.00 LS
0028	711-04297	STRUCTURAL STEEL, FIELD CUT	79.00 SQIN
0029	711-05396	REPLACE	1.00 LS
0030	711-51035	STRUCTURAL STEEL	1229.00 LBS
0031	711-51864	DRILLED HOLE	641.00 EACH
0032	711-51866	RIVET, REMOVE	493.00 EACH
0033	711-51877	JACKING AND SUPPORTING, BEAMS	1.00 LS
0034	711-96479	BOLT, REMOVE	189.00 EACH
0035	711-96800	STUD SHEAR CONNECTORS	270.00 EACH

0036	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1485.00	LFT
0037	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	246.00	LFT
0038	718-06526	HMA FOR UNDERDRAINS	145.00	TON
0039	718-06528	OUTLET PROTECTOR, 1	4.00	EACH
0040	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	1019.00	SYS
0041	718-52610	AGGREGATE FOR UNDERDRAINS	134.00	CYS
0042	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0043	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11793.00	LFT
0044	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0045	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0046	801-06710	FLASHING ARROW SIGN	15.00	DAY
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07118	BARRICADE, III-A	72.00	LFT
0049	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1170.00	LFT
0050	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0051	808-06716	LINE, REMOVE	5760.00	LFT
0052	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1587.00	LFT
0053	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2199.00	LFT
0054	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1224.00	LFT
0055	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	200.00	LFT
0056	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	550.00	LFT
0057	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	26.00	EACH
0058	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	26.00	EACH