

Schedule of Pav Items Letting Date September 15, 2021 Letting ID 210915

Call: 100

Contract: R -38979-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	18.00	LFT
0013	202-96133	PIPE, REMOVE	216.00	LFT
0014	203-02000	EXCAVATION, COMMON	545.00	CYS
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	7250.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51220	EXCAVATION, WET	78.00	CYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	749.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	25.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	80.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	173.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	13.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	88.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	39.00	TON
0027	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	10.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	20.00	SYS
0032	401-10258	JOINT ADHESIVE, SURFACE	546.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	546.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	546.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0036	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0037	616-05689	RIPRAP, CLASS 2	197.00	TON
0038	616-06405	RIPRAP, REVETMENT	26.00	TON

0039	616-06405	RIPRAP, REVETMENT	79.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	110.00	SYS
0041	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	58.00	SYS
0042	621-02770	EROSION CONTROL BLANKET	440.00	SYS
0043	621-06559	MULCHED SEEDING R	440.00	SYS
0044	621-06567	WATER	1.00	KGAL
0045	621-06574	SODDING	52.00	SYS
0046	628-09401	FIELD OFFICE, A	4.00	MOS
0047	714-11682	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS 6 FT. X 4 FT.	92.00	LFT
0048	715-05841	CONCRETE ANCHOR, 60 IN.	1.00	EACH
0049	715-05908	PIPE EXTENSION, CIRCULAR, 60 IN.	18.00	LFT
0050	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	173.00	LFT
0051	801-03291	CONSTRUCTION SIGN, D	4.00	EACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	38.00	EACH
0055	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, III-A	60.00	LFT
0058	801-07119	BARRICADE, III-B	60.00	LFT
0059	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	339.00	LFT
0060	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	314.00	LFT
0061	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	76.00	TON
0062	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	98.00	TON
0063	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	316.00	TON
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH

Call: 101

Contract: R -39747-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0011	201-02245	TREE 6 IN., REMOVE	11.00 EACH
0012	201-02250	TREE 10 IN., REMOVE	5.00 EACH
0013	201-02255	TREE 18 IN., REMOVE	14.00 EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	56.00 SYS
0016	202-02278	CURB, CONCRETE, REMOVE	2028.00 LFT
0017	202-02279	CURB AND GUTTER, REMOVE	25.00 LFT
0018	202-02637	PIPE ABANDON AND GROUT FILL	54.00 LFT
0019	202-52710	SIDEWALK CONCRETE, REMOVE	875.00 SYS
0020	202-91385	INLET, REMOVE	2.00 EACH
0021	202-99080	CONCRETE, REMOVE	4.00 CYS
0022	203-02000	EXCAVATION, COMMON	2673.00 CYS
0023	203-02055	EMBANKMENT	209.00 CYS
0024	203-02070	BORROW	100.00 CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	30455.00 DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0027	205-12618	SWQCP PREPARATION	1.00 LS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	567.00 CYS
0029	206-51235	COFFERDAM	1.00 LS
0030	207-08264	SUBGRADE TREATMENT, TYPE II	1002.00 SYS
0031	207-08266	SUBGRADE TREATMENT, TYPE III	11069.00 SYS
0032	211-06467	AGGREGATE FOR END BENT BACKFILL	61.00 CYS
0033	211-09264	STRUCTURE BACKFILL, TYPE 1	105.00 CYS
0034	211-09266	STRUCTURE BACKFILL, TYPE 3	149.00 CYS
0035	301-12234	COMPACTED AGGREGATE NO. 53	2000.00 CYS
0036	304-07493	WIDENING WITH HMA, TYPE B	1138.00 TON
0037	304-12623	HMA PATCHING FULL DEPTH TYPE B	9.80 TON
0038	306-08039	MILLING, ASPHALT REMOVAL	227.00 SYS
0039	401-10258	JOINT ADHESIVE, SURFACE	3000.00 LFT
0040	406-05521	ASPHALT FOR TACK COAT	8629.00 SYS
0041	601-02241	GUARDRAIL, REMOVE	155.00 LFT
0042	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	309.00 LFT
0043	601-94690	GUARDRAIL, END TREATMENT, MS	2.00 EACH
0044	603-91714	FENCE, RAIL WOOD	254.00 LFT
0045	604-05528	HMA FOR SIDEWALK	1218.00 TON
0046	604-08086	CURB RAMP, CONCRETE	600.00 SYS
0047	604-12083	DETECTABLE WARNING SURFACES	87.00 SYS
0048	605-02493	CURB, ISLAND CONCRETE	15.00 SYS
0049	605-06120	CURB, CONCRETE	3523.00 LFT
0050	605-06140	CURB AND GUTTER, CONCRETE	10.00 LFT
0051	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	50.00 SYS
0052	616-05688	RIPRAP, CLASS 1	122.00 TON

0053	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	76.00	SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0055	621-02770	EROSION CONTROL BLANKET	13685.00	SYS
0056	621-06559	MULCHED SEEDING R	13685.00	SYS
0057	621-06560	MULCHED SEEDING U	13685.00	SYS
0058	621-06570	TOPSOIL	1059.00	CYS
0059	628-09401	FIELD OFFICE, A	12.00	MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0061	628-12685	TELEPHONE SERVICE, A	12.00	MOS
0062	701-08122	PILE, STEEL PIPE, 0.375 IN., 14 IN.	938.00	LFT
0063	701-09558	TEST PILE, INDICATOR, PRODUCTION	174.00	LFT
0064	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00	EACH
0065	701-09679	CONICAL PILE TIP, 14 IN.	24.00	EACH
0066	702-51001	CONCRETE, A, SUPERSTRUCTURE	15.00	CYS
0067	702-51005	CONCRETE, A, SUBSTRUCTURE	71.60	CYS
0068	702-51015	CONCRETE, B, FOOTINGS	29.80	CYS
0069	703-06029	REINFORCING BARS, EPOXY COATED	15373.00	LBS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	711-04845	BRIDGE STEEL TRUSS PRE-ENGINEERED	1.00	LS
0072	714-11124	GEOCOMPOSITE WALL DRAIN	476.00	SFT
0073	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	206.00	LFT
0074	715-05407	PIPE, END BENT DRAIN, 6 IN.	108.00	LFT
0075	715-05435	PIPE, UNDERDRAIN, OUTLET 4 IN.	230.00	LFT
0076	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	7.00	EACH
0077	720-45230	CATCH BASIN, D6	13.00	EACH
0078	720-45410	MANHOLE, C4	3.00	EACH
0079	720-96995	CLEAN INLET	10.00	EACH
0080	724-03855	EXPANSION JOINT SLIDING PLATE	56.00	LFT
0081	732-11810	MODULAR BLOCK WALL	143.00	SFT
0082	732-11811	MODULAR BLOCK WALL ERECTION	1024.00	SFT
0083	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	881.00	SFT
0084	801-03290	CONSTRUCTION SIGN, C	11.00	EACH
0085	801-03291	CONSTRUCTION SIGN, D	11.00	EACH
0086	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	500.00	LFT
0087	801-06710	FLASHING ARROW SIGN	120.00	DAY
0088	801-06775	MAINTAINING TRAFFIC	1.00	LS
0089	802-03821	SIGN, SHEET, WITH LEGEND,	38.00	EACH
0090	802-03821	SIGN, SHEET, WITH LEGEND,	17.00	EACH
0091	802-03821	SIGN, SHEET, WITH LEGEND,	20.00	EACH
0092	802-03821	SIGN, SHEET, WITH LEGEND,	26.00	EACH
0093	802-03821	SIGN, SHEET, WITH LEGEND,	3.00	EACH
0094	802-03821	SIGN, SHEET, WITH LEGEND,	5.00	EACH

0095	802-03821	SIGN, SHEET, WITH LEGEND,	6.00 EACH
0096	802-03821	SIGN, SHEET, WITH LEGEND,	6.00 EACH
0097	802-03821	SIGN, SHEET, WITH LEGEND,	6.00 EACH
0098	802-03821	SIGN, SHEET, WITH LEGEND,	5.00 EACH
0099	802-03821	SIGN, SHEET, WITH LEGEND,	6.00 EACH
0100	802-03821	SIGN, SHEET, WITH LEGEND,	1.00 EACH
0101	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	47.00 LFT
0102	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	332.00 LFT
0103	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00 EACH
0104	805-01842	HANDHOLE SIGNAL TYPE 1	2.00 EACH
0105	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	110.00 LFT
0106	805-02079	CONTROLLER CABINET FOUNDATION, A	1.00 EACH
0107	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00 EACH
0108	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT.	2.00 EACH
0109	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	2.00 EACH
0110	805-11496	PEDESTRIAN HYBRID BEACON	2.00 EACH
0111	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00 EACH
0112	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	2.00 EACH
0113	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	315.00 LFT
0114	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2849.00 LFT
0115	808-06716	LINE, REMOVE	1045.00 LFT
0116	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	7480.00 LFT
0117	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	35.00 LFT
0118	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	41.00 LFT
0119	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	10.00 EACH

Call: 121

Contract: R -40359-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	203-02000	EXCAVATION, COMMON	1225.00	CYS

0012	203-02070	BORROW	425.00	CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	14200.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	205-12618	SWQCP PREPARATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	576.00	SYS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	2092.00	SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	99.00	CYS
0019	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	209.00	SYS
0020	301-12232	COMPACTED AGGREGATE NO. 5	35.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	131.00	CYS
0022	304-07493	WIDENING WITH HMA, TYPE B	106.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1352.00	SYS
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	252.00	TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	313.00	TON
0026	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	460.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	905.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	355.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	905.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0031	610-07487	HMA FOR APPROACHES, TYPE B	127.00	TON
0032	611-06497	MAILBOX ASSEMBLY, SINGLE	7.00	EACH
0033	615-06490	RIGHT-OF-WAY MARKER	11.00	EACH
0034	615-06505	MONUMENT, B	3.00	EACH
0035	616-06405	RIPRAP, REVETMENT	7.00	TON
0036	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	21.00	SYS
0037	621-06575	SODDING, NURSERY	7536.00	SYS
0038	628-09403	FIELD OFFICE, C	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0040	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	92.00	LFT
0041	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	201.00	LFT
0042	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	289.00	LFT
0043	715-09064	VIDEO INSPECTION FOR PIPE	92.00	LFT
0044	715-46005	PIPE END SECTION, DIAMETER 15 IN.	14.00	EACH
0045	720-45410	MANHOLE, C4	1.00	EACH
0046	801-03290	CONSTRUCTION SIGN, C	6.00	EACH
0047	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0048	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1000.00	LFT
0049	801-06625	DETOUR ROUTE MARKER ASSEMBLY	33.00	EACH
0050	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0051	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0052	801-06775	MAINTAINING TRAFFIC	1.00	LS
0053	801-07118	BARRICADE, III-A	72.00	LFT

0054	801-07119	BARRICADE, III-B	48.00	LFT
0055	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	24.00	LFT
0056	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	16.00	LFT
0057	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	18.75	SFT
0058	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	8.00	SFT
0059	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	39.00	SFT
0060	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0061	805-01842	HANDHOLE SIGNAL TYPE 1	7.00	EACH
0062	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0063	805-03978	EMERGENCY VEHICLE PREEMPTION DETECTOR, SINGLE CHANNEL, ONE DIRECTION	3.00	EACH
0064	805-03980	EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	3.00	EACH
0065	805-03985	DETECTOR CABLE 3C 20GA.	511.00	LFT
0066	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	1556.00	LFT
0067	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	6.00	EACH
0068	805-78415	SPAN, CATENARY, AND TETHER	3.00	EACH
0069	805-78420	DISCONNECT HANGER	3.00	EACH
0070	805-78445	SIGNAL SERVICE	1.00	EACH
0071	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	124.00	LFT
0072	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2142.00	LFT
0073	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	320.00	LFT
0074	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	110.00	LFT
0075	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	84.00	LFT
0076	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GA	458.00	LFT
0077	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2444.00	LFT
0078	805-78785	SIGNAL DETECTOR HOUSING	7.00	EACH
0079	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1042.00	LFT
0080	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0081	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	4.00	EACH
0082	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.00	EACH
0083	805-95568	CONDUIT, PVC, 4 IN.	70.00	LFT
0084	807-86810	SERVICE POINT, II	1.00	EACH
0085	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1779.00	LFT
0086	808-12032	GROOVING FOR PAVEMENT MARKINGS	3149.00	LFT
0087	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1370.00	LFT
0088	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	48.00	LFT
0089	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00	EACH

Call: 131

Contract: R -40493-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line

Item No Item Code Description

Quantity Unit

0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02272	PAVED SIDE DITCH, REMOVE	7.00	LFT
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-96133	PIPE, REMOVE	5.00	LFT
0016	202-99187	FENCE, FARM FIELD, REMOVE	50.00	LFT
0017	203-02000	EXCAVATION, COMMON	130.00	CYS
0018	203-02070	BORROW	5.00	CYS
0019	205-11626	PUMP AROUND	6.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	28770.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	87.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	165.00	CYS
0025	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	203.00	SYS
0026	301-12232	COMPACTED AGGREGATE NO. 5	18.00	CYS
0027	301-12234	COMPACTED AGGREGATE NO. 53	18.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	55.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	400.00	SYS
0030	306-08038	MILLING, ASPHALT, 4 IN.	694.00	SYS
0031	306-08043	MILLING, TRANSITION	840.00	SYS
0032	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	180.00	TON
0033	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	118.00	TON
0034	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	48.00	TON
0035	401-10258	JOINT ADHESIVE, SURFACE	1663.00	LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	693.00	LFT
0037	401-11785	LIQUID ASPHALT SEALANT	1633.00	LFT
0038	406-05521	ASPHALT FOR TACK COAT	3061.00	SYS
0039	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0040	603-06060	FENCE, FARM FIELD, RESET	120.00	LFT
0041	610-07487	HMA FOR APPROACHES, TYPE B	2.00	TON
0042	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH

0043	616-05688	RIPRAP, CLASS 1	207.00	TON
0044	616-05689	RIPRAP, CLASS 2	177.00	TON
0045	616-06405	RIPRAP, REVETMENT	18.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	299.00	SYS
0047	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	266.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	11.00	EACH
0049	621-06559	MULCHED SEEDING R	5144.00	SYS
0050	628-09403	FIELD OFFICE, C	9.00	MOS
0051	703-08247	EMBEDDED GALVANIC ANODE	510.00	EACH
0052	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0053	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	110.00	LFT
0054	715-05841	CONCRETE ANCHOR, 60 IN.	2.00	EACH
0055	715-06004	CONCRETE ANCHOR, 48 IN.	3.00	EACH
0056	715-06566	PIPE EXTENSION, CIRCULAR, 6 IN.	20.00	LFT
0057	715-07090	CONCRETE ANCHOR, MIN. AREA 11.6 SFT	2.00	EACH
0058	715-12585	PIPE EXTENSION, DEFORMED, MIN. AREA 11.6 SFT	5.00	LFT
0059	715-12601	CONCRETE ANCHOR, MIN. AREA 55 SFT	2.00	EACH
0060	715-95325	INVERT, CONCRETE PAVED	204.00	LFT
0061	716-07634	PIPE INSTALLATION, TRENCHLESS, 30 IN.	156.00	LFT
0062	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	210.00	LFT
0063	718-08308	UNDERDRAIN PATCHING	52.00	LFT
0064	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	140.00	LFT
0065	725-10226	LINER PIPE, THERMOPLASTIC, CIRCULAR, 13.9-14.1 SFT	188.00	LFT
0066	725-12511	LINER PIPE, THERMOPLASTIC, DEFORMED, 8.9-9.1 SFT	157.00	LFT
0067	725-12786	PIPE LINER, CURED-IN-PLACE, MIN AREA 11.6 SFT	160.00	LFT
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	73.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07118	BARRICADE, III-A	84.00	LFT
0074	801-07119	BARRICADE, III-B	168.00	LFT
0075	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	60.00	LFT
0076	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	422.00	LFT

Call: 141

Contract: R -40562-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL

0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	59.00	LFT
0013	203-02000	EXCAVATION, COMMON	680.00	CYS
0014	203-02070	BORROW	845.00	CYS
0015	205-11626	PUMP AROUND	3.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	11000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	252.00	SYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	384.00	SYS
0021	211-02050	B BORROW	265.00	CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	45.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	875.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	435.00	CYS
0025	301-12232	COMPACTED AGGREGATE NO. 5	137.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	323.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	365.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1861.00	SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	201.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	52.00	TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	128.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	760.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	135.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	760.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	2770.00	SYS
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.00	TON
0037	601-02241	GUARDRAIL, REMOVE	470.00	LFT
0038	610-07487	HMA FOR APPROACHES, TYPE B	62.00	TON
0039	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0040	615-06490	RIGHT-OF-WAY MARKER	26.00	EACH
0041	615-06505	MONUMENT, B	7.00	EACH
0042	616-05688	RIPRAP, CLASS 1	120.00	TON
0043	616-05689	RIPRAP, CLASS 2	48.00	TON
0044	616-06405	RIPRAP, REVETMENT	161.00	TON

0045	616-06451	RIPRAP, UNIFORM	22.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	93.00	SYS
0047	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1393.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0049	621-06559	MULCHED SEEDING R	2727.00	SYS
0050	621-06567	WATER	3.00	KGAL
0051	621-06574	SODDING	525.00	SYS
0052	628-09403	FIELD OFFICE, C	12.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0054	714-12449	STRUCTURE COATED REINFORCED CONCRETE BOX SECTION 21 FT X 7 FT	52.00	LFT
0055	714-12457	STRUCTURE REINFORCED CONCRETE BOX SECTION 20 X 6 FT	81.00	LFT
0056	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	42.00	LFT
0057	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	62.00	LFT
0058	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0059	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0060	725-12452	PIPE LINER, CURED-IN-PLACE 69 IN	61.00	LFT
0061	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0062	801-06625	DETOUR ROUTE MARKER ASSEMBLY	67.00	EACH
0063	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0064	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0065	801-06775	MAINTAINING TRAFFIC	1.00	LS
0066	801-07118	BARRICADE, III-A	96.00	LFT
0067	801-07119	BARRICADE, III-B	156.00	LFT
0068	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	41.00	SFT
0069	802-76055	SIGN POST, A	53.00	LFT
0070	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1520.00	LFT
0071	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1520.00	LFT
0072	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	19.00	EACH
0073	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	19.00	EACH

Call: 151

Contract: R -40842-A

Section No.: 1 ADDED TRAVEL LANES

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL

0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	232.00	SYS
0014	202-02272	PAVED SIDE DITCH, REMOVE	882.00	LFT
0015	202-02273	CENTER CURB, CONCRETE, REMOVE	7.00	SYS
0016	202-02278	CURB, CONCRETE, REMOVE	304.00	LFT
0017	202-02279	CURB AND GUTTER, REMOVE	621.00	LFT
0018	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0019	202-52710	SIDEWALK CONCRETE, REMOVE	140.00	SYS
0020	202-90277	DETECTOR HOUSING, REMOVE	17.00	EACH
0021	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00	EACH
0022	202-94810	CURB TURNOUT, REMOVE	3.00	EACH
0023	203-02000	EXCAVATION, COMMON	23205.00	CYS
0024	203-02070	BORROW	43152.00	CYS
0025	203-51223	EXCAVATION, WATERWAY	31.00	CYS
0026	204-02290	SETTLEMENT PLATE	2.00	EACH
0027	205-11626	PUMP AROUND	1.00	EACH
0028	205-12108	STORMWATER MANAGEMENT BUDGET	122258.00	DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0030	205-12618	SWQCP PREPARATION	1.00	LS
0031	207-08264	SUBGRADE TREATMENT, TYPE II	311.00	SYS
0032	207-08266	SUBGRADE TREATMENT, TYPE III	316.00	SYS
0033	207-09935	SUBGRADE TREATMENT, TYPE IC	26015.00	SYS
0034	207-12498	SUBGRADE TREATMENT, TYPE ID	9873.00	SYS
0035	207-12635	SUBGRADE TREATMENT, TYPE IBC	5944.00	SYS
0036	211-02050	B BORROW	9199.00	CYS
0037	211-09264	STRUCTURE BACKFILL, TYPE 1	1672.00	CYS
0038	211-09265	STRUCTURE BACKFILL, TYPE 2	129.00	CYS
0039	211-09266	STRUCTURE BACKFILL, TYPE 3	11687.00	CYS
0040	211-09268	STRUCTURE BACKFILL, TYPE 5	28.00	CYS
0041	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	1912.00	SYS
0042	301-12231	COMPACTED AGGREGATE NO. 2	4705.00	CYS
0043	301-12233	COMPACTED AGGREGATE NO. 8	9.00	CYS
0044	302-06464	SUBBASE FOR PCCP	168.00	CYS
0045	303-01180	COMPACTED AGGREGATE NO. 53	105.00	TON
0046	306-08034	MILLING, ASPHALT, 1 1/2 IN.	7322.00	SYS
0047	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2799.00	TON
0048	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4374.00	TON
0049	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	10533.00	TON

0050	401-10258	JOINT ADHESIVE, SURFACE	20613.00	LFT
0051	401-10259	JOINT ADHESIVE, INTERMEDIATE	16533.00	LFT
0052	401-11785	LIQUID ASPHALT SEALANT	20613.00	LFT
0053	406-05520	ASPHALT FOR TACK COAT	29.00	TON
0054	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0055	502-06329	PCCP, 12 IN.	1.00	SYS
0056	503-12477	TERMINAL JOINT, TYPE HMA	96.00	LFT
0057	601-02241	GUARDRAIL, REMOVE	3266.00	LFT
0058	601-06035	GUARDRAIL, RESET	419.00	LFT
0059	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	457.00	LFT
0060	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0061	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0062	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	150.00	LFT
0063	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	69.00	LFT
0064	601-99123	GUARDRAIL, TRANSITION, GP	4.00	EACH
0065	603-06045	FENCE, CHAIN LINK, 48 IN.	440.00	LFT
0066	604-06070	SIDEWALK, CONCRETE	4933.00	SYS
0067	604-08086	CURB RAMP, CONCRETE	154.00	SYS
0068	604-12083	DETECTABLE WARNING SURFACES	63.00	SYS
0069	604-92237	HAND RAIL, STEEL	402.00	LFT
0070	605-06140	CURB AND GUTTER, CONCRETE	7982.00	LFT
0071	605-06235	CENTER CURB, D CONCRETE MODIFIED	7.00	LFT
0072	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	24.00	LFT
0073	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	116.00	LFT
0074	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	725.60	SYS
0075	610-07488	HMA FOR APPROACHES, TYPE C	933.00	TON
0076	610-08446	PCCP FOR APPROACHES, 6 IN.	98.00	SYS
0077	610-09108	PCCP FOR APPROACHES, 9 IN.	213.00	SYS
0078	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0079	615-06505	MONUMENT, B	13.00	EACH
0080	616-06405	RIPRAP, REVETMENT	829.00	TON
0081	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	442.00	SYS
0082	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	1828.00	SYS
0083	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0084	621-02770	EROSION CONTROL BLANKET	14193.00	SYS
0085	621-06545	FERTILIZER	6.00	TON
0086	621-06554	SEED MIXTURE U	3031.00	LBS
0087	621-06560	MULCHED SEEDING U	360.00	SYS
0088	621-06567	WATER	14.00	KGAL
0089	621-06574	SODDING	3487.00	SYS
0090	621-06575	SODDING, NURSERY	808.00	SYS
0091	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	110.00	EACH

0092	628-09403	FIELD OFFICE, C	15.00	MOS
0093	701-06011	DYNAMIC PILE LOAD TEST	3.00	EACH
0094	701-09557	TEST PILE, DYNAMIC, PRODUCTION	325.00	LFT
0095	701-09559	TEST PILE, DYNAMIC, RESTRIKE	3.00	EACH
0096	701-09683	PILE SHOE, HP 12 X 74	66.00	EACH
0097	701-95780	PILE, STEEL H, HP 12 X 74	6035.00	LFT
0098	702-04325	TEMPORARY SHORING	1.00	LS
0099	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0100	702-51005	CONCRETE, A, SUBSTRUCTURE	201.70	CYS
0101	702-51015	CONCRETE, B, FOOTINGS	116.40	CYS
0102	702-92857	CONCRETE, C, SUBSTRUCTURE	141.70	CYS
0103	703-06028	REINFORCING BARS	35204.00	LBS
0104	703-06029	REINFORCING BARS, EPOXY COATED	330550.00	LBS
0105	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	264.00	EACH
0106	704-51002	CONCRETE, C, SUPERSTRUCTURE	927.40	CYS
0107	706-11601	RAILING, CONCRETE FT	68.00	CYS
0108	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0109	707-09383	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 60 IN. X 61 IN.	2475.00	LFT
0110	709-51821	SURFACE SEAL	1.00	LS
0111	715-04596	WATER SERVICE	1.00	EACH
0112	715-04596	WATER SERVICE	1.00	EACH
0113	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	7279.00	LFT
0114	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	179.00	LFT
0115	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	48.00	LFT
0116	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1754.00	LFT
0117	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	749.00	LFT
0118	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	153.00	LFT
0119	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	142.00	LFT
0120	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	33.00	LFT
0121	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	984.00	LFT
0122	715-09064	VIDEO INSPECTION FOR PIPE	3815.00	LFT
0123	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0124	715-10126	PIPE EXTENSION, DEFORMED, MIN. AREA 26 0 SFT	26.00	LFT
0125	715-46000	PIPE END SECTION, DIAMETER 12 IN.	10.00	EACH
0126	715-46005	PIPE END SECTION, DIAMETER 15 IN.	3.00	EACH
0127	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0128	715-46015	PIPE END SECTION, DIAMETER 21 IN.	2.00	EACH
0129	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0130	715-46030	PIPE END SECTION, DIAMETER 30 IN.	4.00	EACH
0131	715-91742	WATER METER RELOCATE	2.00	EACH
0132	718-06529	OUTLET PROTECTOR, 2	1.00	EACH
0133	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT

0134	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	5642.00	SYS
0135	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	328.00	SYS
0136	718-52610	AGGREGATE FOR UNDERDRAINS	4459.00	CYS
0137	720-01092	MANHOLE, J15 MODIFIED	5.00	EACH
0138	720-07309	TRENCH DRAIN	72.00	LFT
0139	720-45030	INLET, E7	2.00	EACH
0140	720-45035	INLET, F7	5.00	EACH
0141	720-45410	MANHOLE, C4	11.00	EACH
0142	720-90129	MANHOLE, J2	1.00	EACH
0143	720-94612	MANHOLE, K4	1.00	EACH
0144	720-95422	MANHOLE, J4	8.00	EACH
0145	720-98174	INLET, B15	33.00	EACH
0146	720-98555	INLET, C15	7.00	EACH
0147	720-99416	CATCH BASIN, B15	5.00	EACH
0148	722-51874	OVERLAY DAM	60.00	SFT
0149	731-93945	FACE PANELS, CONCRETE	14131.00	SFT
0150	731-93946	WALL ERECTION	14131.00	SFT
0151	731-93947	LEVELING PAD, CONCRETE	769.00	LFT
0152	735-10241	TEMPORARY WIRE FACING	2849.00	SFT
0153	735-10242	TEMPORARY WALL ERECTION	2849.00	SFT
0154	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0155	801-04308	ROAD CLOSURE SIGN ASSEMBLY	16.00	EACH
0156	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	4618.00	LFT
0157	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	40483.00	LFT
0158	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0159	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	462.00	LFT
0160	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	EACH
0161	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0162	801-06645	CONSTRUCTION SIGN, B	25.00	EACH
0163	801-06775	MAINTAINING TRAFFIC	1.00	LS
0164	801-07118	BARRICADE, III-A	598.00	LFT
0165	801-07119	BARRICADE, III-B	24.00	LFT
0166	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1200.00	LFT
0167	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0168	801-11662	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 12 IN.	65.00	LFT
0169	801-94295	SIGNAL HEAD RELOCATE	10.00	EACH
0170	802-03776	SIGN POST, WOOD 6 IN. X 6 IN.	21.00	LFT
0171	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0172	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	49.00	LFT
0173	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	35.00	LFT
0174	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00	EACH
0175	802-07060	SIGN, SHEET, RELOCATE	5.00	EACH

0176	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	8.00	SFT
0177	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	15.00	SFT
0178	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH
0179	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	3.00	EACH
0180	805-01842	HANDHOLE SIGNAL TYPE 1	16.00	EACH
0181	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	3.00	EACH
0182	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0183	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	21.00	EACH
0184	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0185	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	9.00	EACH
0186	805-04133	SIGNAL POLE, PEDESTAL, 12FT	9.00	EACH
0187	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	5268.00	LFT
0188	805-11817	PEDESTRIAN PUSH BUTTON, APS	21.00	EACH
0189	805-78415	SPAN, CATENARY, AND TETHER	5.00	EACH
0190	805-78420	DISCONNECT HANGER	5.00	EACH
0191	805-78445	SIGNAL SERVICE	1.00	EACH
0192	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	50.00	LFT
0193	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9496.00	LFT
0194	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	4570.00	LFT
0195	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	950.00	LFT
0196	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2550.00	LFT
0197	805-78785	SIGNAL DETECTOR HOUSING	24.00	EACH
0198	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3236.00	LFT
0199	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0200	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	3.00	EACH
0201	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.00	EACH
0202	808-01428	TEMPORARY TRANSVERSE MARKINGS WHITE STOP LINE 24 IN	88.00	LFT
0203	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	2358.00	LFT
0204	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2131.00	LFT
0205	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2334.00	LFT
0206	808-06716	LINE, REMOVE	6937.00	LFT
0207	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0208	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1855.00	LFT
0209	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	754.00	LFT
0210	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	338.00	LFT
0211	808-12032	GROOVING FOR PAVEMENT MARKINGS	2003.00	LFT
0212	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	958.00	LFT
0213	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9585.00	LFT
0214	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	135.00	LFT
0215	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	513.00	LFT
0216	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	21.00	EACH

Call: 161

Contract: R -41235-B

Section No.: 1

BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-03875	CONCRETE STEPS, REMOVE	1.00	EACH
0011	202-05571	TESTING FOR WASTES	1.00	EACH
0012	202-05571	TESTING FOR WASTES	1.00	EACH
0013	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	40.00	CYS
0014	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	40.00	CYS
0015	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	40.00	CYS
0016	202-09243	REGULATED MATERIALS, DISPOSE, TYPE Z	40.00	CYS
0017	202-09244	REGULATED MATERIALS, REMOVE, TYPE Z	40.00	CYS
0018	202-09245	REGULATED MATERIALS, TRANSPORT, TYPE Z	40.00	CYS
0019	202-52710	SIDEWALK CONCRETE, REMOVE	1815.00	SYS
0020	202-91922	STUMP, REMOVE	7.00	EACH
0021	203-02020	EXCAVATION, UNCLASSIFIED	150.00	CYS
0022	203-02070	BORROW	35.00	CYS
0023	205-12108	STORMWATER MANAGEMENT BUDGET	1840.00	DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	593.00	SYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	92.00	CYS
0027	214-11796	GEOGRID, TYPE IB	178.00	SYS
0028	302-07455	DENSE GRADED SUBBASE	106.00	CYS
0029	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	160.00	TON
0030	306-08033	MILLING, ASPHALT, 1 IN.	350.00	SYS
0031	402-07451	HMA WEDGE AND LEVEL, TYPE B	63.00	TON
0032	604-04740	PAVERS	17620.00	SFT
0033	604-06070	SIDEWALK, CONCRETE	191.00	SYS
0034	604-08086	CURB RAMP, CONCRETE	83.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	23.00	SYS
0036	605-02278	CURB, REMOVE	806.00	LFT
0037	605-06120	CURB, CONCRETE	974.00	LFT

0038	605-06125	CURB, CONCRETE, MODIFIED	361.00	LFT
0039	605-97937	CURB AND GUTTER, ROLL CURB	109.00	LFT
0040	610-08446	PCCP FOR APPROACHES, 6 IN.	415.00	SYS
0041	610-09108	PCCP FOR APPROACHES, 9 IN.	178.00	SYS
0042	618-03812	BENCH	10.00	EACH
0043	618-97672	TRASH RECEPTACLE	3.00	EACH
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0045	621-06545	FERTILIZER	1.00	TON
0046	621-06554	SEED MIXTURE U	20.00	LBS
0047	621-06565	MULCHING MATERIAL	1.00	TON
0048	621-06567	WATER	8.00	KGAL
0049	621-06570	TOPSOIL	76.00	CYS
0050	621-06575	SODDING, NURSERY	600.00	SYS
0051	622-03948	PLANTER	6.00	EACH
0052	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	5.00	EACH
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0054	628-11977	COMPUTER SYSTEM	2.00	EACH
0055	628-12683	FIELD OFFICE, D	10.00	MOS
0056	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	46.00	LFT
0057	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	58.00	LFT
0058	715-05408	PIPE, SANITARY SEWER, 8 IN.	100.00	LFT
0059	715-05711	PIPE, SANITARY SEWER, 6 IN.	100.00	LFT
0060	715-40000	PIPE, SANITARY SEWER, 4 IN.	100.00	LFT
0061	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EACH
0062	720-45005	INLET, A2	5.00	EACH
0063	720-45410	MANHOLE, C4	1.00	EACH
0064	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	5.00	EACH
0065	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	31.00	EACH
0067	801-06710	FLASHING ARROW SIGN	90.00	DAY
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS
0069	801-07118	BARRICADE, III-A	140.00	LFT
0070	802-04314	SIGN	2.00	EACH
0071	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	332.00	LFT
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	134.70	SFT
0073	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	63.00	SFT
0074	807-03951	LIGHT POLE ORNAMENTAL	10.00	EACH
0075	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	550.00	LFT
0076	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	30.00	LFT
0077	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	25.00	LFT
0078	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	460.00	LFT
0079	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ADA ACCESSIBLE SYMBOL	1.00	EACH

Call: 191

Contract: R -42054-A

Section No.: 1

ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02279	CURB AND GUTTER, REMOVE	42.00	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	25.00	SYS
0013	203-08607	LINEAR GRADING	1466.00	LFT
0014	205-12108	STORMWATER MANAGEMENT BUDGET	1.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-12498	SUBGRADE TREATMENT, TYPE ID	354.00	SYS
0017	208-02046	GRADING IN GORE AREA	1.00	EACH
0018	303-01180	COMPACTED AGGREGATE NO. 53	24.00	TON
0019	303-07449	COMPACTED AGGREGATE NO. 73	1692.00	TON
0020	304-12625	HMA PATCHING FULL DEPTH TYPE C	196.00	TON
0021	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	360.00	TON
0022	306-08036	MILLING, ASPHALT, 2 IN.	99940.00	SYS
0023	306-08432	MILLING, APPROACH	7885.00	SYS
0024	401-06264	PROFILOGRAPH, HMA	1.00	LS
0025	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	10993.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	40855.00	LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	6982.00	LFT
0028	401-11785	LIQUID ASPHALT SEALANT	40855.00	LFT
0029	406-05520	ASPHALT FOR TACK COAT	39.00	TON
0030	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.00	TON
0031	604-08086	CURB RAMP, CONCRETE	19.00	SYS
0032	604-12083	DETECTABLE WARNING SURFACES	5.00	SYS
0033	605-06120	CURB, CONCRETE	14.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	38.00	LFT
0035	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	65670.00	LFT
0036	610-07488	HMA FOR APPROACHES, TYPE C	742.00	TON

0037	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00	EACH
0038	621-06575	SODDING, NURSERY	17.00	SYS
0039	628-09403	FIELD OFFICE, C	7.00	MOS
0040	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0041	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0042	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0043	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	7.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0045	628-11977	COMPUTER SYSTEM	1.00	EACH
0046	628-12685	TELEPHONE SERVICE, A	7.00	MOS
0047	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	3.00	EACH
0048	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	99165.00	LFT
0049	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	99165.00	LFT
0050	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	240.00	LFT
0051	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	240.00	LFT
0052	801-06640	CONSTRUCTION SIGN, A	47.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-11661	TEMPORARY TRANSVERSE PAVEMENT MARKING, 8 IN.	150.00	LFT
0055	805-06595	CONDUIT, PVC, 2 IN.	85.00	LFT
0056	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	4420.00	LFT
0057	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	5100.00	LFT
0058	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1700.00	LFT
0059	807-98690	HANDHOLE ADJUSTED TO GRADE	3.00	EACH
0060	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	130.00	LFT
0061	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	19.00	EACH
0062	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0063	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	240.00	LFT
0064	808-10101	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 8 IN.	150.00	LFT
0065	808-12032	GROOVING FOR PAVEMENT MARKINGS	99165.00	LFT
0066	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	57645.00	LFT
0067	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	38525.00	LFT
0068	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	80.00	LFT
0069	808-75063	LINE, PREFORMED PLASTIC, BROKEN, YELLOW, 4 IN.	3000.00	LFT
0070	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	765.00	EACH
0071	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	172.00	EACH

Call: 201

Contract: R -42158-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS

0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-96133	PIPE, REMOVE	283.00	LFT
0014	203-02000	EXCAVATION, COMMON	1136.00	CYS
0015	203-02070	BORROW	686.00	CYS
0016	203-51223	EXCAVATION, WATERWAY	222.00	CYS
0017	205-11626	PUMP AROUND	5.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	4330.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	206-51220	EXCAVATION, WET	176.00	CYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	604.00	SYS
0023	211-02050	B BORROW	176.00	CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	121.00	CYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	740.00	CYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	80.00	CYS
0027	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	120.00	SYS
0028	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	255.00	SYS
0029	301-12232	COMPACTED AGGREGATE NO. 5	56.10	CYS
0030	301-12234	COMPACTED AGGREGATE NO. 53	102.10	CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	34.00	TON
0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	218.00	SYS
0033	306-08432	MILLING, APPROACH	239.00	SYS
0034	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	49.00	TON
0035	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	49.00	TON
0036	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	131.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	120.00	LFT
0038	401-10259	JOINT ADHESIVE, INTERMEDIATE	33.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	257.00	LFT
0040	406-05521	ASPHALT FOR TACK COAT	1202.00	SYS
0041	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0042	610-07487	HMA FOR APPROACHES, TYPE B	20.00	TON
0043	615-06490	RIGHT-OF-WAY MARKER	26.00	EACH

0044	615-06505	MONUMENT, B	2.00 EACH
0045	616-05688	RIPRAP, CLASS 1	142.00 TON
0046	616-05689	RIPRAP, CLASS 2	463.00 TON
0047	616-06405	RIPRAP, REVETMENT	702.00 TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	161.00 SYS
0049	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	1691.00 SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00 EACH
0051	621-06559	MULCHED SEEDING R	3501.00 SYS
0052	628-09403	FIELD OFFICE, C	12.00 MOS
0053	702-51005	CONCRETE, A, SUBSTRUCTURE	16.00 CYS
0054	702-51015	CONCRETE, B, FOOTINGS	19.00 CYS
0055	703-06029	REINFORCING BARS, EPOXY COATED	5348.00 LBS
0056	714-11176	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 6 FT.	80.00 LFT
0057	714-11184	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 7 FT.	94.00 LFT
0058	714-11311	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 5 FT.	74.00 LFT
0059	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	77.00 LFT
0060	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	20.00 LFT
0061	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	63.00 LFT
0062	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	56.00 LFT
0063	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	22.00 LFT
0064	715-06802	CONCRETE ANCHOR, MIN. AREA 18.1 SFT	2.00 EACH
0065	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	97.00 TON
0066	715-09890	PIPE, TYPE 1, DEFORMED, MIN. AREA 34.6 SFT	81.00 LFT
0067	715-10159	PIPE, TYPE 1, DEFORMED, MIN. AREA 19.3 SFT	79.00 LFT
0068	720-45030	INLET, E7	3.00 EACH
0069	720-45410	MANHOLE, C4	4.00 EACH
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	32.00 EACH
0071	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	32.00 EACH
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	135.00 EACH
0073	801-06640	CONSTRUCTION SIGN, A	85.00 EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00 LS
0075	801-07118	BARRICADE, III-A	288.00 LFT
0076	801-07119	BARRICADE, III-B	364.00 LFT
0077	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	13.00 LFT
0078	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00 EACH
0079	802-91122	SIGN GROUND MOUNTED RESET	1.00 EACH
0080	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	51.00 LFT
0081	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	440.00 LFT
0082	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	124.00 LFT

Call: 211

Contract: R -42465-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
0001		105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002		109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003		109-08360	CONTRACT LIENS	1.00	DOL
0004		109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005		109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006		109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007		109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008		110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009		201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010		202-96133	PIPE, REMOVE	11.00	LFT
0011		205-11626	PUMP AROUND	3.00	EACH
0012		205-12108	STORMWATER MANAGEMENT BUDGET	1290.00	DOL
0013		205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014		205-12618	SWQCP PREPARATION	1.00	LS
0015		207-12498	SUBGRADE TREATMENT, TYPE ID	112.00	SYS
0016		211-09264	STRUCTURE BACKFILL, TYPE 1	344.00	CYS
0017		616-05688	RIPRAP, CLASS 1	48.00	TON
0018		616-05689	RIPRAP, CLASS 2	50.00	TON
0019		616-06405	RIPRAP, REVETMENT	9.00	TON
0020		616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	48.00	SYS
0021		616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	87.00	SYS
0022		621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0023		621-06559	MULCHED SEEDING R	155.00	SYS
0024		628-09403	FIELD OFFICE, C	9.00	MOS
0025		714-11304	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 4 FT.	71.00	LFT
0026		715-05246	PIPE, TYPE 1, DEFORMED, MIN. AREA 14.7 SFT	128.00	LFT
0027		715-05840	CONCRETE ANCHOR, MIN. AREA 14.7SF	2.00	EACH
0028		715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	39.00	TON
0029		715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	73.00	TON
0030		715-12492	PIPE END SECTION, DIA 66 IN.	1.00	EACH
0031		718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	128.00	SYS
0032		725-10245	PERPETUATION, EXISTING PIPE	1.00	EACH
0033		725-11299	PIPE LINER, CURED-IN-PLACE, 66 IN	40.00	LFT
0034		801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0035		801-06625	DETOUR ROUTE MARKER ASSEMBLY	55.00	EACH
0036		801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0037		801-06775	MAINTAINING TRAFFIC	1.00	LS
0038		801-07118	BARRICADE, III-A	144.00	LFT
0039		801-07119	BARRICADE, III-B	204.00	LFT

Call: 221

Contract: R -42542-A

Section No.: 1

PAVEMENT REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	5.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	121.00	SYS
0016	202-02278	CURB, CONCRETE, REMOVE	1521.00	LFT
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-52710	SIDEWALK CONCRETE, REMOVE	1704.00	SYS
0019	202-93741	GUARDRAIL, END TREATMENT, REMOVE	11.00	EACH
0020	203-02000	EXCAVATION, COMMON	230.00	CYS
0021	203-08607	LINEAR GRADING	209.00	LFT
0022	205-12108	STORMWATER MANAGEMENT BUDGET	37336.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	206-51220	EXCAVATION, WET	1944.00	CYS
0026	206-51225	EXCAVATION, DRY	1104.00	CYS
0027	206-51235	COFFERDAM	1.00	LS
0028	207-08264	SUBGRADE TREATMENT, TYPE II	1346.00	SYS
0029	207-08266	SUBGRADE TREATMENT, TYPE III	124.00	SYS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	6998.50	SYS
0031	207-12635	SUBGRADE TREATMENT, TYPE IBC	17841.00	SYS
0032	211-06467	AGGREGATE FOR END BENT BACKFILL	1264.00	CYS
0033	211-09264	STRUCTURE BACKFILL, TYPE 1	2323.00	CYS
0034	211-09264	STRUCTURE BACKFILL, TYPE 1	2.00	CYS
0035	211-09268	STRUCTURE BACKFILL, TYPE 5	2.00	CYS
0036	214-11796	GEOGRID, TYPE IB	609.00	SYS

0037	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	1324.00	SYS
0038	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2500.00	SYS
0039	301-12232	COMPACTED AGGREGATE NO. 5	322.00	CYS
0040	301-12234	COMPACTED AGGREGATE NO. 53	419.00	CYS
0041	302-06464	SUBBASE FOR PCCP	60.00	CYS
0042	302-07455	DENSE GRADED SUBBASE	233.00	CYS
0043	303-01180	COMPACTED AGGREGATE NO. 53	1921.00	TON
0044	304-07493	WIDENING WITH HMA, TYPE B	67.00	TON
0045	304-12623	HMA PATCHING FULL DEPTH TYPE B	3470.00	TON
0046	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2084.00	SYS
0047	306-08043	MILLING, TRANSITION	1892.00	SYS
0048	306-08159	MILLING, ASPHALT	64864.00	SYS
0049	306-08432	MILLING, APPROACH	1130.00	SYS
0050	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	5507.00	TON
0051	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	9145.00	TON
0052	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	124.00	TON
0053	401-10258	JOINT ADHESIVE, SURFACE	28986.00	LFT
0054	401-10259	JOINT ADHESIVE, INTERMEDIATE	28892.00	LFT
0055	401-11785	LIQUID ASPHALT SEALANT	28986.00	LFT
0056	406-05520	ASPHALT FOR TACK COAT	37.00	TON
0057	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00	TON
0058	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0059	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00	EACH
0060	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	3.00	EACH
0061	601-02241	GUARDRAIL, REMOVE	2358.00	LFT
0062	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	2000.25	LFT
0063	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00	EACH
0064	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	3.00	EACH
0065	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0066	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0067	602-06729	BARRIER, DELINEATOR	6.00	EACH
0068	603-97461	TEMPORARY FENCE	251.00	LFT
0069	604-05528	HMA FOR SIDEWALK	16.00	TON
0070	604-06070	SIDEWALK, CONCRETE	2775.00	SYS
0071	604-08086	CURB RAMP, CONCRETE	369.00	SYS
0072	604-12083	DETECTABLE WARNING SURFACES	53.00	SYS
0073	604-44251	STEPS, CONCRETE	19.00	CYS
0074	604-95344	HAND RAIL, PEDESTRIAN	174.00	LFT
0075	605-06120	CURB, CONCRETE	234.00	LFT
0076	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	237.00	SYS
0077	610-07487	HMA FOR APPROACHES, TYPE B	249.00	TON
0078	610-08446	PCCP FOR APPROACHES, 6 IN.	726.00	SYS

0079	610-09108	PCCP FOR APPROACHES, 9 IN.	609.00	SYS
0080	611-02825	MAILBOX ASSEMBLY, TRIPLE	6.00	EACH
0081	611-06497	MAILBOX ASSEMBLY, SINGLE	12.00	EACH
0082	611-06498	MAILBOX ASSEMBLY, DOUBLE	2.00	EACH
0083	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0084	615-06505	MONUMENT, B	16.00	EACH
0085	615-06510	MONUMENT, C	1.00	EACH
0086	616-05688	RIPRAP, CLASS 1	293.00	TON
0087	616-05689	RIPRAP, CLASS 2	6.00	TON
0088	616-06405	RIPRAP, REVETMENT	146.00	TON
0089	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	177.00	SYS
0090	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	510.00	SYS
0091	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0092	621-02770	EROSION CONTROL BLANKET	1032.00	SYS
0093	621-06545	FERTILIZER	1.00	TON
0094	621-06554	SEED MIXTURE U	219.00	LBS
0095	621-06565	MULCHING MATERIAL	3.00	TON
0096	621-06574	SODDING	54.00	SYS
0097	621-06575	SODDING, NURSERY	4860.00	SYS
0098	621-12612	SEED MIXTURE FLOODPLAIN	44.00	LBS
0099	628-09403	FIELD OFFICE, C	12.00	MOS
0100	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0101	701-09557	TEST PILE, DYNAMIC, PRODUCTION	132.00	LFT
0102	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0103	701-09739	PILE SHOE, HP 12 X 53	58.00	EACH
0104	701-51195	PILE, STEEL H HP 12 X 53	3136.00	LFT
0105	702-51005	CONCRETE, A, SUBSTRUCTURE	227.00	CYS
0106	702-51015	CONCRETE, B, FOOTINGS	418.00	CYS
0107	702-51046	CONCRETE, FOUNDATION SEAL	704.00	CYS
0108	703-06028	REINFORCING BARS	99048.00	LBS
0109	703-06029	REINFORCING BARS, EPOXY COATED	33025.00	LBS
0110	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0111	704-51002	CONCRETE, C, SUPERSTRUCTURE	198.00	CYS
0112	706-11600	RAILING, CONCRETE FC	8.60	CYS
0113	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0114	709-51821	SURFACE SEAL	1.00	LS
0115	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	7464.00	LFT
0116	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	174.00	LFT
0117	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1953.00	LFT
0118	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	161.00	LFT
0119	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	941.00	LFT
0120	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	851.00	LFT

0121	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	102.00	LFT
0122	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	113.00	LFT
0123	715-05407	PIPE, END BENT DRAIN, 6 IN.	200.00	LFT
0124	715-05711	PIPE, SANITARY SEWER, 6 IN.	101.00	LFT
0125	715-40000	PIPE, SANITARY SEWER, 4 IN.	143.00	LFT
0126	715-46000	PIPE END SECTION, DIAMETER 12 IN.	3.00	EACH
0127	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	EACH
0128	715-46020	PIPE END SECTION, DIAMETER 24 IN.	5.00	EACH
0129	718-06531	OUTLET PROTECTOR, 3	3.00	EACH
0130	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0131	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	6146.00	SYS
0132	718-52610	AGGREGATE FOR UNDERDRAINS	672.00	CYS
0133	720-02442	PIPE PLUG EXISTING	1.00	EACH
0134	720-08659	MANHOLE, C5	1.00	EACH
0135	720-45035	INLET, F7	2.00	EACH
0136	720-45042	INLET, HA5	8.00	EACH
0137	720-45270	PIPE CATCH BASIN, 18 IN.	10.00	EACH
0138	720-45275	PIPE CATCH BASIN, 24 IN.	2.00	EACH
0139	720-45410	MANHOLE, C4	22.00	EACH
0140	720-98174	INLET, B15	23.00	EACH
0141	720-98555	INLET, C15	19.00	EACH
0142	801-04308	ROAD CLOSURE SIGN ASSEMBLY	16.00	EACH
0143	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2711.00	LFT
0144	801-06625	DETOUR ROUTE MARKER ASSEMBLY	67.00	EACH
0145	801-06640	CONSTRUCTION SIGN, A	46.00	EACH
0146	801-06645	CONSTRUCTION SIGN, B	39.00	EACH
0147	801-06775	MAINTAINING TRAFFIC	1.00	LS
0148	801-07119	BARRICADE, III-B	1316.00	LFT
0149	802-03896	BOLLARD	2.00	EACH
0150	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	562.00	LFT
0151	802-07060	SIGN, SHEET, RELOCATE	71.00	EACH
0152	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	68.00	SFT
0153	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	23.00	SFT
0154	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	4485.00	LFT
0155	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	57484.00	LFT
0156	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	34627.00	LFT
0157	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	35.00	LFT
0158	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0159	808-11958	TRANSVERSE MARKING, PAINT, YIELD LINE, WHITE, 24 IN.	24.00	LFT
0160	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	60.00	LFT
0161	808-12046	LINE, PAINT, DOTTED, WHITE, 4 IN.	30.00	LFT
0162	808-12176	LINE, PAINT, DOTTED, YELLOW, 4 IN.	60.00	LFT

0163	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE 4"	2067.00	LFT
0164	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	170.00	LFT

Call: 221

Contract: R -42542-A

Section No.: 2 PAVEMENT REPLACEMENT, HMA

Line

Item No	Item Code	Description	Quantity	Unit
0165	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0166	203-02000	EXCAVATION, COMMON	10969.00	CYS
0167	301-12234	COMPACTED AGGREGATE NO. 53	1433.00	CYS
0168	303-01180	COMPACTED AGGREGATE NO. 53	357.00	TON
0169	401-06264	PROFILOGRAPH, HMA	1.00	LS
0170	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1394.00	TON
0171	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2319.00	TON
0172	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	2357.00	TON
0173	401-10258	JOINT ADHESIVE, SURFACE	7707.00	LFT
0174	401-10259	JOINT ADHESIVE, INTERMEDIATE	7707.00	LFT
0175	401-11785	LIQUID ASPHALT SEALANT	7707.00	LFT
0176	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	2877.00	TON
0177	406-05520	ASPHALT FOR TACK COAT	10.00	TON
0178	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	4958.00	LFT
0179	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	446.00	LFT
0180	605-08636	CURB AND GUTTER, TURNOUT COMBINED	11.00	LFT
0181	610-07487	HMA FOR APPROACHES, TYPE B	235.00	TON

Call: 221

Contract: R -42542-A

Section No.: 3 PAVEMENT REPLACEMENT, PCCP

Line

Item No	Item Code	Description	Quantity	Unit
0182	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0183	203-02000	EXCAVATION, COMMON	12603.00	CYS
0184	302-06464	SUBBASE FOR PCCP	4502.00	CYS
0185	303-01180	COMPACTED AGGREGATE NO. 53	168.00	TON
0186	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	211.00	TON
0187	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	354.00	TON
0188	501-10254	QC/QA-PCCP, 8.5 IN.	15669.00	SYS
0189	503-05240	D-1 CONTRACTION JOINT	9574.00	LFT
0190	605-06090	CURB, INTEGRAL CONCRETE	5404.00	LFT
0191	605-09137	CURB, TURNOUT	11.00	LFT

Call: 231

Contract: R -42651-A

Section No.: 1

ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
	0011	202-93741	GUARDRAIL, END TREATMENT, REMOVE	8.00	EACH
	0012	203-08607	LINEAR GRADING	505.00	LFT
	0013	303-07449	COMPACTED AGGREGATE NO. 73	1132.00	TON
	0014	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	282.00	TON
	0015	306-08036	MILLING, ASPHALT, 2 IN.	63752.00	SYS
	0016	306-08432	MILLING, APPROACH	5099.00	SYS
	0017	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	7012.00	TON
	0018	401-10258	JOINT ADHESIVE, SURFACE	25385.00	LFT
	0019	401-11785	LIQUID ASPHALT SEALANT	41005.00	LFT
	0020	406-05520	ASPHALT FOR TACK COAT	18.00	TON
	0021	601-02241	GUARDRAIL, REMOVE	2377.00	LFT
	0022	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1806.50	LFT
	0023	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
	0024	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
	0025	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	23430.00	LFT
	0026	610-07488	HMA FOR APPROACHES, TYPE C	561.00	TON
	0027	615-06520	MONUMENT, RE-ESTABLISH	9.00	EACH
	0028	628-09403	FIELD OFFICE, C	5.00	MOS
	0029	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
	0030	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
	0031	801-06710	FLASHING ARROW SIGN	60.00	DAY
	0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0033	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1760.00	LFT
	0034	805-78785	SIGNAL DETECTOR HOUSING	4.00	EACH
	0035	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	800.00	LFT
	0036	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
	0037	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	900.00	LFT
	0038	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	23866.00	LFT

0039	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	16523.00	LFT
0040	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	1050.00	LFT
0041	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	324.00	LFT
0042	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	98.00	LFT
0043	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	40.00	LFT
0044	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	9.00	EACH
0045	808-12032	GROOVING FOR PAVEMENT MARKINGS	42339.00	LFT
0046	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	129.00	EACH
0047	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	129.00	EACH

Call: 241

Contract: R -43127-A

Section No.: 1 MEDIAN RECONSTRUCTION

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-02273	CENTER CURB, CONCRETE, REMOVE	1481.00	SYS
0011	207-08264	SUBGRADE TREATMENT, TYPE II	1704.00	SYS
0012	302-07455	DENSE GRADED SUBBASE	2.00	CYS
0013	304-12627	HMA PATCHING FULL DEPTH TYPE D	1090.00	TON
0014	503-03489	RETROFITTED TIE BARS	16.00	EACH
0015	503-05240	D-1 CONTRACTION JOINT	16.00	LFT
0016	506-06333	PCCP PATCHING, FULL DEPTH	32.00	SYS
0017	507-08269	CRACKS IN PCCP, FILLED	2000.00	LFT
0018	605-06255	CENTER CURB, D CONCRETE	365.00	SYS
0019	628-09403	FIELD OFFICE, C	9.00	MOS
0020	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0021	628-12685	TELEPHONE SERVICE, A	9.00	MOS
0022	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	6.00	EACH
0023	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	785.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	87.00	EACH
0025	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0026	801-06710	FLASHING ARROW SIGN	240.00	DAY
0027	801-06775	MAINTAINING TRAFFIC	1.00	LS

0028	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
0029	808-06716	LINE, REMOVE	6544.00	LFT
0030	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0031	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	26376.00	LFT
0032	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	281.00	LFT
0033	808-12032	GROOVING FOR PAVEMENT MARKINGS	7912.00	LFT
0034	808-95933	CURB, PAINTING, YELLOW	18464.00	LFT

Call: 251

Contract: R -43482-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-52710	SIDEWALK CONCRETE, REMOVE	16.00	SYS
0011	203-02000	EXCAVATION, COMMON	37.00	CYS
0012	203-02070	BORROW	49.00	CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	400.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	207-08264	SUBGRADE TREATMENT, TYPE II	270.00	SYS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	1976.00	SYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	126.00	TON
0018	304-07493	WIDENING WITH HMA, TYPE B	30.00	TON
0019	304-07493	WIDENING WITH HMA, TYPE B	362.00	TON
0020	304-12623	HMA PATCHING FULL DEPTH TYPE B	22.00	TON
0021	306-08042	MILLING, SCARIFICATION	24027.00	SYS
0022	306-08043	MILLING, TRANSITION	121.00	SYS
0023	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2103.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	3580.00	LFT
0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	442.00	LFT
0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	470.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	3580.00	LFT
0028	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0029	604-08530	BRICK	448.00	EACH

0030	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0031	621-06559	MULCHED SEEDING R	585.00 SYS
0032	628-09403	FIELD OFFICE, C	10.00 MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0034	702-76240	CONCRETE	3.00 CYS
0035	801-06640	CONSTRUCTION SIGN, A	3.00 EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 261

Contract: R -44016-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
	0009	306-08036	MILLING, ASPHALT, 2 IN.	3160.00	SYS
	0010	306-08043	MILLING, TRANSITION	50.00	SYS
	0011	306-08432	MILLING, APPROACH	925.00	SYS
	0012	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	407.00	TON
	0013	401-10258	JOINT ADHESIVE, SURFACE	444.00	LFT
	0014	401-11785	LIQUID ASPHALT SEALANT	444.00	LFT
	0015	402-07787	HMA WEDGE AND LEVEL, TYPE D	25.00	TON
	0016	406-05520	ASPHALT FOR TACK COAT	2.00	TON
	0017	610-07788	HMA FOR APPROACHES, TYPE D	102.00	TON
	0018	720-12797	CASTING, INLET, ADJUST TO GRADE	1.00	EACH
	0019	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
	0020	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2952.00	LFT
	0021	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2952.00	LFT
	0022	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	200.00	LFT
	0023	801-06640	CONSTRUCTION SIGN, A	17.00	EACH
	0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0025	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
	0026	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2000.00	LFT
	0027	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	200.00	LFT
	0028	805-78785	SIGNAL DETECTOR HOUSING	4.00	EACH
	0029	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	640.00	LFT

0030	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	397.00	LFT
0031	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	217.00	LFT
0032	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2338.00	LFT
0033	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	11.00	EACH
0034	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	73.00	LFT

Call: 301

Contract: B -37667-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	788.00	CYS
	0013	203-02070	BORROW	2536.00	CYS
	0014	203-51223	EXCAVATION, WATERWAY	279.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	24200.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	205-12618	SWQCP PREPARATION	1.00	LS
	0018	206-51817	SHEET PILING STEEL	1250.00	SFT
	0019	207-08264	SUBGRADE TREATMENT, TYPE II	202.00	SYS
	0020	207-08266	SUBGRADE TREATMENT, TYPE III	870.00	SYS
	0021	207-09935	SUBGRADE TREATMENT, TYPE IC	2259.00	SYS
	0022	211-06467	AGGREGATE FOR END BENT BACKFILL	35.00	CYS
	0023	211-09264	STRUCTURE BACKFILL, TYPE 1	13.00	CYS
	0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	228.00	SYS
	0025	301-12234	COMPACTED AGGREGATE NO. 53	443.00	CYS
	0026	302-06464	SUBBASE FOR PCCP	38.00	CYS
	0027	303-01180	COMPACTED AGGREGATE NO. 53	302.00	TON
	0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	300.00	TON
	0029	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	462.00	TON
	0030	401-10258	JOINT ADHESIVE, SURFACE	2544.00	LFT
	0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	2544.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	2544.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0034	601-06037	GUARDRAIL, END TREATMENT, I	4.00	EACH
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	50.00	LFT
0036	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0037	602-06729	BARRIER, DELINEATOR	6.00	EACH
0038	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	148.00	SYS
0039	610-07487	HMA FOR APPROACHES, TYPE B	44.00	TON
0040	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	2.00	EACH
0041	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0042	615-06505	MONUMENT, B	4.00	EACH
0043	616-06405	RIPRAP, REVETMENT	314.00	TON
0044	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	408.00	SYS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0046	621-06553	SEED MIXTURE R	72.00	LBS
0047	621-06559	MULCHED SEEDING R	984.00	SYS
0048	621-06574	SODDING	27.00	SYS
0049	621-08161	PERMANENT TURF REINFORCEMENT MAT	1682.00	SYS
0050	628-09403	FIELD OFFICE, C	6.00	MOS
0051	701-09558	TEST PILE, INDICATOR, PRODUCTION	134.00	LFT
0052	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0053	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	570.00	LFT
0054	703-06029	REINFORCING BARS, EPOXY COATED	38931.00	LBS
0055	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	34.00	EACH
0056	704-51002	CONCRETE, C, SUPERSTRUCTURE	114.70	CYS
0057	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0058	706-11404	RAILING, STEEL PF-1	132.00	LFT
0059	706-11602	RAILING, CONCRETE PF-1	7.00	CYS
0060	707-05983	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 36 IN. X 12 IN.	224.00	LFT
0061	709-51821	SURFACE SEAL	1.00	LS
0062	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	170.00	LFT
0063	715-05407	PIPE, END BENT DRAIN, 6 IN.	100.00	LFT
0064	715-46000	PIPE END SECTION, DIAMETER 12 IN.	8.00	EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	7.00	EACH
0067	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS
0069	801-07118	BARRICADE, III-A	48.00	LFT
0070	801-07119	BARRICADE, III-B	48.00	LFT
0071	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1892.00	LFT

Call: 311

Contract: B -39233-A

Section No.: 1

BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-91840	FENCE, CHAIN. LINK, REMOVE	40.00	LFT
0015	202-96133	PIPE, REMOVE	16.00	LFT
0016	203-02000	EXCAVATION, COMMON	2037.00	CYS
0017	203-02070	BORROW	1070.00	CYS
0018	203-08607	LINEAR GRADING	724.00	LFT
0019	205-11626	PUMP AROUND	1.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	36950.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	274.00	CYS
0024	206-51235	COFFERDAM	1.00	LS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	1904.00	SYS
0026	211-06467	AGGREGATE FOR END BENT BACKFILL	76.00	CYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	3.00	CYS
0028	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1904.00	SYS
0029	301-12231	COMPACTED AGGREGATE NO. 2	16.00	CYS
0030	301-12234	COMPACTED AGGREGATE NO. 53	229.00	CYS
0031	302-06464	SUBBASE FOR PCCP	94.00	CYS
0032	303-01180	COMPACTED AGGREGATE NO. 53	326.00	TON
0033	306-08034	MILLING, ASPHALT, 1 1/2 IN.	534.00	SYS
0034	306-08043	MILLING, TRANSITION	281.00	SYS
0035	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	180.00	TON
0036	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	232.00	TON
0037	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	826.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	1799.00	LFT

0039	401-10259	JOINT ADHESIVE, INTERMEDIATE	1357.00	LFT
0040	401-11785	LIQUID ASPHALT SEALANT	1799.00	LFT
0041	406-05521	ASPHALT FOR TACK COAT	3865.00	SYS
0042	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00	TON
0043	503-12477	TERMINAL JOINT, TYPE HMA	72.00	LFT
0044	601-02241	GUARDRAIL, REMOVE	3564.00	LFT
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	650.00	LFT
0046	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	8.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0048	602-06729	BARRIER, DELINEATOR	18.00	EACH
0049	603-06045	FENCE, CHAIN LINK, 48 IN.	40.00	LFT
0050	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	366.00	SYS
0051	615-06490	RIGHT-OF-WAY MARKER	34.00	EACH
0052	615-06505	MONUMENT, B	4.00	EACH
0053	616-06405	RIPRAP, REVETMENT	721.00	TON
0054	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	18.00	SYS
0055	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	1070.00	SYS
0056	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0057	621-04258	SEED MIXTURE	5.00	LBS
0058	621-06553	SEED MIXTURE R	95.00	LBS
0059	621-06559	MULCHED SEEDING R	1181.00	SYS
0060	621-06574	SODDING	78.00	SYS
0061	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	5.00	EACH
0062	628-09403	FIELD OFFICE, C	13.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0064	628-11977	COMPUTER SYSTEM	1.00	EACH
0065	628-12685	TELEPHONE SERVICE, A	13.00	MOS
0066	701-02938	CORED HOLE IN ROCK, 24 IN	108.00	LFT
0067	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0068	701-09557	TEST PILE, DYNAMIC, PRODUCTION	163.00	LFT
0069	701-09558	TEST PILE, INDICATOR, PRODUCTION	65.00	LFT
0070	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0071	701-09739	PILE SHOE, HP 12 X 53	16.00	EACH
0072	701-12361	PREBORED HOLE, 24 IN	261.00	LFT
0073	701-51195	PILE, STEEL H HP 12 X 53	1361.00	LFT
0074	702-92857	CONCRETE, C, SUBSTRUCTURE	74.60	CYS
0075	703-06029	REINFORCING BARS, EPOXY COATED	118355.00	LBS
0076	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	84.00	EACH
0077	704-51002	CONCRETE, C, SUPERSTRUCTURE	257.30	CYS
0078	706-11600	RAILING, CONCRETE FC	35.40	CYS
0079	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0080	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	428.00	LFT

0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	711-51038	STRUCTURAL STEEL	1.00	LS
0084	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	16.00	LFT
0085	715-05407	PIPE, END BENT DRAIN, 6 IN.	290.00	LFT
0086	715-08069	CONCRETE ANCHOR, MIN. AREA 5.1 SFT	2.00	EACH
0087	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	260.00	SYS
0088	725-10221	LINER PIPE, THERMOPLASTIC, CIRCULAR, 4.3-4.4 SFT	307.00	LFT
0089	725-10245	PERPETUATION, EXISTING PIPE	1.00	EACH
0090	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0092	801-06640	CONSTRUCTION SIGN, A	56.00	EACH
0093	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07118	BARRICADE, III-A	144.00	LFT
0096	801-07119	BARRICADE, III-B	192.00	LFT
0097	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	48.00	LFT
0098	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	12.00	SFT
0099	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0100	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	88.00	LFT
0101	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1740.00	LFT
0102	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1040.00	LFT
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	14.00	EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	14.00	EACH

Call: 321

Contract: B -39290-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	4.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS

0013	202-02240	PAVEMENT REMOVAL	110.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	203-02000	EXCAVATION, COMMON	305.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	16458.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51225	EXCAVATION, DRY	140.00	CYS
0020	206-51235	COFFERDAM	1.00	LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	463.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	52.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	502.00	SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	98.00	CYS
0025	302-06464	SUBBASE FOR PCCP	53.00	CYS
0026	304-12623	HMA PATCHING FULL DEPTH TYPE B	272.00	TON
0027	306-08043	MILLING, TRANSITION	1628.00	SYS
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	159.00	TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	117.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1179.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	699.00	LFT
0032	401-11785	LIQUID ASPHALT SEALANT	1878.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	3060.00	SYS
0034	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0035	503-12477	TERMINAL JOINT, TYPE HMA	88.00	LFT
0036	601-02241	GUARDRAIL, REMOVE	490.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	97.00	LFT
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0039	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0040	601-99132	GUARDRAIL, TRANSITION, VH, 6 FT 3 IN. SPACING	1.00	EACH
0041	602-06729	BARRIER, DELINEATOR	24.00	EACH
0042	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1179.00	LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	210.00	SYS
0044	615-06505	MONUMENT, B	2.00	EACH
0045	616-05688	RIPRAP, CLASS 1	344.00	TON
0046	616-06405	RIPRAP, REVETMENT	164.00	TON
0047	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	793.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06559	MULCHED SEEDING R	533.00	SYS
0050	621-06565	MULCHING MATERIAL	2.00	TON
0051	621-06574	SODDING	43.00	SYS
0052	621-12612	SEED MIXTURE FLOODPLAIN	56.00	LBS
0053	621-52448	SIGN, DO NOT SPRAY	10.00	EACH
0054	622-91786	SEEDLING	75.00	EACH

0055	628-09403	FIELD OFFICE, C	12.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0057	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	4.00	EACH
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	32.00	EACH
0059	702-92857	CONCRETE, C, SUBSTRUCTURE	51.80	CYS
0060	703-06029	REINFORCING BARS, EPOXY COATED	258537.00	LBS
0061	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	46.00	EACH
0062	704-51002	CONCRETE, C, SUPERSTRUCTURE	589.60	CYS
0063	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0064	706-09962	RAILING, CONCRETE PF-1	818.00	LFT
0065	706-11404	RAILING, STEEL PF-1	834.00	LFT
0066	709-51821	SURFACE SEAL	1.00	LS
0067	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0068	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0069	715-05407	PIPE, END BENT DRAIN, 6 IN.	130.00	LFT
0070	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	EACH
0071	726-92406	BEARING ASSEMBLY ELASTOMERIC	16.00	EACH
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0074	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00	LS
0076	801-07118	BARRICADE, III-A	96.00	LFT
0077	801-07119	BARRICADE, III-B	192.00	LFT
0078	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	212.00	LFT
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1694.00	LFT

Call: 331

Contract: B -40368-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	624.00	SYS

0012	202-02278	CURB, CONCRETE, REMOVE	650.00	LFT
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-52710	SIDEWALK CONCRETE, REMOVE	356.00	SYS
0015	203-02000	EXCAVATION, COMMON	216.00	CYS
0016	203-02070	BORROW	334.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	8757.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	206-51235	COFFERDAM	1.00	LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	649.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	68.00	CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	18.00	CYS
0024	302-06464	SUBBASE FOR PCCP	116.00	CYS
0025	304-12625	HMA PATCHING FULL DEPTH TYPE C	15.00	TON
0026	306-08043	MILLING, TRANSITION	1850.00	SYS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	168.00	TON
0028	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	174.00	TON
0029	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	88.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1604.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	1604.00	LFT
0032	401-11785	LIQUID ASPHALT SEALANT	1604.00	LFT
0033	402-10087	HMA FOR TEMPORARY PAVEMENT, D	29.00	TON
0034	406-05521	ASPHALT FOR TACK COAT	4452.00	SYS
0035	503-03489	RETROFITTED TIE BARS	171.00	EACH
0036	503-12477	TERMINAL JOINT, TYPE HMA	132.00	LFT
0037	601-02241	GUARDRAIL, REMOVE	364.00	LFT
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0040	603-06065	FENCE, CHAIN LINK, RESET	111.00	LFT
0041	604-06070	SIDEWALK, CONCRETE	402.00	SYS
0042	605-06090	CURB, INTEGRAL CONCRETE	537.00	LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	454.00	SYS
0044	615-06505	MONUMENT, B	2.00	EACH
0045	616-05689	RIPRAP, CLASS 2	599.00	TON
0046	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	371.00	SYS
0047	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0048	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0049	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00	LS
0050	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0052	621-02770	EROSION CONTROL BLANKET	573.00	SYS
0053	621-06560	MULCHED SEEDING U	1129.00	SYS

0054	628-09403	FIELD OFFICE, C	12.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0056	628-12686	TELEPHONE SERVICE, B	12.00	MOS
0057	702-04325	TEMPORARY SHORING	1.00	LS
0058	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0059	702-51005	CONCRETE, A, SUBSTRUCTURE	1.20	CYS
0060	702-51863	FIELD DRILLED HOLE IN CONCRETE	24.00	EACH
0061	703-06028	REINFORCING BARS	196.00	LBS
0062	703-06029	REINFORCING BARS, EPOXY COATED	148616.00	LBS
0063	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	80.00	EACH
0064	704-51002	CONCRETE, C, SUPERSTRUCTURE	441.80	CYS
0065	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.00	EACH
0066	706-09961	RAILING, CONCRETE PS-1	262.00	LFT
0067	706-11418	RAILING, STEEL PS-1	278.00	LFT
0068	709-51821	SURFACE SEAL	1.00	LS
0069	710-09158	PATCHING CONCRETE STRUCTURES	160.00	SFT
0070	711-51864	DRILLED HOLE	8.00	EACH
0071	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0072	711-96800	STUD SHEAR CONNECTORS	4060.00	EACH
0073	715-05407	PIPE, END BENT DRAIN, 6 IN.	284.00	LFT
0074	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	8.00	EACH
0075	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	172.00	SYS
0076	718-52610	AGGREGATE FOR UNDERDRAINS	3.00	CYS
0077	724-12773	BRIDGE EXPANSION JOINT, PCF	127.00	LFT
0078	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0079	801-03290	CONSTRUCTION SIGN, C	1.00	EACH
0080	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0081	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15289.00	LFT
0082	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0083	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0084	801-06710	FLASHING ARROW SIGN	16.00	DAY
0085	801-06775	MAINTAINING TRAFFIC	1.00	LS
0086	801-07118	BARRICADE, III-A	96.00	LFT
0087	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	692.00	LFT
0088	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0089	808-06716	LINE, REMOVE	2853.00	LFT
0090	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	2902.00	LFT
0091	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	226.00	LFT
0092	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2875.00	LFT
0093	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	511.00	LFT
0094	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	34.00	LFT
0095	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1.00	EACH

0096	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	309.00	LFT
0097	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	1.00	EACH

Call: 341

Contract: B -40428-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0013	202-02240	PAVEMENT REMOVAL	577.00	SYS
	0014	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	40.00	SFT
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0018	202-93047	MANHOLE, REMOVE	1.00	EACH
	0019	203-02000	EXCAVATION, COMMON	460.00	CYS
	0020	203-02070	BORROW	500.00	CYS
	0021	205-11626	PUMP AROUND	2.00	EACH
	0022	205-12108	STORMWATER MANAGEMENT BUDGET	26165.00	DOL
	0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0024	205-12618	SWQCP PREPARATION	1.00	LS
	0025	206-51220	EXCAVATION, WET	95.00	CYS
	0026	207-12498	SUBGRADE TREATMENT, TYPE ID	1922.00	SYS
	0027	211-06467	AGGREGATE FOR END BENT BACKFILL	1.00	CYS
	0028	211-09265	STRUCTURE BACKFILL, TYPE 2	1185.00	CYS
	0029	211-09266	STRUCTURE BACKFILL, TYPE 3	400.00	CYS
	0030	211-09268	STRUCTURE BACKFILL, TYPE 5	203.00	CYS
	0031	301-12234	COMPACTED AGGREGATE NO. 53	58.00	CYS
	0032	302-06464	SUBBASE FOR PCCP	114.00	CYS
	0033	303-01180	COMPACTED AGGREGATE NO. 53	408.00	TON
	0034	304-07493	WIDENING WITH HMA, TYPE B	186.00	TON

0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	624.00	SYS
0036	306-11872	MILLING, PROFILE	512.00	SYS
0037	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	149.00	TON
0038	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	58.00	TON
0039	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	73.00	TON
0040	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	44.00	TON
0041	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	142.00	TON
0042	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	178.00	TON
0043	401-10258	JOINT ADHESIVE, SURFACE	2098.00	LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	690.00	LFT
0045	401-11785	LIQUID ASPHALT SEALANT	2098.00	LFT
0046	406-05521	ASPHALT FOR TACK COAT	3473.00	SYS
0047	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.50	TON
0048	601-02241	GUARDRAIL, REMOVE	1095.00	LFT
0049	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	562.50	LFT
0050	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0051	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0052	602-06729	BARRIER, DELINEATOR	8.00	EACH
0053	603-06060	FENCE, FARM FIELD, RESET	174.00	LFT
0054	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	194.00	SYS
0055	615-06505	MONUMENT, B	6.00	EACH
0056	616-05688	RIPRAP, CLASS 1	244.00	TON
0057	616-06405	RIPRAP, REVETMENT	1759.00	TON
0058	616-06451	RIPRAP, UNIFORM	47.00	TON
0059	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	1482.00	SYS
0060	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	2051.00	SYS
0061	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	340.00	SYS
0062	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	287.00	SYS
0063	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0064	621-02770	EROSION CONTROL BLANKET	1047.00	SYS
0065	621-06559	MULCHED SEEDING R	146.00	SYS
0066	621-06560	MULCHED SEEDING U	1305.00	SYS
0067	621-06565	MULCHING MATERIAL	0.90	TON
0068	621-06567	WATER	0.90	KGAL
0069	621-06574	SODDING	98.00	SYS
0070	621-12612	SEED MIXTURE FLOODPLAIN	10.00	LBS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0072	628-12683	FIELD OFFICE, D	18.00	MOS
0073	702-51015	CONCRETE, B, FOOTINGS	6.00	CYS
0074	702-51863	FIELD DRILLED HOLE IN CONCRETE	166.00	EACH
0075	702-92857	CONCRETE, C, SUBSTRUCTURE	15.70	CYS
0076	703-06029	REINFORCING BARS, EPOXY COATED	33580.00	LBS

0077	704-51002	CONCRETE, C, SUPERSTRUCTURE	75.00	CYS
0078	706-09960	RAILING, CONCRETE FC	156.60	LFT
0079	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0080	709-51821	SURFACE SEAL	1.00	LS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	710-09158	PATCHING CONCRETE STRUCTURES	30.00	SFT
0084	714-11175	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 5 FT.	105.00	LFT
0085	714-12722	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 6 FT	54.00	LFT
0086	715-06050	CAP	4.00	EACH
0087	715-07794	WATER MAIN CONNECTIONS	2.00	EACH
0088	715-98961	FORCE MAIN	30.00	LFT
0089	716-07654	PIPE INSTALLATION, TRENCHLESS, 6 IN.	100.00	LFT
0090	718-04986	CLEANOUT	1.00	EACH
0091	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	10.00	SYS
0092	720-45510	MANHOLE, C4 MODIFIED	1.00	EACH
0093	724-12773	BRIDGE EXPANSION JOINT, PCF	83.00	LFT
0094	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0095	801-06625	DETOUR ROUTE MARKER ASSEMBLY	50.00	EACH
0096	801-06640	CONSTRUCTION SIGN, A	73.00	EACH
0097	801-06645	CONSTRUCTION SIGN, B	34.00	EACH
0098	801-06775	MAINTAINING TRAFFIC	1.00	LS
0099	801-07118	BARRICADE, III-A	144.00	LFT
0100	801-07119	BARRICADE, III-B	144.00	LFT
0101	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	55.00	LFT
0102	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	11.00	LFT
0103	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	24.00	SFT
0104	802-91122	SIGN GROUND MOUNTED RESET	2.00	EACH
0105	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	178.00	LFT
0106	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1764.00	LFT
0107	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	612.00	LFT
0108	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00	EACH
0109	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	EACH

Call: 351

Contract: B -40439-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0014	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	609.00	SYS
0016	202-02272	PAVED SIDE DITCH, REMOVE	125.00	LFT
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-93741	GUARDRAIL, END TREATMENT, REMOVE	6.00	EACH
0020	202-94749	CURB, ASPHALT, REMOVE	508.00	LFT
0021	202-96531	FENCE RIGHT-OF-WAY, REMOVE	180.00	LFT
0022	203-02000	EXCAVATION, COMMON	4438.00	CYS
0023	203-02010	EXCAVATION, ROCK	286.00	CYS
0024	203-02070	BORROW	1550.00	CYS
0025	203-08279	EXPANDED POLYSTYRENE FILL	2416.00	CYS
0026	205-12108	STORMWATER MANAGEMENT BUDGET	281743.00	DOL
0027	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0028	205-12618	SWQCP PREPARATION	1.00	LS
0029	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	2743.00	CYS
0030	206-51235	COFFERDAM	1.00	LS
0031	207-09935	SUBGRADE TREATMENT, TYPE IC	6322.00	SYS
0032	211-02050	B BORROW	2798.00	CYS
0033	211-09265	STRUCTURE BACKFILL, TYPE 2	15.00	CYS
0034	211-09266	STRUCTURE BACKFILL, TYPE 3	883.00	CYS
0035	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1989.00	SYS
0036	301-12233	COMPACTED AGGREGATE NO. 8	2065.00	CYS
0037	301-12234	COMPACTED AGGREGATE NO. 53	832.00	CYS
0038	302-06464	SUBBASE FOR PCCP	84.00	CYS
0039	304-12623	HMA PATCHING FULL DEPTH TYPE B	28.00	TON
0040	306-08034	MILLING, ASPHALT, 1 1/2 IN.	9520.00	SYS
0041	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	850.00	TON
0042	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	340.00	TON
0043	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	765.00	TON
0044	401-10258	JOINT ADHESIVE, SURFACE	2026.00	LFT
0045	401-10259	JOINT ADHESIVE, INTERMEDIATE	1518.00	LFT

0046	401-11785	LIQUID ASPHALT SEALANT	2026.00	LFT
0047	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	370.00	TON
0048	402-10087	HMA FOR TEMPORARY PAVEMENT, D	170.00	TON
0049	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0050	503-05240	D-1 CONTRACTION JOINT	123.00	LFT
0051	503-12477	TERMINAL JOINT, TYPE HMA	84.00	LFT
0052	503-12477	TERMINAL JOINT, TYPE HMA	84.00	LFT
0053	601-02241	GUARDRAIL, REMOVE	844.00	LFT
0054	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	421.00	LFT
0055	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	233.00	LFT
0056	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	6.00	EACH
0057	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00	EACH
0058	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00	EACH
0059	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0060	602-06729	BARRIER, DELINEATOR	104.00	EACH
0061	603-06040	FENCE, FARM FIELD, 47 IN.	180.00	LFT
0062	605-05523	CURB, HMA	292.00	LFT
0063	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1350.00	LFT
0064	607-06390	PAVED SIDE DITCH, M	125.00	LFT
0065	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	404.00	SYS
0066	615-06505	MONUMENT, B	4.00	EACH
0067	616-05688	RIPRAP, CLASS 1	2001.00	TON
0068	616-06405	RIPRAP, REVETMENT	169.00	TON
0069	616-09395	GEOMEMBRANE	677.00	SYS
0070	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	240.00	SYS
0071	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1948.00	SYS
0072	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0073	621-02770	EROSION CONTROL BLANKET	325.00	SYS
0074	621-04258	SEED MIXTURE	22.00	LBS
0075	621-06545	FERTILIZER	1.00	TON
0076	621-06553	SEED MIXTURE R	342.00	LBS
0077	621-06565	MULCHING MATERIAL	6.00	TON
0078	621-06567	WATER	3.00	KGAL
0079	621-06574	SODDING	82.00	SYS
0080	624-92647	HERBICIDE TREATMENT	1.00	ACRE
0081	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0082	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4 RESET	4454.00	LFT
0083	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0084	628-12684	FIELD OFFICE, E	36.00	MOS
0085	701-06011	DYNAMIC PILE LOAD TEST	3.00	EACH
0086	701-09557	TEST PILE, DYNAMIC, PRODUCTION	165.00	LFT
0087	701-09558	TEST PILE, INDICATOR, PRODUCTION	605.00	LFT

0088	701-09559	TEST PILE, DYNAMIC, RESTRIKE	3.00 EACH
0089	701-09560	TEST PILE, INDICATOR, RESTRIKE	9.00 EACH
0090	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	4710.00 LFT
0091	701-09679	CONICAL PILE TIP, 14 IN.	91.00 EACH
0092	701-09739	PILE SHOE, HP 12 X 53	27.00 EACH
0093	701-51195	PILE, STEEL H HP 12 X 53	1080.00 LFT
0094	702-04325	TEMPORARY SHORING	1.00 LS
0095	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	56.00 EACH
0096	702-51005	CONCRETE, A, SUBSTRUCTURE	1354.90 CYS
0097	702-51015	CONCRETE, B, FOOTINGS	453.00 CYS
0098	702-51863	FIELD DRILLED HOLE IN CONCRETE	1804.00 EACH
0099	702-92857	CONCRETE, C, SUBSTRUCTURE	628.20 CYS
0100	703-06028	REINFORCING BARS	206676.00 LBS
0101	703-06029	REINFORCING BARS, EPOXY COATED	970100.00 LBS
0102	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	92.00 EACH
0103	704-51002	CONCRETE, C, SUPERSTRUCTURE	2207.80 CYS
0104	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	263.00 SYS
0105	706-11601	RAILING, CONCRETE FT	454.80 CYS
0106	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00 EACH
0107	709-51821	SURFACE SEAL	1.00 LS
0108	709-51821	SURFACE SEAL	1.00 LS
0109	710-09158	PATCHING CONCRETE STRUCTURES	400.00 SFT
0110	711-51038	STRUCTURAL STEEL	1.00 LS
0111	711-51038	STRUCTURAL STEEL	1.00 LS
0112	714-05562	RETAINING WALL	3165.00 SFT
0113	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1452.00 LFT
0114	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	345.00 LFT
0115	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	609.00 LFT
0116	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	6.00 LFT
0117	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00 LS
0118	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0119	718-06528	OUTLET PROTECTOR, 1	8.00 EACH
0120	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1060.00 SYS
0121	718-52610	AGGREGATE FOR UNDERDRAINS	1346.00 CYS
0122	720-45005	INLET, A2	1.00 EACH
0123	721-98445	AUTOMATIC DRAINAGE GATE, 6 IN.	1.00 EACH
0124	731-93945	FACE PANELS, CONCRETE	2587.00 SFT
0125	731-93946	WALL ERECTION	2587.00 SFT
0126	731-93947	LEVELING PAD, CONCRETE	369.00 LFT
0127	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00 EACH
0128	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0129	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	41449.00 LFT

0130	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	20.00	LFT
0131	801-06625	DETOUR ROUTE MARKER ASSEMBLY	11.00	EACH
0132	801-06640	CONSTRUCTION SIGN, A	44.00	EACH
0133	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0134	801-06710	FLASHING ARROW SIGN	720.00	DAY
0135	801-06775	MAINTAINING TRAFFIC	1.00	LS
0136	801-07118	BARRICADE, III-A	72.00	LFT
0137	801-07119	BARRICADE, III-B	94.00	LFT
0138	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	4341.00	LFT
0139	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	1033.00	LFT
0140	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	330.00	LFT
0141	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0142	801-12081	PORTABLE SIGNAL	1.00	LS
0143	801-12324	LAW ENFORCEMENT OFFICER	48.00	HRS
0144	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	4.00	EACH
0145	801-12417	PORTABLE TRAFFIC SENSOR	8.00	EACH
0146	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0147	804-06770	DELINEATOR POST	4.00	EACH
0148	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	285.00	LFT
0149	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3606.00	LFT
0150	808-06716	LINE, REMOVE	6141.00	LFT
0151	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	459.00	LFT
0152	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1834.00	LFT
0153	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1834.00	LFT
0154	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3400.00	LFT
0155	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	32.00	EACH
0156	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	32.00	EACH

Call: 361

Contract: B -40881-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0012	202-51368	SLOPEWALL, REMOVE	26.00	SYS
0013	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00	EACH
0014	202-96128	GUTTER, CONCRETE, REMOVE	210.00	LFT
0015	203-02000	EXCAVATION, COMMON	225.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	9000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	30.00	CYS
0020	206-51235	COFFERDAM	1.00	LS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	30.00	CYS
0022	302-06464	SUBBASE FOR PCCP	50.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	208.00	TON
0024	306-08043	MILLING, TRANSITION	234.00	SYS
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	20.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	300.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	300.00	LFT
0028	406-05521	ASPHALT FOR TACK COAT	467.00	SYS
0029	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0030	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0031	601-02241	GUARDRAIL, REMOVE	470.00	LFT
0032	601-05999	CURVED TERMINAL END	2.00	EACH
0033	601-09238	HAND DIG GUARDRAIL POST HOLES	4.00	EACH
0034	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	225.00	LFT
0035	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0036	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0037	602-06729	BARRIER, DELINEATOR	14.00	EACH
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	193.40	SYS
0039	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0040	615-06530	BENCH MARK POST	1.00	EACH
0041	616-06405	RIPRAP, REVETMENT	159.00	TON
0042	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	216.00	SYS
0043	616-51367	SLOPEWALL, CONCRETE, 4 IN.	26.00	SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0045	621-06559	MULCHED SEEDING R	90.00	SYS
0046	621-06565	MULCHING MATERIAL	1.00	TON
0047	621-06567	WATER	1.00	KGAL
0048	621-06574	SODDING	22.00	SYS
0049	621-12612	SEED MIXTURE FLOODPLAIN	12.00	LBS
0050	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	25.00	EACH
0051	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	49.00	EACH

0052	628-09401	FIELD OFFICE, A	12.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0054	628-11977	COMPUTER SYSTEM	1.00	EACH
0055	702-51005	CONCRETE, A, SUBSTRUCTURE	44.20	CYS
0056	702-51863	FIELD DRILLED HOLE IN CONCRETE	444.00	EACH
0057	702-92857	CONCRETE, C, SUBSTRUCTURE	34.80	CYS
0058	703-01540	THREADED TIE BAR ASSEMBLY	34.00	EACH
0059	703-06028	REINFORCING BARS	4564.00	LBS
0060	703-06029	REINFORCING BARS, EPOXY COATED	101752.00	LBS
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	247.50	CYS
0062	706-09960	RAILING, CONCRETE FC	453.00	LFT
0063	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0064	707-11517	STRUCTURAL MEMBER, CONCRETE BOX BEAM, 27 IN.X 36 IN.	1119.00	LFT
0065	709-51821	SURFACE SEAL	1.00	LS
0066	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0067	715-05407	PIPE, END BENT DRAIN, 6 IN.	120.00	LFT
0068	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	80.00	SYS
0069	720-44296	INLET, CAP	2.00	EACH
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0071	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0072	801-06640	CONSTRUCTION SIGN, A	13.00	EACH
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	48.00	LFT
0075	801-07119	BARRICADE, III-B	24.00	LFT
0076	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	40.00	LFT
0077	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	11.00	LFT
0078	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	5.00	SFT
0079	802-91122	SIGN GROUND MOUNTED RESET	2.00	EACH

Call: 371

Contract: B -42038-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	203-08607	LINEAR GRADING	280.00	LFT

0009	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	398.00	SFT
0010	507-07482	CRACKS IN PCCP, ROUT AND SEAL	280.00	LFT
0011	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0012	621-06559	MULCHED SEEDING R	100.00	SYS
0013	628-09403	FIELD OFFICE, C	8.00	MOS
0014	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0015	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0016	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0017	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0018	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	16.00	MOS
0019	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0020	628-11977	COMPUTER SYSTEM	1.00	EACH
0021	709-51821	SURFACE SEAL	1.00	LS
0022	709-51821	SURFACE SEAL	1.00	LS
0023	709-51821	SURFACE SEAL	1.00	LS
0024	709-51821	SURFACE SEAL	1.00	LS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	709-51821	SURFACE SEAL	1.00	LS
0027	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	370.00	SFT
0028	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	938.00	SFT
0029	724-12777	BRIDGE EXPANSION JOINT SEAL, SS, REPLACE	53.00	LFT
0030	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4092.00	SYS
0031	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0032	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0033	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	22595.00	LFT
0034	801-06625	DETOUR ROUTE MARKER ASSEMBLY	11.00	EACH
0035	801-06640	CONSTRUCTION SIGN, A	64.00	EACH
0036	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0037	801-06710	FLASHING ARROW SIGN	26.00	DAY
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-07118	BARRICADE, III-A	204.00	LFT
0040	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0041	801-12042	TRUCK MOUNTED ATTENUATOR	49.00	DAY
0042	802-03821	SIGN, SHEET, WITH LEGEND,	2.00	EACH
0043	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	3.40	SYS
0044	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	640.00	LFT
0045	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3330.00	LFT
0046	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3330.00	LFT
0047	808-06716	LINE, REMOVE	3650.00	LFT
0048	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00	EACH
0049	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	23.00	EACH

Call: 381

Contract: B -42059-A

Section No.: 1

BRIDGE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	386.00	SYS
0012	203-02000	EXCAVATION, COMMON	937.00	CYS
0013	207-09935	SUBGRADE TREATMENT, TYPE IC	386.00	SYS
0014	207-12498	SUBGRADE TREATMENT, TYPE ID	2022.00	SYS
0015	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	30.00	EACH
0016	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	14.00	CYS
0017	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	386.00	SYS
0018	302-06464	SUBBASE FOR PCCP	96.00	CYS
0019	302-07455	DENSE GRADED SUBBASE	17.00	CYS
0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1084.00	SYS
0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	256.00	TON
0022	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	278.00	TON
0023	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	668.00	TON
0024	501-06266	PROFILOGRAPH PCCP	1.00	LS
0025	501-12707	QC/QA CONTINUOUS REINFORCED CONCRETE PAVEMENT, 11 IN.	386.00	SYS
0026	503-03489	RETROFITTED TIE BARS	50.00	EACH
0027	503-05240	D-1 CONTRACTION JOINT	88.00	LFT
0028	503-12478	TERMINAL JOINT, TYPE PCCP	88.00	LFT
0029	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	88.00	LFT
0030	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	176.00	SFT
0031	602-06729	BARRIER, DELINEATOR	20.00	EACH
0032	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	201.00	LFT
0033	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	101.00	SYS
0034	703-06029	REINFORCING BARS, EPOXY COATED	4138.00	LBS
0035	706-05734	CONCRETE BRIDGE RAILING TRANSITION, TBT	2.00	EACH
0036	709-51821	SURFACE SEAL	1.00	LS
0037	709-51821	SURFACE SEAL	1.00	LS

0038	718-08308	UNDERDRAIN PATCHING	120.00	LFT
0039	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0040	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20672.00	LFT
0041	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0042	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0043	801-06710	FLASHING ARROW SIGN	240.00	DAY
0044	801-06775	MAINTAINING TRAFFIC	1.00	LS
0045	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	744.00	LFT
0046	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0047	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0048	808-06716	LINE, REMOVE	5168.00	LFT
0049	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3608.00	LFT
0050	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3608.00	LFT
0051	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	450.00	LFT
0052	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH
0053	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	28.00	EACH

Call: 391

Contract: B -42087-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	602-06729	BARRIER, DELINEATOR	30.00	EACH
	0009	628-09403	FIELD OFFICE, C	4.00	MOS
	0010	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0011	709-51821	SURFACE SEAL	1.00	LS
	0012	709-51821	SURFACE SEAL	1.00	LS
	0013	709-51821	SURFACE SEAL	1.00	LS
	0014	709-51821	SURFACE SEAL	1.00	LS
	0015	709-51821	SURFACE SEAL	1.00	LS
	0016	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1251.00	SFT
	0017	727-90308	EPOXY INJECTION, CRACK PREPARATION	600.00	LFT
	0018	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00	GAL
	0019	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
	0020	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS

0021	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0022	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0023	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1855.00	SYS
0024	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	3.00	EACH
0025	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	19000.00	LFT
0026	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	9500.00	LFT
0027	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0028	801-06645	CONSTRUCTION SIGN, B	11.00	EACH
0029	801-06710	FLASHING ARROW SIGN	112.00	DAY
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
0031	801-07118	BARRICADE, III-A	72.00	LFT
0032	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0033	801-12042	TRUCK MOUNTED ATTENUATOR	18.00	DAY
0034	801-12324	LAW ENFORCEMENT OFFICER	320.00	HRS
0035	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	585.00	LFT
0036	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	845.00	LFT
0037	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	65.00	LFT
0038	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	160.00	LFT
0039	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	258.00	LFT
0040	808-75994	PRISMATIC REFLECTOR	6.00	EACH
0041	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.00	EACH
0042	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	10.00	EACH

Call: 401

Contract: B -42170-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-94954	BARRIER WALL, CONCRETE, REMOVE	200.00	LFT
0013	203-02000	EXCAVATION, COMMON	10.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	12050.00	DOL

0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	100.00	SYS
0017	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	20.00	TON
0018	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3472.00	SYS
0019	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	288.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	15624.00	LFT
0021	401-11785	LIQUID ASPHALT SEALANT	15624.00	LFT
0022	402-10087	HMA FOR TEMPORARY PAVEMENT, D	44.00	TON
0023	406-05521	ASPHALT FOR TACK COAT	3472.00	SYS
0024	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	144.00	SFT
0025	506-06334	PCCP PATCHING, PARTIAL DEPTH	66.00	SYS
0026	507-07482	CRACKS IN PCCP, ROUT AND SEAL	352.00	LFT
0027	507-08269	CRACKS IN PCCP, FILLED	400.00	LFT
0028	507-08271	JOINTS IN PCCP, FILLED	188.00	LFT
0029	507-08272	JOINTS IN PCCP, SAW AND SEAL	328.00	LFT
0030	602-01064	CONCRETE BARRIER	200.00	LFT
0031	602-06729	BARRIER, DELINEATOR	94.00	EACH
0032	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	7812.00	LFT
0033	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0034	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0035	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0036	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0037	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0038	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0039	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0040	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0041	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0042	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0043	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0044	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0046	621-06560	MULCHED SEEDING U	400.00	SYS
0047	628-09403	FIELD OFFICE, C	12.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0049	709-51821	SURFACE SEAL	1.00	LS
0050	709-51821	SURFACE SEAL	1.00	LS
0051	709-51821	SURFACE SEAL	1.00	LS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	710-09158	PATCHING CONCRETE STRUCTURES	688.00	SFT
0055	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0056	713-04858	TEMPORARY BRIDGE	1.00	LS

0057	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	104.00	LFT
0058	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	266.00	SFT
0059	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	11395.00	SFT
0060	724-09627	STRUCTURAL EXPANSION JOINT SEAL, M, REPLACE	328.00	LFT
0061	724-12773	BRIDGE EXPANSION JOINT, PCF	110.00	LFT
0062	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	12955.00	SYS
0063	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0064	801-03290	CONSTRUCTION SIGN, C	8.00	EACH
0065	801-03291	CONSTRUCTION SIGN, D	4.00	EACH
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	64702.00	LFT
0067	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	30720.00	LFT
0068	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1870.00	LFT
0069	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0070	801-06640	CONSTRUCTION SIGN, A	113.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	28.00	EACH
0072	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	856.00	EACH
0073	801-06710	FLASHING ARROW SIGN	178.00	DAY
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0076	801-07118	BARRICADE, III-A	48.00	LFT
0077	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	572.00	LFT
0078	801-08403	TEMPORARY TRAFFIC BARRIER TYPE 4	2952.00	LFT
0079	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	10.00	EACH
0080	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	42.00	DAY
0081	801-12081	PORTABLE SIGNAL	1.00	LS
0082	801-12652	QUEUE TRUCK	50.00	DAY
0083	808-06716	LINE, REMOVE	24135.00	LFT
0084	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0085	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1630.00	LFT
0086	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	8341.00	LFT
0087	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	9258.00	LFT
0088	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	948.00	LFT
0089	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	40.00	LFT
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	13491.00	LFT
0091	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	399.00	EACH
0092	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	391.00	EACH

Call: 411

Contract: B -42208-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No Item Code Description

Quantity Unit

0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	318.00	SFT
0008	709-51821	SURFACE SEAL	1.00	LS
0009	709-51821	SURFACE SEAL	1.00	LS
0010	709-51821	SURFACE SEAL	1.00	LS
0011	709-51821	SURFACE SEAL	1.00	LS
0012	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	734.00	SFT
0013	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4070.00	SYS
0014	801-04308	ROAD CLOSURE SIGN ASSEMBLY	59.00	EACH
0015	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	79.00	EACH
0016	801-06640	CONSTRUCTION SIGN, A	88.00	EACH
0017	801-06775	MAINTAINING TRAFFIC	1.00	LS
0018	801-07118	BARRICADE, III-A	384.00	LFT
0019	801-07119	BARRICADE, III-B	324.00	LFT
0020	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	69.00	LFT
0021	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1443.00	LFT
0022	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1443.00	LFT

Call: 421

Contract: B -42460-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-52710	SIDEWALK CONCRETE, REMOVE	106.00	SYS
0013	202-96133	PIPE, REMOVE	119.00	LFT
0014	203-02000	EXCAVATION, COMMON	208.00	CYS

0015	203-02070	BORROW	681.00	CYS
0016	203-51223	EXCAVATION, WATERWAY	137.00	CYS
0017	205-11626	PUMP AROUND	2.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	3179.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	207-12498	SUBGRADE TREATMENT, TYPE ID	462.00	SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	809.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	70.00	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	367.00	SYS
0025	306-08432	MILLING, APPROACH	108.00	SYS
0026	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	63.00	TON
0027	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	52.00	TON
0028	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	95.00	TON
0029	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	28.00	TON
0030	401-11785	LIQUID ASPHALT SEALANT	267.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	1181.00	SYS
0032	507-08271	JOINTS IN PCCP, FILLED	134.00	LFT
0033	603-97461	TEMPORARY FENCE	575.00	LFT
0034	604-06070	SIDEWALK, CONCRETE	87.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	11.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	1.50	SYS
0037	610-07487	HMA FOR APPROACHES, TYPE B	11.00	TON
0038	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH
0039	615-06505	MONUMENT, B	2.00	EACH
0040	616-05688	RIPRAP, CLASS 1	358.00	TON
0041	616-06405	RIPRAP, REVETMENT	11.00	TON
0042	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	487.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0044	621-06559	MULCHED SEEDING R	776.00	SYS
0045	621-06560	MULCHED SEEDING U	1620.00	SYS
0046	628-09401	FIELD OFFICE, A	6.00	MOS
0047	701-09558	TEST PILE, INDICATOR, PRODUCTION	50.00	LFT
0048	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0049	701-09656	PILE, STEEL PIPE, 0.250 IN., 12 IN.	725.00	LFT
0050	702-51015	CONCRETE, B, FOOTINGS	42.00	CYS
0051	703-06028	REINFORCING BARS	3314.00	LBS
0052	708-01112	GROUT, NON-SHRINK	1.00	CYS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	714-11168	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT X 7 FT	87.00	LFT
0055	714-11175	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 5 FT.	83.00	LFT
0056	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	6.00	LFT

0057	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	12.00	LFT
0058	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	22.00	LFT
0059	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	38.00	LFT
0060	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	EACH
0061	720-45065	INLET, N12	1.00	EACH
0062	720-45410	MANHOLE, C4	1.00	EACH
0063	720-45415	MANHOLE, D4	1.00	EACH
0064	720-92025	MANHOLE, D2	1.00	EACH
0065	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	32.00	SFT
0066	727-90308	EPOXY INJECTION, CRACK PREPARATION	50.00	LFT
0067	727-90309	EPOXY INJECTION, EPOXY MATERIAL	6.00	GAL
0068	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0069	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	649.00	SYS
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	18.00	EACH
0071	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2030.00	LFT
0072	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	586.00	LFT
0073	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	80.00	LFT
0074	801-06625	DETOUR ROUTE MARKER ASSEMBLY	76.00	EACH
0075	801-06640	CONSTRUCTION SIGN, A	51.00	EACH
0076	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0077	801-06775	MAINTAINING TRAFFIC	1.00	LS
0078	801-07118	BARRICADE, III-A	276.00	LFT
0079	801-07119	BARRICADE, III-B	180.00	LFT
0080	801-11990	TEMPORARY CURB RAMP	4.00	EACH
0081	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0082	801-12081	PORTABLE SIGNAL	1.00	LS
0083	801-12389	TEMPORARY PAVEMENT MARKING, REMOVABLE, 25 IN	46.00	LFT
0084	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	92.00	SYS
0085	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0086	808-06694	LINE, PAINT, SOLID, YELLOW, 8 IN.	344.00	LFT
0087	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	60.00	LFT
0088	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	729.00	LFT
0089	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	54.00	LFT
0090	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	36.00	LFT
0091	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.00	EACH

Call: 431

Contract: B -42468-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS

0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	493.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	203-02000	EXCAVATION, COMMON	97.00	CYS
0016	203-08607	LINEAR GRADING	827.00	LFT
0017	205-12108	STORMWATER MANAGEMENT BUDGET	10668.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	206-51220	EXCAVATION, WET	145.00	CYS
0021	206-51235	COFFERDAM	1.00	LS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	521.00	SYS
0023	302-06464	SUBBASE FOR PCCP	135.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	233.00	TON
0025	306-08043	MILLING, TRANSITION	1194.00	SYS
0026	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	44.00	TON
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	52.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	655.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	655.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	1344.00	SYS
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0032	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0033	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0034	601-02241	GUARDRAIL, REMOVE	939.00	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	282.00	LFT
0036	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	7.00	EACH
0037	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0038	602-06729	BARRIER, DELINEATOR	10.00	EACH
0039	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	522.00	SYS
0040	616-05688	RIPRAP, CLASS 1	1550.00	TON
0041	616-06405	RIPRAP, REVETMENT	60.00	TON
0042	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1095.00	SYS
0043	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	441.00	SYS

0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0045	621-06559	MULCHED SEEDING R	292.00 SYS
0046	621-06560	MULCHED SEEDING U	856.00 SYS
0047	621-06567	WATER	0.20 kGAL
0048	621-06574	SODDING	74.00 SYS
0049	628-09403	FIELD OFFICE, C	9.00 MOS
0050	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00 LS
0051	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	2.00 EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	77563.00 LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	168.00 EACH
0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	175.80 CYS
0055	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00 EACH
0056	706-11404	RAILING, STEEL PF-1	201.00 LFT
0057	706-11602	RAILING, CONCRETE PF-1	12.00 CYS
0058	709-51821	SURFACE SEAL	1.00 LS
0059	709-51821	SURFACE SEAL	1.00 LS
0060	710-09158	PATCHING CONCRETE STRUCTURES	60.00 SFT
0061	715-05407	PIPE, END BENT DRAIN, 6 IN.	94.00 LFT
0062	722-01066	HYDRODEMOLITION	533.00 SYS
0063	722-12380	BRIDGE DECK OVERLAY, BUDGET	8714.00 DOL
0064	722-12382	TRANSVERSE GROOVING	859.00 SYS
0065	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	533.00 SYS
0066	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	77.00 SFT
0067	722-51874	OVERLAY DAM	95.00 SFT
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH
0069	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	4430.00 LFT
0070	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1310.00 LFT
0071	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.00 LFT
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00 EACH
0073	801-06640	CONSTRUCTION SIGN, A	26.00 EACH
0074	801-06645	CONSTRUCTION SIGN, B	6.00 EACH
0075	801-06710	FLASHING ARROW SIGN	60.00 DAY
0076	801-06775	MAINTAINING TRAFFIC	1.00 LS
0077	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00 EACH
0078	801-07118	BARRICADE, III-A	120.00 LFT
0079	801-07119	BARRICADE, III-B	96.00 LFT
0080	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	355.00 LFT
0081	801-12081	PORTABLE SIGNAL	1.00 LS
0082	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	187.00 LFT
0083	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1385.00 LFT
0084	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	80.00 LFT

Call: 431

Contract: B -42468-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0085	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	533.00	SYS

Call: 431

Contract: B -42468-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME

Line

Item No	Item Code	Description	Quantity	Unit
0086	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	533.00	SYS

Call: 441

Contract: B -42498-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-01015	CLEARING AND GRUBBING	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	3416.00	SYS
0014	202-02273	CENTER CURB, CONCRETE, REMOVE	193.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	271.00	LFT
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0020	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
0021	202-94749	CURB, ASPHALT, REMOVE	745.00	LFT
0022	202-94954	BARRIER WALL, CONCRETE, REMOVE	929.00	LFT
0023	203-02000	EXCAVATION, COMMON	3970.00	CYS
0024	205-12108	STORMWATER MANAGEMENT BUDGET	12333.00	DOL

0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	89.00	CYS
0027	207-08266	SUBGRADE TREATMENT, TYPE III	4170.00	SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	4752.00	SYS
0029	211-06467	AGGREGATE FOR END BENT BACKFILL	89.00	CYS
0030	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	10.00	EACH
0031	213-09270	FLOWABLE BACKFILL, REMOVABLE	10.00	CYS
0032	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	4389.00	SYS
0033	301-12234	COMPACTED AGGREGATE NO. 53	86.00	CYS
0034	302-06464	SUBBASE FOR PCCP	741.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	203.00	TON
0036	306-08043	MILLING, TRANSITION	5296.00	SYS
0037	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	943.00	TON
0038	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	840.00	TON
0039	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	2056.00	TON
0040	401-10258	JOINT ADHESIVE, SURFACE	9968.00	LFT
0041	401-10259	JOINT ADHESIVE, INTERMEDIATE	9248.00	LFT
0042	401-11785	LIQUID ASPHALT SEALANT	9968.00	LFT
0043	402-10086	HMA FOR TEMPORARY PAVEMENT, C	250.00	TON
0044	406-05520	ASPHALT FOR TACK COAT	8.00	TON
0045	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0046	502-06329	PCCP, 12 IN.	1520.00	SYS
0047	503-03489	RETROFITTED TIE BARS	86.00	EACH
0048	503-05240	D-1 CONTRACTION JOINT	912.00	LFT
0049	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	1520.00	SYS
0050	503-12477	TERMINAL JOINT, TYPE HMA	521.00	LFT
0051	503-12478	TERMINAL JOINT, TYPE PCCP	171.00	LFT
0052	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	171.00	LFT
0053	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	288.00	SFT
0054	507-08269	CRACKS IN PCCP, FILLED	80.00	LFT
0055	601-02241	GUARDRAIL, REMOVE	2773.00	LFT
0056	601-06035	GUARDRAIL, RESET	200.00	LFT
0057	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	712.50	LFT
0058	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0059	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	9.00	EACH
0060	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0061	602-01064	CONCRETE BARRIER	813.00	LFT
0062	602-06729	BARRIER, DELINEATOR	20.00	EACH
0063	605-05523	CURB, HMA	745.00	LFT
0064	605-06140	CURB AND GUTTER, CONCRETE	271.00	LFT
0065	605-06200	CENTER CURB, A CONCRETE	434.00	LFT
0066	605-08636	CURB AND GUTTER, TURNOUT COMBINED	16.00	LFT

0067	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	4854.00	LFT
0068	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1716.00	SYS
0069	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	378.00	SYS
0070	616-51366	SLOPEWALL, CONCRETE, 5 IN.	20.00	SYS
0071	616-93772	INSPECTION HOLE	2.00	EACH
0072	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0073	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0074	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0075	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0076	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0077	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0078	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0079	621-03909	SEED MIXTURE, NATIVE	366.00	LBS
0080	628-11976	COMPUTER SYSTEM EQUIPMENT	6.00	EACH
0081	628-12684	FIELD OFFICE, E	14.00	MOS
0082	702-04325	TEMPORARY SHORING	1.00	LS
0083	702-04325	TEMPORARY SHORING	1.00	LS
0084	702-04325	TEMPORARY SHORING	1.00	LS
0085	703-06029	REINFORCING BARS, EPOXY COATED	175090.00	LBS
0086	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	994.00	EACH
0087	704-51002	CONCRETE, C, SUPERSTRUCTURE	170.00	CYS
0088	706-11600	RAILING, CONCRETE FC	2.00	CYS
0089	706-11601	RAILING, CONCRETE FT	35.00	CYS
0090	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	5.00	EACH
0091	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0092	706-51020	RAILING, CONCRETE C	12.00	CYS
0093	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0094	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	709-51821	SURFACE SEAL	1.00	LS
0098	709-51821	SURFACE SEAL	1.00	LS
0099	709-51821	SURFACE SEAL	1.00	LS
0100	710-09158	PATCHING CONCRETE STRUCTURES	720.00	SFT
0101	711-02707	ANCHOR PLATE	96.00	EACH
0102	711-51035	STRUCTURAL STEEL	6467.00	LBS
0103	711-51035	STRUCTURAL STEEL	3561.00	LBS
0104	711-51864	DRILLED HOLE	864.00	EACH
0105	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0106	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0107	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0108	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS

0109	711-96479	BOLT, REMOVE	256.00 EACH
0110	715-05407	PIPE, END BENT DRAIN, 6 IN.	568.00 LFT
0111	720-12797	CASTING, INLET, ADJUST TO GRADE	32.00 EACH
0112	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00 EACH
0113	722-01066	HYDRODEMOLITION	11530.00 SYS
0114	722-12380	BRIDGE DECK OVERLAY, BUDGET	125427.90 DOL
0115	722-12382	TRANSVERSE GROOVING	13922.00 SYS
0116	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	11530.00 SYS
0117	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	500.00 SFT
0118	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	100.00 SFT
0119	722-51874	OVERLAY DAM	936.00 SFT
0120	724-12773	BRIDGE EXPANSION JOINT, PCF	410.00 LFT
0121	726-12766	BEARING ASSEMBLY, SHIM EXISTING	10.00 EACH
0122	727-90308	EPOXY INJECTION, CRACK PREPARATION	728.00 LFT
0123	727-90309	EPOXY INJECTION, EPOXY MATERIAL	58.00 GAL
0124	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0125	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0126	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0127	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0128	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1848.00 SYS
0129	801-03290	CONSTRUCTION SIGN, C	12.00 EACH
0130	801-03291	CONSTRUCTION SIGN, D	9.00 EACH
0131	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00 EACH
0132	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	111686.60 LFT
0133	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	3.00 EACH
0134	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	188.00 LFT
0135	801-06625	DETOUR ROUTE MARKER ASSEMBLY	111.00 EACH
0136	801-06640	CONSTRUCTION SIGN, A	238.00 EACH
0137	801-06645	CONSTRUCTION SIGN, B	66.00 EACH
0138	801-06710	FLASHING ARROW SIGN	718.00 DAY
0139	801-06775	MAINTAINING TRAFFIC	1.00 LS
0140	801-07118	BARRICADE, III-A	336.00 LFT
0141	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	950.00 LFT
0142	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	10560.00 LFT
0143	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00 EACH
0144	802-04893	REFERENCE POST	12.00 EACH
0145	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	819.00 LFT
0146	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	4011.00 LFT
0147	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9966.00 LFT
0148	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1498.00 LFT
0149	808-06716	LINE, REMOVE	33233.00 LFT
0150	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	868.00 LFT

0151	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	210.00	LFT
0152	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5898.00	LFT
0153	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	7455.00	LFT
0154	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1077.00	LFT
0155	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	188.00	LFT
0156	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1118.00	LFT
0157	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	4.00	EACH
0158	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	312.00	LFT
0159	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	2198.00	LFT
0160	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	259.00	LFT
0161	808-12032	GROOVING FOR PAVEMENT MARKINGS	29660.00	LFT
0162	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	11024.00	LFT
0163	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	116.00	EACH

Call: 441

Contract: B -42498-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0164	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	11530.00	SYS

Call: 441

Contract: B -42498-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0165	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	11530.00	SYS

Call: 451

Contract: B -42504-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-51368	SLOPEWALL, REMOVE	262.00	SYS
0014	202-62420	BRIDGE RAILING, REMOVE	12.00	LFT
0015	203-02000	EXCAVATION, COMMON	859.00	CYS
0016	203-08607	LINEAR GRADING	2280.00	LFT
0017	205-11626	PUMP AROUND	1.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	18143.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1520.00	SYS
0022	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	44.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1520.00	SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	424.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	746.00	TON
0026	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	126.00	TON
0027	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	252.00	TON
0028	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	586.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	2280.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	2280.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	2280.00	LFT
0032	402-12364	ASPHALTIC PLUG JOINT	56.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	4560.00	SYS
0034	507-07482	CRACKS IN PCCP, ROUT AND SEAL	400.00	LFT
0035	507-08271	JOINTS IN PCCP, FILLED	410.00	LFT
0036	601-06035	GUARDRAIL, RESET	320.00	LFT
0037	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	19.00	LFT
0038	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	2280.00	LFT
0039	616-05689	RIPRAP, CLASS 2	285.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	228.00	SYS
0041	616-51367	SLOPEWALL, CONCRETE, 4 IN.	281.00	SYS
0042	616-93019	RIPRAP, GROUTED, 18 IN.	32.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0044	621-02770	EROSION CONTROL BLANKET	700.00	SYS
0045	621-03787	SEED MIXTURE D	11.00	LBS
0046	621-06559	MULCHED SEEDING R	700.00	SYS
0047	621-06565	MULCHING MATERIAL	1.30	TON
0048	628-09403	FIELD OFFICE, C	6.00	MOS
0049	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0050	702-51005	CONCRETE, A, SUBSTRUCTURE	6.00	CYS
0051	702-51863	FIELD DRILLED HOLE IN CONCRETE	128.00	EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	762.00	LBS

0053	706-09959	RAILING, CONCRETE FT	12.00	LFT
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	710-09158	PATCHING CONCRETE STRUCTURES	55.00	SFT
0059	715-06566	PIPE EXTENSION, CIRCULAR, 6 IN.	11.00	LFT
0060	715-09064	VIDEO INSPECTION FOR PIPE	350.00	LFT
0061	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	609.00	SFT
0062	725-11762	LINER PIPE, THERMOPLASTIC, DEFORMED, 36.4-38.5 SFT	350.00	LFT
0063	727-90308	EPOXY INJECTION, CRACK PREPARATION	1000.00	LFT
0064	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00	GAL
0065	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0066	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1552.00	SYS
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0068	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	1.00	EACH
0069	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	14310.00	LFT
0070	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20746.00	LFT
0071	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	16800.00	LFT
0072	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0074	801-06640	CONSTRUCTION SIGN, A	118.00	EACH
0075	801-06645	CONSTRUCTION SIGN, B	28.00	EACH
0076	801-06710	FLASHING ARROW SIGN	16.00	DAY
0077	801-06775	MAINTAINING TRAFFIC	1.00	LS
0078	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00	EACH
0079	801-07118	BARRICADE, III-A	152.00	LFT
0080	801-07119	BARRICADE, III-B	48.00	LFT
0081	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4964.00	LFT
0082	801-12042	TRUCK MOUNTED ATTENUATOR	16.00	DAY
0083	801-12081	PORTABLE SIGNAL	1.00	LS
0084	802-04893	REFERENCE POST	2.00	EACH
0085	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	990.00	LFT
0086	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1520.00	LFT
0087	808-06716	LINE, REMOVE	8856.00	LFT
0088	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	804.00	LFT
0089	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2701.00	LFT
0090	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	43.00	LFT
0091	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH

Call: 461

Contract: B -42569-A

Section No.: 1

BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
0001		105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002		109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003		109-08360	CONTRACT LIENS	1.00	DOL
0004		109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005		109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006		109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007		109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008		109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009		109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010		109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011		110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012		201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013		202-02240	PAVEMENT REMOVAL	2024.00	SYS
0014		202-06541	REMOVE	16.00	EACH
0015		202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0016		202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0017		202-51368	SLOPEWALL, REMOVE	2366.00	SYS
0018		202-86946	HANDHOLE, REMOVE	4.00	EACH
0019		202-90747	RETAINING WALL, REMOVE	400.00	LFT
0020		202-91385	INLET, REMOVE	3.00	EACH
0021		202-94954	BARRIER WALL, CONCRETE, REMOVE	2994.00	LFT
0022		202-96022	CONCRETE FOUNDATION, REMOVE	2.00	EACH
0023		202-96133	PIPE, REMOVE	230.00	LFT
0024		203-02000	EXCAVATION, COMMON	26477.00	CYS
0025		203-10106	AGGREGATE COLUMN	1.00	LS
0026		204-08552	VIBRATING WIRE SETTLEMENT SYSTEM	6.00	EACH
0027		204-08553	DATA LOGGING SYSTEM	6.00	EACH
0028		204-11633	VIBRATING WIRE PIEZOMETER	4.00	EACH
0029		205-12108	STORMWATER MANAGEMENT BUDGET	83278.00	DOL
0030		205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0031		205-12618	SWQCP PREPARATION	1.00	LS
0032		206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	641.00	CYS
0033		207-08264	SUBGRADE TREATMENT, TYPE II	253.00	SYS
0034		207-09934	SUBGRADE TREATMENT, TYPE IB	5532.00	SYS
0035		207-09935	SUBGRADE TREATMENT, TYPE IC	23695.00	SYS
0036		211-02050	B BORROW	9855.00	CYS
0037		211-06467	AGGREGATE FOR END BENT BACKFILL	304.00	CYS
0038		211-09264	STRUCTURE BACKFILL, TYPE 1	116.00	CYS
0039		211-09266	STRUCTURE BACKFILL, TYPE 3	7170.00	CYS

0040	214-11796	GEOGRID, TYPE IB	253.00	SYS
0041	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	5968.00	SYS
0042	301-12233	COMPACTED AGGREGATE NO. 8	139.00	CYS
0043	301-12234	COMPACTED AGGREGATE NO. 53	1592.00	CYS
0044	302-06464	SUBBASE FOR PCCP	156.00	CYS
0045	303-01180	COMPACTED AGGREGATE NO. 53	7432.00	TON
0046	304-07789	WIDENING WITH HMA, TYPE D	495.00	TON
0047	306-08042	MILLING, SCARIFICATION	1789.00	SYS
0048	306-08043	MILLING, TRANSITION	2735.00	SYS
0049	306-08159	MILLING, ASPHALT	1062.00	SYS
0050	306-08432	MILLING, APPROACH	185.00	SYS
0051	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2432.00	TON
0052	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	4035.00	TON
0053	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	14504.00	TON
0054	401-10258	JOINT ADHESIVE, SURFACE	15486.00	LFT
0055	401-10259	JOINT ADHESIVE, INTERMEDIATE	14982.00	LFT
0056	401-11785	LIQUID ASPHALT SEALANT	15486.00	LFT
0057	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	3241.00	TON
0058	402-10087	HMA FOR TEMPORARY PAVEMENT, D	584.00	TON
0059	406-05520	ASPHALT FOR TACK COAT	33.00	TON
0060	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0061	503-05240	D-1 CONTRACTION JOINT	46.00	LFT
0062	503-12477	TERMINAL JOINT, TYPE HMA	372.00	LFT
0063	601-02241	GUARDRAIL, REMOVE	2116.00	LFT
0064	601-06035	GUARDRAIL, RESET	267.00	LFT
0065	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	2086.00	LFT
0066	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0067	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0068	602-01064	CONCRETE BARRIER	2331.00	LFT
0069	602-06729	BARRIER, DELINEATOR	164.00	EACH
0070	602-11938	CONCRETE BARRIER, MODIFIED SECTION	130.00	CYS
0071	603-06045	FENCE, CHAIN LINK, 48 IN.	1753.00	LFT
0072	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	11054.00	LFT
0073	608-05741	WICK DRAIN	68858.00	LFT
0074	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	612.00	SYS
0075	610-07487	HMA FOR APPROACHES, TYPE B	154.00	TON
0076	615-06490	RIGHT-OF-WAY MARKER	26.00	EACH
0077	615-06505	MONUMENT, B	12.00	EACH
0078	615-06510	MONUMENT, C	2.00	EACH
0079	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0080	616-06405	RIPRAP, REVETMENT	242.00	TON
0081	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	424.00	SYS

0082	616-51367	SLOPEWALL, CONCRETE, 4 IN.	1488.00	SYS
0083	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0084	621-02770	EROSION CONTROL BLANKET	4334.00	SYS
0085	621-06545	FERTILIZER	2.00	TON
0086	621-06554	SEED MIXTURE U	841.00	LBS
0087	621-06565	MULCHING MATERIAL	10.00	TON
0088	621-06567	WATER	23.00	KGAL
0089	621-06574	SODDING	132.00	SYS
0090	621-06575	SODDING, NURSERY	5557.00	SYS
0091	621-12613	SEED MIXTURE SHADE	103.00	LBS
0092	628-09403	FIELD OFFICE, C	36.00	MOS
0093	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0094	628-12685	TELEPHONE SERVICE, A	36.00	MOS
0095	629-12029	PLANT GROWTH LAYER	29703.00	SYS
0096	701-06011	DYNAMIC PILE LOAD TEST	6.00	EACH
0097	701-09557	TEST PILE, DYNAMIC, PRODUCTION	483.00	LFT
0098	701-09559	TEST PILE, DYNAMIC, RESTRIKE	6.00	EACH
0099	701-09891	PILE SHOE, HP 12 X 84	126.00	EACH
0100	701-12304	VIBRATION MONITORING	1.00	LS
0101	701-95782	PILE, STEEL H, HP, 12 X 84	8004.00	LFT
0102	702-04325	TEMPORARY SHORING	1.00	LS
0103	702-51005	CONCRETE, A, SUBSTRUCTURE	671.30	CYS
0104	702-51015	CONCRETE, B, FOOTINGS	60.70	CYS
0105	702-51863	FIELD DRILLED HOLE IN CONCRETE	900.00	EACH
0106	702-92857	CONCRETE, C, SUBSTRUCTURE	244.10	CYS
0107	703-06028	REINFORCING BARS	112641.00	LBS
0108	703-06029	REINFORCING BARS, EPOXY COATED	511096.00	LBS
0109	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	2316.00	EACH
0110	704-51002	CONCRETE, C, SUPERSTRUCTURE	1113.80	CYS
0111	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	109.00	SYS
0112	706-09959	RAILING, CONCRETE FT	486.00	LFT
0113	706-09959	RAILING, CONCRETE FT	576.00	LFT
0114	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0115	709-51821	SURFACE SEAL	1.00	LS
0116	709-51821	SURFACE SEAL	1.00	LS
0117	711-51038	STRUCTURAL STEEL	1.00	LS
0118	711-51038	STRUCTURAL STEEL	1.00	LS
0119	711-51820	TEMPORARY SUPPORT	1.00	LS
0120	711-51820	TEMPORARY SUPPORT	1.00	LS
0121	711-51864	DRILLED HOLE	316.00	EACH
0122	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0123	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS

0124	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	8599.00	LFT
0125	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	388.00	LFT
0126	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	78.00	LFT
0127	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	180.00	LFT
0128	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	40.00	LFT
0129	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	315.00	LFT
0130	715-05407	PIPE, END BENT DRAIN, 6 IN.	508.00	LFT
0131	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	1116.00	LFT
0132	715-09064	VIDEO INSPECTION FOR PIPE	258.00	LFT
0133	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0134	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	EACH
0135	715-46010	PIPE END SECTION, DIAMETER 18 IN.	6.00	EACH
0136	718-06528	OUTLET PROTECTOR, 1	14.00	EACH
0137	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0138	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	6515.00	SYS
0139	718-52610	AGGREGATE FOR UNDERDRAINS	774.00	CYS
0140	720-02442	PIPE PLUG EXISTING	1.00	EACH
0141	720-12797	CASTING, INLET, ADJUST TO GRADE	20.00	EACH
0142	724-12773	BRIDGE EXPANSION JOINT, PCF	200.00	LFT
0143	735-10241	TEMPORARY WIRE FACING	9377.00	SFT
0144	735-10242	TEMPORARY WALL ERECTION	9377.00	SFT
0145	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0146	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0147	801-06201	TEMPORARY PANEL SIGNS	105.00	SFT
0148	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	10024.00	LFT
0149	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	131160.00	LFT
0150	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	EACH
0151	801-06640	CONSTRUCTION SIGN, A	128.00	EACH
0152	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0153	801-06710	FLASHING ARROW SIGN	48.00	DAY
0154	801-06775	MAINTAINING TRAFFIC	1.00	LS
0155	801-07118	BARRICADE, III-A	410.00	LFT
0156	801-07119	BARRICADE, III-B	130.00	LFT
0157	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	136.00	LFT
0158	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	1453.00	LFT
0159	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5230.00	LFT
0160	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	1506.00	LFT
0161	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2004.00	LFT
0162	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0163	801-94295	SIGNAL HEAD RELOCATE	4.00	EACH
0164	802-02475	SIGN, PANEL, RELOCATE	5.00	EACH
0165	802-03783	SIGN, PANEL, REMOVE	2.00	EACH

0166	802-04089	SIGN, SHEET, REMOVE	1.00 EACH
0167	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	100.00 LFT
0168	802-07057	SIGN, PANEL, WITH LEGEND	625.00 SFT
0169	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00 EACH
0170	802-07060	SIGN, SHEET, RELOCATE	9.00 EACH
0171	802-09224	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE D	1.00 EACH
0172	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	1.00 EACH
0173	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	1.00 EACH
0174	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	18.00 SFT
0175	802-11818	OVERHEAD SIGN STRUCTURE, BUTTERFLY CANTILEVER	1.00 EACH
0176	802-11818	OVERHEAD SIGN STRUCTURE, BUTTERFLY CANTILEVER	1.00 EACH
0177	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00 EACH
0178	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	4.00 EACH
0179	802-12351	OVERHEAD BUTTERFLY CANTILEVER SIGN STRUCTURE FOUNDATION, DRILLED SHAFT 45 INCH	2.00 EACH
0180	802-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	1.00 EACH
0181	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.00 EACH
0182	802-76095	STRUCTURAL STEEL, BREAKAWAY	4214.00 LBS
0183	805-03968	CONDUIT, PVC, 1 IN. SCHEDULE 80	165.00 LFT
0184	805-04973	CONDUIT	679.00 LFT
0185	805-04973	CONDUIT	340.00 LFT
0186	805-04973	CONDUIT	1019.00 LFT
0187	805-06595	CONDUIT, PVC, 2 IN.	100.00 LFT
0188	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	265.00 LFT
0189	807-02191	HANDHOLE LIGHTING	1.00 EACH
0190	807-04651	WIRE	400.00 LFT
0191	807-04651	WIRE	400.00 LFT
0192	807-78590	HANDHOLE	2.00 EACH
0193	807-86955	CABLE-DUCT MARKER	5.00 EACH
0194	807-86955	CABLE-DUCT MARKER	4.00 EACH
0195	807-86955	CABLE-DUCT MARKER	20.00 EACH
0196	808-06716	LINE, REMOVE	18563.00 LFT
0197	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0198	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	10903.00 LFT
0199	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	11070.00 LFT
0200	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	225.00 LFT
0201	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	3760.00 LFT
0202	808-12032	GROOVING FOR PAVEMENT MARKINGS	25148.00 LFT
0203	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	98.00 LFT
0204	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	39.00 LFT
0205	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	188.00 EACH
0206	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	233.00 EACH
0207	809-04970	FIBER OPTIC	388.00 EACH

0208	809-04970	FIBER OPTIC	1.00 EACH
0209	809-04970	FIBER OPTIC	1.00 EACH
0210	809-04970	FIBER OPTIC	1.00 EACH
0211	809-94971	FIBER OPTIC CABLE	5000.00 LFT

Call: 471

Contract: B -42869-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0009	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0010	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0011	628-09401	FIELD OFFICE, A	4.00	MOS
0012	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0013	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4570.00	LFT
0014	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0015	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
0017	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0018	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	105.00	LFT
0019	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	420.00	LFT
0020	808-06716	LINE, REMOVE	525.00	LFT

Call: 481

Contract: B -42920-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0012	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0013	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0014	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0015	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0016	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0017	628-09403	FIELD OFFICE, C	12.00	MOS
0018	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0019	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0020	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0021	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0022	628-11977	COMPUTER SYSTEM	1.00	EACH
0023	628-12685	TELEPHONE SERVICE, A	12.00	MOS
0024	709-51821	SURFACE SEAL	1.00	LS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	709-51821	SURFACE SEAL	1.00	LS
0027	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	11.00	EACH
0028	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5000.00	LFT
0029	801-06640	CONSTRUCTION SIGN, A	69.00	EACH
0030	801-06710	FLASHING ARROW SIGN	80.00	DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00	LS
0032	801-07118	BARRICADE, III-A	100.00	LFT
0033	801-07119	BARRICADE, III-B	50.00	LFT
0034	801-12042	TRUCK MOUNTED ATTENUATOR	80.00	DAY

Call: 491

Contract: B -43113-A

Section No.: 1 BRIDGE PAINTING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS

0010	203-02020	EXCAVATION, UNCLASSIFIED	226.00	CYS
0011	205-11626	PUMP AROUND	4.00	EACH
0012	205-12108	STORMWATER MANAGEMENT BUDGET	3000.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	205-12618	SWQCP PREPARATION	1.00	LS
0015	301-12231	COMPACTED AGGREGATE NO. 2	226.00	CYS
0016	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
0017	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
0018	701-12769	HDPE PILE ENCASEMENT SYSTEM	1.00	LS
0019	702-51005	CONCRETE, A, SUBSTRUCTURE	3.00	CYS
0020	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 521

Contract: T -40326-A

Section No.: 1 SIGN REPLACEMENT

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	801-06775	MAINTAINING TRAFFIC	1.00	LS
0009	802-04089	SIGN, SHEET, REMOVE	20.00	EACH
0010	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	19938.00	LFT
0011	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2163.00	EACH
0012	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0013	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	11198.00	SFT
0014	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	2618.00	SFT

Call: 531

Contract: T -40371-A

Section No.: 1 PEDESTRIAN FACILITIES IMPROVEMENT

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	270.00	SYS
0013	202-02278	CURB, CONCRETE, REMOVE	5432.00	LFT
0014	202-02772	CASTING, REMOVE	2.00	EACH
0015	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	9.00	CYS
0016	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	9.00	CYS
0017	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	9.00	CYS
0018	202-52710	SIDEWALK CONCRETE, REMOVE	3210.00	SYS
0019	202-91385	INLET, REMOVE	2.00	EACH
0020	202-91840	FENCE, CHAIN. LINK, REMOVE	10.00	LFT
0021	202-96133	PIPE, REMOVE	3.00	LFT
0022	202-98370	POLE, REMOVE	1.00	EACH
0023	203-02070	BORROW	130.00	CYS
0024	205-12108	STORMWATER MANAGEMENT BUDGET	11770.00	DOL
0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	56.00	SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	44.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	4.00	CYS
0029	304-12625	HMA PATCHING FULL DEPTH TYPE C	14.00	TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4794.00	SYS
0031	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0032	604-03643	BRICK PAVERS	19.00	SYS
0033	604-06070	SIDEWALK, CONCRETE	1612.00	SYS
0034	604-08086	CURB RAMP, CONCRETE	1713.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	246.00	SYS
0036	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	1.00	SYS
0037	605-06120	CURB, CONCRETE	4419.00	LFT
0038	605-06121	CURB, CONCRETE B	238.00	LFT
0039	605-06140	CURB AND GUTTER, CONCRETE	656.00	LFT
0040	610-07488	HMA FOR APPROACHES, TYPE C	410.00	TON
0041	610-09108	PCCP FOR APPROACHES, 9 IN.	23.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0043	621-06560	MULCHED SEEDING U	247.00	SYS
0044	621-06567	WATER	1.00	KGAL
0045	621-06570	TOPSOIL	46.00	CYS
0046	621-06575	SODDING, NURSERY	126.00	SYS
0047	628-09403	FIELD OFFICE, C	12.00	MOS

0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0049	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	119.00 LFT
0050	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	43.00 TON
0051	715-09064	VIDEO INSPECTION FOR PIPE	119.00 LFT
0052	720-01355	INLET, CLEAN EXISTING	5.00 EACH
0053	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00 EACH
0054	720-03905	CATCH BASIN, A	2.00 EACH
0055	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00 EACH
0056	720-44020	CASTING, 3, FURNISH AND ADJUST TO GRADE	2.00 EACH
0057	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	10.00 EACH
0058	720-45010	INLET, A3	10.00 EACH
0059	801-03290	CONSTRUCTION SIGN, C	2.00 EACH
0060	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00 EACH
0061	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00 EACH
0062	801-06640	CONSTRUCTION SIGN, A	212.00 EACH
0063	801-06645	CONSTRUCTION SIGN, B	392.00 EACH
0064	801-06710	FLASHING ARROW SIGN	896.00 DAY
0065	801-06775	MAINTAINING TRAFFIC	1.00 LS
0066	801-07118	BARRICADE, III-A	120.00 LFT
0067	801-07119	BARRICADE, III-B	96.00 LFT
0068	802-04089	SIGN, SHEET, REMOVE	2.00 EACH
0069	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	89.00 LFT
0070	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	470.00 LFT
0071	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	18.00 EACH
0072	802-07060	SIGN, SHEET, RELOCATE	21.00 EACH
0073	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	252.00 SFT
0074	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	18.00 SFT
0075	804-11921	DELINEATOR POST FLEXIBLE, TYPE II	35.00 EACH
0076	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.00 EACH
0077	805-01842	HANDHOLE SIGNAL TYPE 1	5.00 EACH
0078	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	13.00 EACH
0079	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	55.00 LFT
0080	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0081	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	14.00 EACH
0082	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	10.00 EACH
0083	805-05405	SIGNAL POLE, PEDESTAL, 4FT	7.00 EACH
0084	805-11799	RECTANGULAR RAPID FLASHING BEACON	28.00 EACH
0085	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	280.00 LFT
0086	805-11817	PEDESTRIAN PUSH BUTTON, APS	17.00 EACH
0087	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	2.00 EACH
0088	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	154.00 LFT
0089	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	902.00 LFT

0090	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GA	43.00	LFT
0091	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	1.00	EACH
0092	805-99162	SIGNAL POLE, PEDESTAL, 11 FT	2.00	EACH
0093	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	14251.00	LFT
0094	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	223.00	LFT
0095	808-09968	PAVEMENT MARKING	8561.00	SFT
0096	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	25.00	LFT
0097	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	150.00	LFT
0098	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	170.00	LFT
0099	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	343.00	LFT
0100	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	1714.00	LFT
0101	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	236.00	LFT
0102	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	696.00	LFT
0103	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	15.00	LFT
0104	808-12032	GROOVING FOR PAVEMENT MARKINGS	1094.00	LFT
0105	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	207.00	LFT
0106	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	8169.00	LFT
0107	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	23030.00	LFT

Call: 541

Contract: T -41376-A

Section No.: 1 PEDESTRIAN FLASHING BEACON

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	38.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0010	202-02278	CURB, CONCRETE, REMOVE	48.00	LFT
	0011	202-02279	CURB AND GUTTER, REMOVE	59.00	LFT
	0012	202-52710	SIDEWALK CONCRETE, REMOVE	52.00	SYS
	0013	202-96151	TRANSPORTATION OF SALVAGEABLE ITEMS	1.00	LS
	0014	203-02000	EXCAVATION, COMMON	35.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	1358.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	301-12234	COMPACTED AGGREGATE NO. 53	1.00	CYS
	0018	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	4.00	TON

0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	43.00	SYS
0020	604-06070	SIDEWALK, CONCRETE	61.00	SYS
0021	604-08086	CURB RAMP, CONCRETE	171.00	SYS
0022	604-12083	DETECTABLE WARNING SURFACES	21.00	SYS
0023	605-06120	CURB, CONCRETE	10.00	LFT
0024	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	26.00	LFT
0025	605-90726	CURB, CONCRETE, DEPRESSED	65.00	LFT
0026	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	34.00	LFT
0027	621-06567	WATER	1.00	KGAL
0028	621-06575	SODDING, NURSERY	12.00	SYS
0029	628-09401	FIELD OFFICE, A	8.00	MOS
0030	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0031	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0032	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0033	628-11783	CELLULAR TELEPHONE SERVICE, 2000 MIN.	8.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0035	628-11977	COMPUTER SYSTEM	1.00	EACH
0036	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	8.00	LFT
0037	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0038	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	2.00	EACH
0039	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	90.00	LFT
0040	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0041	801-06645	CONSTRUCTION SIGN, B	53.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, III-A	71.00	LFT
0044	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	16.00	SYS
0045	802-04089	SIGN, SHEET, REMOVE	12.00	EACH
0046	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	105.00	LFT
0047	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00	EACH
0048	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	56.00	EACH
0049	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0050	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	282.00	SFT
0051	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	261.00	SFT
0052	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	38.00	EACH
0053	805-04133	SIGNAL POLE, PEDESTAL, 12FT	10.00	EACH
0054	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	28.00	EACH
0055	805-08475	FLASHER MODERNIZATION	1.00	LS
0056	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	28.00	EACH
0057	805-11799	RECTANGULAR RAPID FLASHING BEACON	10.00	EACH
0058	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	10.00	EACH
0059	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	396.00	LFT
0060	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	26.00	LFT

Call: 551

Contract: T -41388-A

Section No.: 1

PEDESTRIAN INTERSECTION IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-01015	CLEARING AND GRUBBING	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	29.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	1169.00	LFT
0013	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	7.00	CYS
0014	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	7.00	CYS
0015	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	7.00	CYS
0016	202-06541	REMOVE	1.00	EACH
0017	202-52710	SIDEWALK CONCRETE, REMOVE	531.00	SYS
0018	202-96022	CONCRETE FOUNDATION, REMOVE	1.00	EACH
0019	203-02000	EXCAVATION, COMMON	96.00	CYS
0020	203-02055	EMBANKMENT	46.00	CYS
0021	205-12108	STORMWATER MANAGEMENT BUDGET	15625.00	DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	304.00	SYS
0024	304-12625	HMA PATCHING FULL DEPTH TYPE C	121.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	442.00	SYS
0026	401-07327	QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	37.00	TON
0027	406-05520	ASPHALT FOR TACK COAT	8.00	TON
0028	506-06333	PCCP PATCHING, FULL DEPTH	70.00	SYS
0029	604-06070	SIDEWALK, CONCRETE	248.00	SYS
0030	604-08086	CURB RAMP, CONCRETE	321.00	SYS
0031	604-12083	DETECTABLE WARNING SURFACES	83.00	SYS
0032	605-06120	CURB, CONCRETE	725.00	LFT
0033	605-06140	CURB AND GUTTER, CONCRETE	64.00	LFT
0034	605-97937	CURB AND GUTTER, ROLL CURB	634.00	LFT
0035	621-06560	MULCHED SEEDING U	619.00	SYS
0036	621-06570	TOPSOIL	66.00	CYS

0037	628-09401	FIELD OFFICE, A	5.00	MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0039	628-12685	TELEPHONE SERVICE, A	6.00	MOS
0040	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	44.00	LFT
0041	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	32.00	LFT
0042	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	1424.00	LFT
0043	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	EACH
0044	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0045	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	5.00	EACH
0046	720-45010	INLET, A3	4.00	EACH
0047	720-45025	INLET, D6	2.00	EACH
0048	801-06775	MAINTAINING TRAFFIC	1.00	LS
0049	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	1.00	EACH
0050	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	4.00	SFT
0051	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	18.00	SFT
0052	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0053	805-11799	RECTANGULAR RAPID FLASHING BEACON	2.00	EACH
0054	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	2.00	EACH
0055	805-99162	SIGNAL POLE, PEDESTAL, 11 FT	2.00	EACH
0056	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	431.00	LFT
0057	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	2.00	SYS
0058	808-06368	TRANSVERSE MARKING, REMOVE	158.00	LFT
0059	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	172.00	LFT
0060	808-06716	LINE, REMOVE	923.00	LFT
0061	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	298.00	LFT
0062	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	946.00	LFT
0063	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	189.00	LFT
0064	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	5.00	EACH

Call: 561

Contract: T -41801-A

Section No.: 1 SIGNING INSTALLATION AND REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	801-06640	CONSTRUCTION SIGN, A	8.00	EACH

0009	801-06775	MAINTAINING TRAFFIC	1.00	LS
0010	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0011	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	2090.00	LFT
0012	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	1602.00	SFT

Call: 571

Contract: T -41882-A

Section No.: 1 NEW SIGN INSTALLATION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	202-06580	CONTAMINATED SOIL, REMOVE	2.00	CYS
	0009	801-06640	CONSTRUCTION SIGN, A	19.00	EACH
	0010	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
	0011	801-06710	FLASHING ARROW SIGN	2.00	DAY
	0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0013	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	44.00	EACH
	0014	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
	0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	192.00	SFT
	0016	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	24.00	EACH
	0017	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	24.00	EACH
	0018	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	24.00	EACH
	0019	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	24.00	EACH

Call: 581

Contract: T -42486-A

Section No.: 1 RAISED PAVEMENT MARKINGS, REFURBISHED

Line	Item No	Item Code	Description	Quantity	Unit
	0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0002	109-08360	CONTRACT LIENS	1.00	DOL
	0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0006	801-06710	FLASHING ARROW SIGN	180.00	DAY
	0007	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0008	801-92448	CONSTRUCTION SIGNS MOBILE	1800.00	DAY

0009	808-75994	PRISMATIC REFLECTOR	43118.00 EACH
0010	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6468.00 EACH
0011	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6468.00 EACH

Call: 591

Contract: T -42518-A

Section No.: 1 RAISED PAVEMENT MARKINGS, REFURBISHED

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	801-06710	FLASHING ARROW SIGN	90.00	DAY
0007	801-06775	MAINTAINING TRAFFIC	1.00	LS
0008	801-12324	LAW ENFORCEMENT OFFICER	100.00	HRS
0009	801-92448	CONSTRUCTION SIGNS MOBILE	90.00	DAY
0010	808-75994	PRISMATIC REFLECTOR	26092.00	EACH
0011	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1305.00	EACH
0012	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2609.00	EACH

Call: 621

Contract: TM-43526-A

Section No.: 1 TRAFFIC SIGNAL MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-52710	SIDEWALK CONCRETE, REMOVE	50.00	SYS
0008	604-06070	SIDEWALK, CONCRETE	50.00	SYS
0009	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS
0011	802-03821	SIGN, SHEET, WITH LEGEND,	6.00	EACH
0012	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	EACH
0013	805-01816	SIGNAL SUPPORT FOUNDATION, 36 IN. X 36 IN. X 96 IN.	1.00	EACH
0014	805-01820	SIGNAL POLE, STEEL STRAIN, INSTALL	1.00	EACH
0015	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	1.00	EACH
0016	805-01835	TRAFFIC SIGNAL HEAD, REPAIR	1.00	EACH

0017	805-01842	HANDHOLE SIGNAL TYPE 1	1.00 EACH
0018	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	2.00 EACH
0019	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	500.00 LFT
0020	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	1.00 EACH
0021	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	1.00 EACH
0022	805-03372	TETHER FOR SIGNAL	1.00 EACH
0023	805-04952	CONTROLLER AND CABINET	1.00 EACH
0024	805-06364	FIBER OPTIC BREAKOUT KIT	2.00 EACH
0025	805-06595	CONDUIT, PVC, 2 IN.	100.00 LFT
0026	805-08464	RADIO INTERCONNECT	1.00 EACH
0027	805-09845	CONTACT CLOSURE CARD	1.00 EACH
0028	805-09846	RECEIVER PROCESSOR	1.00 EACH
0029	805-10107	WIRELESS MAGNETOMETER DETECTOR	1.00 EACH
0030	805-10108	WIRELESS REPEATER	1.00 EACH
0031	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	1.00 EACH
0032	805-11540	MICROLOOP DETECTOR PROBE	1.00 EACH
0033	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	1.00 EACH
0034	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00 EACH
0035	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0036	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	1.00 EACH
0037	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0038	805-78420	DISCONNECT HANGER	1.00 EACH
0039	805-78445	SIGNAL SERVICE	1.00 EACH
0040	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	75.00 LFT
0041	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	10000.00 LFT
0042	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	300.00 LFT
0043	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	300.00 LFT
0044	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	300.00 LFT
0045	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	500.00 LFT
0046	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	7000.00 LFT
0047	805-78785	SIGNAL DETECTOR HOUSING	20.00 EACH
0048	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1700.00 LFT
0049	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0050	805-78930	CONTROLLER CABINET FOUNDATION, M	1.00 EACH
0051	805-91706	ANCHOR BOLT REPAIR	1.00 EACH
0052	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	1.00 EACH
0053	805-97509	CONTROLLER CABINET FOUNDATION M MODIFY TO P1	1.00 EACH
0054	807-87085	ELECTRICIAN	150.00 HRS