



TYPE D-1 SAWED CONTRACTION JOINT SEALANT OPTIONS

NOTES

1. Transverse joints shall be constructed perpendicular to the centerline with a maximum spacing of 18'-0" unless otherwise specified.
2. The configuration of the preformed elastomeric joint seal shall be a 9/16" to 5/8" wide seal with at least a five cell internal design. The seal height shall be 9/16" to 13/16" in uncompressed stage.
3. For transverse construction joints, the initial saw cut may be eliminated.

INDIANA DEPARTMENT OF TRANSPORTATION											
TRANSVERSE JOINT SEALS											
MARCH 2005											
STANDARD DRAWING NO. E 503-CCPJ-06											
	<table style="width: 100%; border: none;"> <tr> <td style="border: none;">/s/ Richard L. VanCleave</td> <td style="border: none; text-align: right;">3-01-05</td> </tr> <tr> <td style="border: none;">DESIGN STANDARDS ENGINEER</td> <td style="border: none; text-align: right;">DATE</td> </tr> <tr> <td colspan="2" style="border: none;"> </td> </tr> <tr> <td style="border: none;">/s/ Richard K. Smutzer</td> <td style="border: none; text-align: right;">3-01-05</td> </tr> <tr> <td style="border: none;">CHIEF HIGHWAY ENGINEER</td> <td style="border: none; text-align: right;">DATE</td> </tr> </table>	/s/ Richard L. VanCleave	3-01-05	DESIGN STANDARDS ENGINEER	DATE			/s/ Richard K. Smutzer	3-01-05	CHIEF HIGHWAY ENGINEER	DATE
/s/ Richard L. VanCleave	3-01-05										
DESIGN STANDARDS ENGINEER	DATE										
/s/ Richard K. Smutzer	3-01-05										
CHIEF HIGHWAY ENGINEER	DATE										
DESIGN STANDARDS ENGINEER											