

Reduced Speed Advance Warning Sign Assembly

Worksite Speed Limit Sign Assembly

XG 20-5

All Dimensions are in mm unless otherwise specified.

INDIANA DEPARTMENT OF TRANSPORTATION


Amber strobe

light (typ.)

WORKSITE SPEED LIMIT SIGN ASSEMBLY

SEPTEMBER 2007

STANDARD DRAWING NO. 801-TCDV-10



/s/ Richard L. VanCleave DESIGN STANDARDS ENGINEER

/s/Mark A. Miller CHIEF HIGHWAY ENGINEER 09/04/07 DATE

09/04/07

DATE

General Notes:

- 1. If not trailer mounted, signs and supports shall meet NCHRP 350 crash evaluation criteria.
- 2. Mounting height shall be 2130 for interstate applications.
- 3. Advance Warning Sign speed shall match Worksite Sign.
- 4. The Work Site Speed Limit shall be 45 MPH, or 10 MPH below the posted speed limit for the roadway under construction, whichever is less.