INDEX	
SHEET NO.	SUBJECT
1	Fabrication Tolerances Index and General Notes
2	Fabrication Tolerances Prestressed Box Beam
3	Fabrication Tolerances Prestressed I-Beam and Bulb-Tee Beam
4	Fabrication Tolerances Prestressed NEXT Beam

## **GENERAL NOTES:**

- 1. Tolerances shown are maximum permissible variations from the dimensions shown on the shop drawings. Tolerances shall not be considered cumulative. Longitudinal tolerances are based on design length. Casting length shall be adjusted to compensate for shrinkage and plastic flow.
- 2. Mild reinforcing bar concrete cover tolerance shall be +3/8 in. to -1/8 in.
- 3. Vertical camber shall be checked within 72 hours of transfer of prestressing force. Camber shall be measured within three days prior to shipping and any exceedances shall be reported to the Engineer prior to shipping.
- 4. Tolerance in length of beam shall be checked after the final curing phase and within three days prior to shipping.
- 5. Tolerance in horizontal alignment shall be checked immediately after de-tensioning is complete, prior to removal from bed.
- 6. At concrete bearing area, deviation from plane surface when tested in all directions of the plane surface with a steel straightedge shall not be more than  $\pm 1/8$  in.
- 7. Local smoothness of any surface shall not deviate from a 10 ft straightedge by more than 1/8 in.


## INDIANA DEPARTMENT OF TRANSPORTATION

## FABRICATION TOLERANCES INDEX AND GENERAL NOTES

SEPTEMBER 2025

STANDARD DRAWING NO. E 7

E 707-BPBF-01



DESIGN STANDARDS ENGINEER DATE

03/20/2025

CHIEF ENGINEER DATE

DATE

