

**INDIANA DEPARTMENT OF TRANSPORTATION**

**INTER-DEPARTMENT COMMUNICATION  
Standards Section -- Room N642**

March 17, 1999

**DESIGN MEMORANDUM No. 99-03  
TECHNICAL ADVISORY**

**TO: All Design, Operations, and District Personnel, and Consultants**

**FROM: /s/ Richard L. VanCleave  
Richard L. VanCleave  
Design Policy Engineer  
Technical Services Division**

**SUBJECT: Traffic Controls for Construction Operations**

**EFFECTIVE: September 1, 1999**

The Standards Committee has approved extensive revisions to Standard Specifications Section 801, Traffic Controls for Construction and Maintenance Operations. These changes have affected some of the pay items in this section. The revisions will be shown in the Supplemental Specifications and standard drawings effective September 1, 1999. They will therefore be effective for all contracts beginning with the September 14, 1999, letting.

The following standard sheets have been revised.

801-TCDV-01      Detours 2A1

The following standard sheets have been developed. The english versions will be found in the recurring drawings.

801-TCDV-10	E 801-TCDV-10
801-TCDV-11	E 801-TCDV-11
801-TCSN-12	E 801-TCSN-12
801-TCSN-13	E 801-TCSB-13

The list of new code numbers and pay items is as follows:

801-06196	Detour Route Marker Assembly, Multiple Routes; EACH
801-02949	Drum, Permanent; EACH
801-06197	Flexible Channelizer, Permanent; EACH
801-06198	Patroller; DAY
801-06199	Road Closure Sign Assembly, Permanent; EACH
801-06201	Temporary Panel Signs; m <sup>2</sup> / SFT
801-06202	Temporary Panel Sign Supports; m / LFT
801-06203	Temporary Pavement Marking, 100 mm / 4 in.; m / LFT
801-06204	Temporary Pavement Marking, 125 mm / 5 in.; m / LFT
801-06206	Temporary Pavement Marking, 150 mm / 6 in.; m / LFT
801-06207	Temporary Pavement Marking, Removable, 100 mm / 4 in.; m / LFT
801-06208	Temporary Pavement Marking, Removable, 125 mm / 5 in.; m / LFT
801-06209	Temporary Pavement Marking, Removable, 150 mm / 6 in.; m / LFT
801-01504	Temporary Pavement Message Marking, Lane Indication Arrow; EACH
801-01505	Temporary Pavement Message Marking, Word 'Only'; EACH
801-01506	Temporary Pavement Message Marking, Word 'R X R'; EACH
801-06211	Temporary Pavement Message Marking, Removable, Lane Indication Arrow; EACH
801-06212	Temporary Pavement Message Marking, Removable, Word 'Only'; EACH
801-06213	Temporary Pavement Message Marking, Removable, Word 'R X R'; EACH
801-06214	Temporary Transverse Pavement Marking, 150 mm / 6 in.; m / LFT
801-06216	Temporary Transverse Pavement Marking, 600 mm / 24 in.; m / LFT
801-06217	Temporary Transverse Pavement Marking, Removable, 150 mm / 6 in.; m / LFT
801-06218	Temporary Transverse Pavement Marking, Removable, 600 mm / 24 in.; m / LFT
801-06219	Tubular Marker, Permanent; EACH

The existing codes and pay items are being revised as follows:

801-97643	Buzz Strips; m / LFT becomes
801-97643	Temporary Buzz Strips; m / LFT
801-09133	Changeable Message Sign; EACH becomes
801-09133	Temporary Changeable Message Sign; EACH
806-53072	Temporary Traffic Signal; LS becomes
801-53072	Temporary Traffic Signal; LS
806-01851	Temporary Traffic Signal with Loop Detectors; LS becomes
801-01851	Temporary Traffic Signal with Detectors; LS

The code numbers and pay item names for other pay items listed in Standard Specifications Section 801 are unchanged.

ARCHIVED

RVC:DLS:sc  
Attachments