

CRACKERS DEMO

INVITATION TO BID

June 1,2026

Minority and Women's Business Enterprises Division
402 W Washington Street, Room 2469
Indianapolis, IN 46204

Project: CL-02-061, 4332 W 79th Street Culvert Replacement

Location: Marion County

Bid Due: June 25,2026

Quotes Due: June 24,2026 by 10am

To Whom It May Concern:

Rieth-Riley Construction Co., Inc. is bidding on the project listed above as a prime contractor for **CL-02-061, 4332 W 79th Street Culvert Replacement**. We are inviting quotations from MBE/WBE/IVOSB subcontractor/supplier firms that might be interested in partnering with us on the project.

Subcontractor/Supplier opportunities include:

Traffic Sign/Marking, Pipe, Sod/Seed, Aggregates, Trucking, Surveying, Rebar, Milling, Ready Mix

Plans and specifications are available for review on Repro Graphics or by request through Crackers Estimator.

Questions regarding this project should be directed to Luke Clark at lukec@crackersdemo.com or at 574-875-7684

Written quotations should be sent via email to lukec@crackersdemo.com no later than June 24, 2026, by 10am.

Thank you



PART 3
CONTRACT ITEMS AND UNIT PRICES

Contract Item No.	Description/ Unit Price [in Words]	Estimated Quantity		Prices in Figures	
				Unit Price	Total Price for Item
I-105-06845	CONSTRUCTION ENGINEERING	1.0	LSUM		
I-110-01001	MOBILIZATION AND DEMOBILIZATION	1.0	LSUM		
I-201-52370	CLEARING RIGHT OF WAY	1.0	LSUM		
I-202-96133	PIPE, REMOVE	55.0	LFT		
I-205-11626	PUMP AROUND	1.0	EACH		
I-205-12108	STORM WATER MANAGEMENT BUDGET	1,800.0	DOL		
I-205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.0	LS		
I-207-09935	SUBGRADE TREATMENT, TYPE IC	52.0	SYS		
I-211-09265	STRUCTURE BACKFILL, TYPE 2	71.0	CYS		
I-301-12234	COMPACTED AGGREGATE NO 53	51.0	CYS		
I-306-08034	MILLING, ASPHALT, 1 1/2 IN.	313.0	SYD		
I-401-11526	JOINT ADHESIVE	142.0	LFT		
D-402-02124	HMA SURFACE, TYPE B, OPTION A	26.0	TON		
I-406-05520	ASPHALT FOR TACK COAT	1.0	TONS		
I-616-06405	RIPRAP, REVETMENT	27.0	TONS		
I-616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	178.0	SYS		
I-621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.0	EACH		
I-621-02770	EROSION CONTROL BLANKET	63.0	SYD		
I-621-06560	MULCHED SEEDING U	332.0	SYD		
I-702-51005	CONCRETE, A, SUBSTRUCTURE	5.0	CYS		
I-702-51015	CONCRETE, B, FOOTINGS	2.0	CYS		
I-703-06029	REINFORCING BARS, EPOXY COATED	615.0	LBS		
I-714-11192	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	53.0	LFT		
I-715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	20.0	TONS		
I-801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.0	EACH		
I-801-06625	DETOUR ROUTE MARKER ASSEMBLY	23.0	EACH		
I-801-06640	CONSTRUCTION SIGN, A	10.0	EACH		
I-801-06775	MAINTAINING TRAFFIC	1.0	LSUM		
I-801-07118	BARRICADE, III-A	72.0	LFT		
I-801-07119	BARRICADE, III-B	48.0	LFT		
I-808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	129.0	LFT		
I-808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	76.0	LFT		

TOTAL BID: _____