




# Prestressed Tips

**James Collins – Prestress Services Industries, LLC**  
**Pete White – INDOT Bridge Design**



**PRESTRESS**



# Overview

- Who We Are
- Basics of Building a Beam
- Design Pointers
- Common RFIs
- ASCE / INDOT - Design Topic Updates




# Prestress Services Industries, LLC



PRESTRESS

- I-Girders, Box & NEXT Beams, Architectural Panels, Deck Panels, Custom Prestress Sections
- PCI Certified Production Plants
  - Decatur, IN
  - Mount Vernon, OH
  - Lexington, KY
  - Melbourne, KY
- Prestress Transportation (PST)



# James Collins – Drafting Manager

- Employed at Prestress since January 2008
- Prestress has Produced over 5,180 bridge jobs over 18-year career
- Over 3,000 projects involved with personally (Drawing, Checking, reviewing plans.)
- Over 700 INDOT projects



**PRESTRESS**


# Basics of Building a Beam



# Prestressing Bed Basics



# Bottom of the Bed



# Uprights



# Bunker Stacks




# Pull Plates




# Strand Chucks and Stressing Jack



# Intermediate Beam Ends




# Holddowns



## H-55-R Strand Restraining Device

### Specifications:



- High Strength Coil Rod Diameter – 1.0" (25 mm).
- Max. safe working load per strand – 4,000 lbs. (17.7 kN) See Note 3 on Page 8.
- Max. safe working load per unit – 48,000 lbs. (212.0 kN) See Note 3 on Page 8.
- (A) Horizontal spacing – 2.0" (50 mm).
- (B) Min. vertical spacing (form to centerline of first strand) – 2.0" (50 mm).
- (C) Standard vertical spacing – 2.0" (50 mm).
- (D) Overall width – 6-7/8" (174.6 mm).



**Warning:** Safe working load displayed can only be achieved by utilizing Dayton/Richmond B-12 High Strength Coil Rod and B-25 Heavy Coil Nuts.



# Holddowns



# Holddowns


## 406-12.02(03) Indiana Bulb-Tee Beam [Rev. Oct. 2012, Sep. 2022, Feb. 2025]

Draped strands may be considered for use in a bulb-tee beam if tensile stresses in the top of the beam near its end are exceeded if using straight strands, or to increase shear capacity near beam ends. The maximum allowable compressive strength, tensile strength, extent of strand debonding, and number of top strands should be considered in evaluating the need for draped strands. If draped strands are used, the maximum allowable hold-down force per strand should be 3.8 kip, with a maximum total hold-down force of 33 kips.


Hold-down points should be located as follows to facilitate beam fabrication:

1. Beams less than or equal to 50 ft long: Use 5'-0" between hold-down points (2'-6" each side of the beam centerline).
2. Beams greater than 50 ft long: Use 10'-0" between hold-down points (5'-0" each side of the beam centerline).


# A Frames



# Bed Layout



# Bed Layout



POUR 3

642

630

350' BED LAYOUT  
\* FOR INTERNAL USE ONLY



# Design Pointers




# Camber

## ESTIMATED CAMBERS

SPAN	2, 9 & 16 (EXT)	3, 10 & 17 (EXT)	4, 11 & 18 (EXT)	5, 12 & 19 (EXT)	6, 13 & 20 (EXT)	2-6, 9-13 & 16-20 (INT)
MARK #	504, 506, 525, 532	507, 509, 526, 533	510, 512, 527, 534	513, 515, 528, 535	516, 518, 529, 536	505, 508, 511, 514, 517
CAMBER AT RELEASE	5.7"	5.7"	5.7"	5.7"	5.7"	5.7"
CAMBER AT ERECTION	10.0"	10.0"	10.0"	10.0"	10.0"	10.0"
SUPERIMPOSED DEAD LOAD	-7.3"	-7.3"	-7.3"	-7.3"	-7.3"	-8.6"
RESIDUAL CAMBER	2.7"	2.7"	2.7"	2.7"	2.7"	1.4"
SPAN	1 & 21 (EXT)	1 & 21 (INT)	7, 8, 14 & 15 (EXT)	7, 8, 14 & 15 (INT)		
MARK #	501 & 503, 537 & 539	502, 538	519, 521, 530, 522, 524, 531	520, 523		
CAMBER AT RELEASE	5.8"	5.8"	5.8"	5.8"		
CAMBER AT ERECTION	10.1"	10.1"	10.1"	10.1"		
SUPERIMPOSED DEAD LOAD	-6.7"	-7.8"	-6.4"	-7.5"		
RESIDUAL CAMBER	3.4"	2.3"	3.7"	2.6"		

# Lift Loops

- Based on PCI Handbook and Internal PSI Testing
- RFI for Inclined or Additional Loops for Passing
- Over RR Need 150% Capacity
- Specification Section 707



# Standard Spec 707.08

- Assumed Lifting Point = Transportation Point
- Box Beams & NEXT Beams:  $>1.5d$  and 3'
- I-Beams/ Bulb-Tees:  $>d$  and 3.5'
- PSI Checks Angled Lifting or “Other” Methods

## 707.08 Handling and Shipping

Precast concrete and precast prestressed concrete structural members shall not be subjected to excessive abuse which produces crushing or undue marring of the concrete. All structural members damaged during handling, storing, transporting, or erecting shall be replaced. Unless otherwise approved, precast concrete and precast prestressed concrete structural members shall be handled with a suitable hoisting device provided with a spreader sling. The spreader shall be of sufficient length to prevent horizontal forces being produced in the structural member due to lifting and shall be equipped with leads and hooks at each end. NEXT beams shall be handled in a manner that minimizes twisting of the beams. NEXT beams shall be lifted by a minimum of four lifting points, two at each end of the beam, with a load equalizing device at one end of the beam that will prevent torsional forces in the beam during lifting. Unless otherwise shown on the contract plans, the location of the lifting points along the tops of the beams shall be in accordance with the transportation support point requirements given herein. If any other method of handling is used, it shall be shown in the working drawings. If the method produces horizontal forces in the precast concrete or precast prestressed concrete structural member, design calculations shall be submitted showing resulting stresses. The design of the structural members shall be satisfactory to handle these stresses in accordance with AASHTO LRFD Bridge Design Specifications. The structural members shall be lifted by the devices and procedures shown on the working drawings.

During transportation, the structural members shall be supported with truck bolsters or battens no less than 4 in. wide which are padded with no less than 1/2 in. of rubber. The ends of I-beams, U-beams, and bulb-tee shall extend no more than the depth of the beam and not more than 3 ft 6 in. beyond the supports. The ends of box beams and NEXT beams shall extend no more than 1 1/2 times their depth and not more than 3 ft beyond the supports. The supports at one end of NEXT beams shall be designed to allow the transportation vehicle to twist about its longitudinal axis independently from the beams, thereby eliminating the possibility of introducing torsional forces in the beams during transportation. The ends of slabs shall extend no more than the depth of the beam beyond the supports.

# Contract Plan Lifting Notes

- Be Wary of Old Drawing Sets
- Remove Note


The beams are to be supported at bearing points while stored and while transporting to job site. Several lifting devices are satisfactory. The type used must be guaranteed by the beam manufacturer and approved by the Engineer on the Shop Drawings.

# Welded Wire Reinforcement (WWR)


- Mats have 6-9 Week Leadtime
- Enable Cage Pre-Fabrication
- Maximum Limits of D31 at 2”
- Cross wire is 40% size of Main  
le:  $0.4 \times 0.31 \text{ in}^2 = 0.124 \text{ in}^2$




# End of Beam Web Congestion




# End of Beam Web Congestion



*Sample Beam End Elevation*



*Typical 401a Bar*



*Sample WWR Beam End Elevation*



# Prestressing Strand Pattern & Debonding

- Spread Strands Across Beam Width
- Top Flange Strands Outside of Draped Strands
- INDOT Design Manual 406-10.0
- Debonding Staggered in Alternate Positions, Rows
- Avoid Debonding:
  - Outermost Side Strands
  - Strands Under Web


# Prestressing Strand Pattern & Debonding




*Sample Contract  
 Plan Sections*



*Sample Shop  
 Drawing Sections*




# Prestressing Strand Pattern & Debonding



**STRAND PATTERN AT BEAM ENDS**  
Scale: 1" = 1'-0"

*Sample Contract Plan Section*



*Sample Shop Drawing Section*


# Skewed Box Beams

- Minimize Skew as Possible
- Clip Corners for Reduced Cracking
- Recognize Big Skews Don't Sit Evenly
- Design for Unevenness
- Shims Now Included



# Beam End Notches


- Beam End Notches Create Corners
- Avoid or Minimize Notches
- Lower Draped Strand
- Provide Additional Reinforcement to Prevent Crack Propagation



# Common RFIs



# Request for Information (RFI)



**RFI Form**  
**REQUEST FOR INFORMATION**

**PLEASE SEND ALL HARDWARE (NOT SUPPLIED BY PSD). Requested Delivery Date:** \_\_\_\_\_  
**THAT IS TO BE CAST IN THE BEAMS TO: Anticipated days beam seats will be poured, prior to delivery:** \_\_\_\_\_

**Mt. Vernon Plant @ 435 Columbus Road, Mt. Vernon, OH 43050**

<b>RE:</b>			
<b>Date:</b>	<b>Requested Return Date:</b>		
<b>To:</b>	<b>From:</b>		

**Deck Forming:**

Is there a minimum/maximum casting date between beam and deck fabrication?	<input type="radio"/> YES	<input type="radio"/> NO
<i>If YES to above questions please specify how many days</i>		
Is this a phase job?	<input type="radio"/> YES	<input type="radio"/> NO
Beam lines requiring inserts:		
Using exterior form hangers / inserts?	<input type="radio"/> YES	<input type="radio"/> NO
Type:	Spacing:	
Using stay in place forms & metal deck clips?	<input type="radio"/> YES	<input type="radio"/> NO
Spacing:	Gauge:	

**Additional Hardware:**

Require safety post inserts?	<input type="radio"/> YES	<input type="radio"/> NO
Insert Type & Size:	Spacing:	
Other inserts?	<input type="radio"/> YES	<input type="radio"/> NO
Insert Type & Size:	Spacing:	

**Diaphragms:**

Concrete Diaphragm Notice: For diaphragms at the beam ends, PSI will only provide straight threaded bars. Contractor is responsible for field bending as needed.

None <input type="radio"/>	Concrete <input type="radio"/>	Steel <input type="radio"/>	Steel Supplier name: _____
----------------------------	--------------------------------	-----------------------------	----------------------------

**Product Inspection:**

State Job:	LPA:	County:	Private:
------------	------	---------	----------

**Sealer: Please be sure to fill out all information**

Sealer requirement?	YES	NO (skip section)	Federal Color:
Ext. Bottom	Ext. Face	Tops	All Beams
Thoroscal	Silane	Non-epoxy urethane	Other (specify)

**Lifting devices: Indicate 90° to pass beams (2 cranes) or 60° for single crane**

Requesting alternate lift loops? (including loops to pass beams)	<input type="radio"/> YES	<input type="radio"/> NO
------------------------------------------------------------------	---------------------------	--------------------------

Lifting loops will be provided in accordance with applicable state standards and the latest edition of the PCI Design Handbook. Beams are designed to be picked using all provided lift loops simultaneously and equally, engaged 90° to the beam (vertical). Prestress Services is not liable for any improper use of the provided loops.  
**Restrictions:** Additional lifting loops may be provided in alternate locations and orientations upon request. The design, capacities, locations of any additional lift loops is the sole responsibility of the contractor and designer. It will be their responsibility to provide design calculations to the fabricator prior to the submittal of the beam shop drawings. The calculations will show that the additional lift loops can handle the beams, as well as showing that there will be no adverse effects on the beams. Prestress Services Industries, LLC reserves the right to reject any and all lift loop requests. The Fabricator shall install appropriately sized loops at the angle and location requested in accordance with all applicable PCI standards.  
**Designer** = responsible for checking the beam being picked with loops at location dictated by Contractor.  
**Fabricator** = responsible for installing safe lifting loops at the location and angle already checked by designer.  
**Contractor/Erector** = responsible for all lifting/rigging operations and equipment (anything used for lifting, but excluding the loops in the beams)


**GENERAL NOTES**

- ALL 17"x48" COMPOSITE BOX BEAMS ARE MADE IN ACCORDANCE WITH 2019 OHIO DEPARTMENT OF TRANSPORTATION SPECIFICATIONS, AND STANDARD DRAWING PSB0-2-07 AND THE 9th EDITION, 2020 AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS AND THE ODOT BRIDGE DESIGN MANUAL, 2020. LOADING IS PER HL93, FWS = 0.060 KSF.
- CONCRETE: 150 LBS/CF (INCLUDES REINFORCEMENT).
- CONCRETE STRENGTHS: 6,000 PSI AT RELEASE, 8,000 PSI AT 28 DAYS.
- FINISHES: TOP - SCORE 1 1/2" O.C. 1" DEEP.  
 BOTTOM & SIDES - AS CAST AGAINST FORMS.  
 ENDS - FIELD APPLY TYPE B WATERPROOFING THAT ARE NOT COMPLETELY ENCASED IN CONCRETE (BY OTHERS)  
 SURFACE PREP - 100 GRIT SANDBLAST/WATER BLAST FINISH ACCORDING TO ODOT CMS 512.03 SECTION F.  
 SEALER PREP TO BE COMPLETED BY PS.  
 SEALER - EPOXY-URETHANE TO BE FURNISHED AND APPLIED BY PS. COLOR: LIGHT NEUTRAL, FED# 17778  
 COVERAGE - ODOT APPROVED EPOXY/URETHANE APPLIED AT AN APPROVED RATE AS SPECIFIED PER MANUFACTURER (LISTED ON ODOT QUALIFIED PRODUCTS LIST) RECOMMENDATIONS (SEE DETAIL)  
 KEYWAYS - MEDIUM SANDBLAST AT PLANT WITHIN FOUR DAYS PRIOR TO SHIPPING.  
 BEAM ENDS - SEAL ALL STRANDS WITH TYPE E WATERPROOFING PER 512.08. WATERPROOFING SHALL EXTEND A MINIMUM OF 2" SURROUNDING EACH STRAND END. (BY OTHERS)

	SPAN 1 & 3	SPAN 2
AT DAY 0 =	1 1/2"	1 1/2"
AT DAY 30 =	1 1/2"	2 1/2"
REMAINING DEAD LOAD DEFLECTION =	1/2"	1/2"

**SHIPOOSE HARDWARE**

- 66 - 1"Øx8'-0" TIE RODS (G)
- 132 - 1/2"x4"x4" PLATE WASHERS w/1 1/8"Ø HOLE (G)
- 132 - 1"Ø HEAVY HEX NUTS (G)
- 24 - 1"Øx2'-5" DOWEL RODS (SMOOTH, A-311) (G)
- 48 - 1"Øx1'-10" DOWEL RODS (SMOOTH, A-311) (G)
- 72 - 1"x6"x6" PEJIF GROUT RETAINERS
- 232 LF - 7 STRAND JUTE
- 70 LBS - INTERPLAST N GROUT ADDITIVE



**INSTALLED HARDWARE**

14 - TOTAL GAL. OF EPOXY-URETHANE. CALCULATED AT A RATE OF 120 SF/GAL

**COATINGS (LEGEND)**

- (G) HOT DIP GALVANIZED ASTM A153 OR A153
- (EP) ELECTROPLATED ASTM B633
- (B) BLACK ASTM A615

**LIFTING LOOP GUIDELINES:**

ALL LIFTING DEVICES PROVIDED BY PRESTRESS SERVICES ARE DESIGNED TO BE USED SIMULTANEOUSLY AND EQUALLY, 90 DEGREES TO THE BEAM AS RECOMMENDED BY PCI GUIDELINES WITH THE USE OF A SPREADER BEAM OR TWO CRANES. ANY ADDITIONAL LIFTING DEVICES THAT ARE REQUESTED THAT DEVIATE FROM THIS STANDARD FOR ERECTING PURPOSES IS THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR IS ADVISED TO HAVE AN ENGINEER REVIEW ANY DEVIATION FROM THIS STANDARD WITH CONSIDERATION GIVEN TO BEAM STRESSES, STRENGTH, AND STABILITY. PRESTRESS SERVICES WILL NOT BE LIABLE FOR ANY VARIATIONS TO THE STANDARD PROCEDURE.

**NOTES**


**DRAWING INDEX**

SHEET #	SHEET TITLE	DATE	ISSUED FOR	BY	DATE	ISSUED FOR	BY	DATE	ISSUED FOR	BY
1	COVER SHEET									
2	ERECTOR LAYOUT & DETAILS									
3	ERECTOR DETAILS									
4	BEAM DETAILS									
5	BAR BENDING DETAILS									
6	REINFORCEMENT SECTIONS									
7	STRAND DETAILS & END MATS									
8	201 REINFORCEMENT									
9	202 REINFORCEMENT									
10	203 REINFORCEMENT									
11	204 REINFORCEMENT									
12	205 REINFORCEMENT									
13	206 REINFORCEMENT									
14	207 REINFORCEMENT									
15	208 REINFORCEMENT									
16	209 REINFORCEMENT									
17	201 HARDWARE									
18	202 HARDWARE									
19	203 HARDWARE									
20	204 HARDWARE									
21	205 HARDWARE									
22	206 HARDWARE									
23	207 HARDWARE									
24	208 HARDWARE									
25	209 HARDWARE									

**LPA PROJECT**

**COVER SHEET**

ALLEN COUNTY, OHIO PID: 115921  
 S WEST ST. OVER OTTAWA RIVER  
 BRIDGE ID: ALL-MEST-00.090 SFN: 260096  
 17"x48" COMPOSITE BOX BEAMS  
 CONTRACTOR: RB JERGENS



**PRESTRESS SERVICES INDUSTRIES LLC**  
 Production: Mt. Vernon, OH (740) 393-1121 | Drafting: Columbus, OH (614) 299-0461  
 DATE: 10-12-23 DRAWN: KADEN RUCKER CHECKED: ISSAC HEARN  
 CODE: CB17480 SHEET: 1 OF 25 JOB NO: P23358




# Box Beam Drains



- Sized for thickness of bottom slab (5.5" Typ.)
- 1" Diameter




# Inserts at Form Seams




# Web Holes & Inserts



# Bottom Bulb Confinement Bars



*Design Manual Detail*



*Shop Drawing Detail*






# ASCE / INDOT – Design Topic Updates





# Beam Camber

- What is prestressed beam camber?
  - (-) Downward deflection due to beam self weight
  - (+) Upward deflection due to internal prestressing
  - (=) Beam camber at release (immediately after strand detensioning)
  - Beam camber at erection (considers increase in camber due to creep)
  - Highly variable and hard to accurately predict (concrete stiffness, humidity, temperature, time)





# Beam Camber

- What issues can result from unanticipated prestressed beam camber?
  - Too much camber can cause beam to interfere with deck reinforcement
  - Too little camber can result in excessive fillet loads
  - Too little camber can require additional fillet reinforcing



# Beam Camber

- Prestress Services shared as-built camber data for hundreds of prestressed beams.
  - Discrepancies between predicted and actual cambers much more pronounced in larger beams, and under-camber much more frequent than over-camber in all sizes



# Beam Camber

- New IDM Figure 406-12E provides example of fillet load calculations
  - Example has been simplified by assuming a constant grade vertical roadway profile
  - Project-specific calculations should include appropriate vertical curve corrections in fillet thickness calculations
  - Beam seat elevations should be based on full anticipated camber (not 75% of calculated)

## EXAMPLE FILLET DESIGN: THICKNESS USED TO CALCULATE FILLET LOAD

### Anticipated Camber from Beam Analysis:

Prestress Camber at Release: 6.0 in.  
Beam Self Weight at Release: -3.0 in.  
Beam Camber at Release = 6.0 in. - 3.0 in. = 3.0 in.  
Deflection Multiplier at Erection: 1.75

### Design Camber at Erection used for Geometry:


Calculate beam camber at erection = (6.0 in. - 3.0 in.) (1.75) = 5.25 in.  
Minimum fillet thickness at mid-span of beam = 0.75 in. + 49 in. x 0.5 x 2% = 1.24 in. (see 404-2.02(03))  
Fillet thickness at ends of beam = 5.25 in. + 1.24 in. = 6.49 in. (Assuming a constant grade vertical roadway profile. Bridges constructed with vertical curves will require vertical curve correction calculations.)

### Assumed Camber at Erection used for Fillet Loads:


Calculate beam camber used to calculate fillet load = 5.25 in. x 75% = 3.94 in. (see 406-12.04(03))  
Min. fillet thickness for fillet load = 1.24 in. + (5.25 in. - 3.94 in.) = 2.55 in.

### Fillet Summary:

Design fillet thickness used to calculate fillet load varies from 6.49 in. at beam ends to 2.55 in. at mid-span  
Actual fillet thickness used for bridge geometry varies from 6.49 in. at beam ends to 1.24 in. at mid-span




ELEVATION VIEW




SECTION A-A

# Beam Camber

- How can we better deal with prestressed beam camber?
  - Make sure plans are consistent and clear
  - New IDM Figure 406-12F provides example of camber information to be shown on design plans
  - Continue to evaluate predicted versus measured beam camber to determine if multipliers should be updated, but for now continue to IDM guidance of 1.75



ELEVATION VIEW



SECTION A-A

TABLE OF CAMBERS (In.)				
	Span A Ext. Beam	Span A Int. Beam	Span B Ext. Beam	Span B Int. Beam
(1) Beam Camber at Release	3.00	3.00	3.25	3.25
(2) Beam Camber at Erection	5.25	5.25	5.69	5.69
(3) Deflection due to Deck Pour	-2.50	-2.50	-2.80	-2.80
(4) Residual Beam Camber	2.75	2.75	2.89	2.89


**Camber Notes:**

- (1) Beam camber at release is the upward camber due to prestress minus the downward deflection due to beam self-weight, without time dependent creep effects.
- (2) Beam camber at erection is upward camber due to prestress minus the downward deflection due to beam self-weight, with time dependent creep effects.
- (3) Deflection due to deck pour is the beam deflection due to the weight of wet concrete at the time of deck pour.
- (4) Residual camber is the difference between beam camber at erection and the deflection due to deck pour and represents the camber of the beam immediately after the deck pour.




# Beam Camber

- Effect of beam camber over time on continuous bridges
  - If unrestrained, beams continue to camber upwards for about 120 days
  - Continuity is often established by pier diaphragms prior final camber
  - Pier diaphragms provide restraint against camber (halt upward deflection)
  - Secondary positive restraining moment develop
  - Increase in tension at the bottom of the beams




# Beam Camber

- How do we design prestressed beams to account for secondary restraining moments?
  - Assume a reasonable time between beam casting and pier diaphragm pour (more time reduces restraining moments but constrains construction schedules)
  - Secondary restraining moment might necessitate additional strands
  - IDM 406-12.06(04) specifies between 28 days and no more than 60 days
  - A note should be placed on the plans indicating, *“The beams shall be cast a minimum of [ ] days prior to pouring the pier diaphragm.”*



# Beam Camber

- Secondary restraining moments shouldn't be considered if they result in a less conservative design
  - Positive restraining moments at interior supports will offset negative moments due to loads that are applied to the composite section
  - Longitudinal deck reinforcement requirements will be reduced, so positive restraining moments should be ignored when designing for negative moment capacity



# Beam Camber

- Changes in beam camber over time can result in secondary positive restraining moments in continuous structures only
  - Single-span (or multi-span without continuity diaphragms) bridges don't provide any resistance to beam end rotation due to creep
  - Integral and semi-integral end bents are assumed to allow rotation at beam ends

Please don't include notes related to casting dates on plans for single-span bridges

## GENERAL BEAM NOTES

1. Beams shall be cast a minimum of 60 days prior to pouring the deck.
2. Allowance in the beam length should be made during fabrication to

# Beam Camber

- 2026 Standard Drawings for Elastomeric Bearing Assemblies will include standard load and flange plates, and standard shims that can be used to account for unanticipated camber





TABLE OF DIMENSIONS

Bearing Designation	Plate Width W	Plate Length L	Flange Connection Plate Thickness	Bearing Plate Thickness
T1	28 1/2"	18"	1 1/2"	3/4"
T2	28 1/2"	18"	1 1/2"	3/4"
T3	28 1/2"	18"	1 1/2"	3/4"
T4	28 1/2"	20"	1 1/2"	3/4"
TH1	41 1/2"	18"	1 1/2"	3/4"
TH2	41 1/2"	18"	1 1/2"	3/4"
TH3	41 1/2"	18"	1 1/2"	3/4"
TH4	41 1/2"	20"	1 1/2"	3/4"

INDIANA DEPARTMENT OF TRANSPORTATION

ELASTOMERIC BEARING ASSEMBLY DETAILS  
TYPE T1 to TH4 FOR PRESTRESSED BULB-TEE AND  
WIDE FLANGE PRESTRESSED BULB-TEE BEAMS  
SEPTEMBER 2026

STANDARD DRAWING NO. E 726-BEBP-04

DESIGN STANDARDS ENGINEER	DATE
CHIEF ENGINEER	DATE



Questions?



# Prestress Services Industries, LLC



- Sales:
  - Dave Szydlik [dszydlik@prestressservices.com](mailto:dszydlik@prestressservices.com)
- Project Services:
  - Shanon Schug [sschug@prestressservices.com](mailto:sschug@prestressservices.com)
- Engineering:
  - Celeste Spaans, PE [cspaans@prestressservices.com](mailto:cspaans@prestressservices.com)
- Drafting:
  - James Collins [jcollins@prestressservices.com](mailto:jcollins@prestressservices.com)

