



SUBGRADE STABILITY CHALLENGES WITH RUBBLIZE AND ROLL PAVEMENT REHABILITATION



Christopher Merklin, PE, Administrator, ODOT
Office of Geotechnical Engineering




Department of
Transportation

HOW DID WE GET HERE?



- Major arterial route – 6 miles of major rehab
 - 4-Lane divided road
 - 2 Proposed R-cut intersections, 2 Proposed at grade intersections, 4 Bridge rehabilitations
 - \$30M DB contract, but...
 - ODOT performs borings, designs pavement (9" Rubblize and Roll, 7.25" asphalt), intersections, etc.
 - Full depth replacement at outside shoulder widenings, intersections, bridge approaches with 14" cement stabilization

SAMPLE SLIDE



GEOTECHNICAL PROFILE

- Rubblize and Roll is not an option when the average N_{60L} value for the subgrade below the existing pavement is less than 12.
- During construction, the Rubblize and Roll is attempted before an area is selected for excavation and replacement. **The actual excavation areas will be selected based on the inability to Rubblize and Roll.**

GEOTECHNICAL PROFILE

Chemical Stabilization Options		
320	Rubblize & Roll	Option
206	Cement Stabilization	Option
	Lime Stabilization	No
206	Depth	NA

Excavate and Replace Stabilization Options		
Global Geotextile	Average(N60L):	0"
	Average(HP):	0"
Global Geogrid	Average(N60L):	0"
	Average(HP):	0"

Design CBR	9
------------	---


% Samples within 6 feet of subgrade			
N ₆₀ ≤ 5	0%	HP ≤ 0.5	1%
N ₆₀ < 12	8%	0.5 < HP ≤ 1	1%
12 ≤ N ₆₀ < 15	10%	1 < HP ≤ 2	17%
N ₆₀ ≥ 20	64%	HP > 2	40%
M+	19%		
Rock	3%		
Unsuitable	9%		

Excavate and Replace at Surface	
Average	0"
Maximum	0"
Minimum	0"

% Proposed Subgrade Surface	
Unstable & Unsuitable	45%
Unstable	40%
Unsuitable	6%

	N ₆₀	N _{60L}	HP	LL	PL	PI	Silt	Clay	P 200	M _C	M _{OPT}	GI
Average	28	18	3.06	21	15	6	26	15	41	13	10	3
Maximum	90	30	4.50	40	21	22	67	39	91	26	16	16
Minimum	6	6	0.50	15	12	1	6	4	11	5	0	0

Classification Counts by Sample																			
ODOT Class	Rock	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-3	A-3a	A-4a	A-4b	A-5	A-6a	A-6b	A-7-5	A-7-6	A-8a	A-8b	Totals
Count	6	1	34	38	0	1	0	0	27	150	19	0	14	2	0	0	0	0	292
Percent	2%	0%	12%	13%	0%	0%	0%	0%	9%	51%	7%	0%	5%	1%	0%	0%	0%	0%	100%
% Rock Granular Cohesive	2%	86%										12%					100%		
Surface Class Count	4	1	21	28	0	1	0	0	12	76	5	0	5	1	0	0	0	0	154
Surface Class Percent	3%	1%	14%	18%	0%	1%	0%	0%	8%	49%	3%	0%	3%	1%	0%	0%	0%	0%	100%



OVERRIDE TABLE		
Calculated Average	New Values	Check to Override
3.06	0.50	<input type="checkbox"/> HP
17.79	6.00	<input type="checkbox"/> N60L

Average HP
Average N_{60L}



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE



<https://youtu.be/Qj5tBPmLBXA>




CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE

- Rubblize and Roll requirements
 - $\geq 75\%$ with maximum dimension < 3 inches above steel
 - $\geq 90\%$ with maximum dimension < 9 inches below steel (100% < 12 inches)
- All of the rubblized concrete met the gradation requirements, so no problem with the subgrade, right?



CONSTRUCTION SEQUENCE



CONSTRUCTION SEQUENCE

- R&R Spec
 - **Do not allow traffic** on the rubblized pavement before the asphalt concrete base and intermediate courses are in place.
 - **No proof rolling**
- Do not allow more than 48 hours to elapse between rubblizing the pavement and placing the initial asphalt concrete course. However, in the event of rain, the Engineer may waive this time limitation to allow sufficient time for the rubblized pavement to dry to the Engineer's satisfaction.

SIDE BAR – R-CUT



SIDE BAR – R-CUT



CONSTRUCTION SEQUENCE

- 2024
 - NB constructed up to intermediate course of asphalt
 - Outside shoulder of SB constructed (chemically stabilized subgrade, underdrains, asphalt)
- 2025
 - Flip traffic to NB
 - Construct SB
 - Surface course on everything
 - Complete the project one construction season early!



CONSTRUCTION SEASON WEATHER COMPARISON

	Month	Precip	Monthly Average
Began milling mainline 6/25/24	Jun-24	1.04	2.97
	Jul-24	2.96	
	Aug-24	6.61	included a 4.25 inches on 8/4/2024
Begn R&R 9/23/24	Sep-24	3.4	
Began paving over R&R 9/25/24	Oct-24	0.85	
Began milling mainline 3/24/25	Apr-25	5.02	4.35
Began R&R 6/5/25	May-25	4.76	
Began paving over R&R 6/6/25	Jun-25	3.28	



2025 CONSTRUCTION



2025 CONSTRUCTION



2025 CONSTRUCTION



2025 CONSTRUCTION





TROUBLESHOOT

- During the placement of the base asphalt the adjacent lane paved previously began to show signs of failure under loading.
- Initial limits of concern: 3800 feet x 24 feet
- 6/25/2025 Perform FWD and DCP, and test asphalt cores

TROUBLESHOOT

- Asphalt –
Stability OK
- DCP – Variable,
but mostly OK
- FWD – **Alarming!**





TROUBLESHOOT

- FWD testing showed very high deflections, structure deficiencies of **5.5 to 7.5 inches**.
- District now concerned about **ALL R&R (19,175 feet)**.
- Test the NB Section (no stability issues, in service) to confirm the design is OK.

TROUBLESHOOT

- 7/9/2025 – 17 ADCP, FWD NB Section



TROUBLESHOOT

- 7/9/2025 FWD NB -
Additional
intermediate course
needed by section

Length	Start	Stop	Treatment	7/9 NB
270	0+30	3+00	Cement Stabilization	0
4100	3+00	44+00	Rubblize & Roll	0.36
234	44+00	46+34	Cement Stabilization	0
Warwick Bridge				
182	48+09	49+90	Cement Stabilization	0
Chippewa Creek Bridge				
219	52+81	55+00	Cement Stabilization	0
1700	55+00	72+00	Rubblize & Roll	0
229	72+00	74+29	Cement Stabilization	0
CSX Bridge				
183	78+17	80+00	Cement Stabilization	0
1350	80+00	93+50	Rubblize & Roll	0
232	93+50	95+82	Cement Stabilization	0
Galehouse Bridge				
4459	98+31	142+90	Undercut	0
510	142+90	148+00	Cement Stabilization	0
4750	148+00	195+50	Rubblize & Roll	0.09
2475	195+50	220+25	Cement Stabilization	0
2375	220+25	244+00	Rubblize & Roll	0.88
1000	244+00	254+00	Cement Stabilization	0
4900	254+00	303+00	Rubblize & Roll	1.46
467	303+00	307+67	Cement Stabilization	0

TROUBLESHOOT

- Now you know how we got here
- 7/14/2025 – Proof roll 5 miles of pavement
- Much improved in the last month (drainage?)
- Isolated (and few) 1/8-1/4” deflection



TROUBLESHOOT

- Run FWD (again) every 150 feet
- Additional (asphalt) structure reduced over time

5104	Total CY	Est. Add. Cost: \$1,339,813.37			NB Passing Lane	SB Passing Lane	SB Driving Lane					
CY	Length	Start	Stop	Treatment	7/9 NB	Initial SB	Initial SB	7/29 SB	Δ (%)	8/13 SB	Δ (%)	New Add Structure (in.)
	270	0+30	3+00	Cement Stabilization	0	0	0	0		0		OK
1082	4100	3+00	44+00	Rubblize & Roll	0.36	3.44	3.08	2.39	22%	2.21	8%	2.25
	234	44+00	46+34	Cement Stabilization	0	0	0	0		0		OK
Warwick Bridge												
	182	48+09	49+90	Cement Stabilization	0	0	0	0		0		OK
Chippewa Creek Bridge												
	219	52+81	55+00	Cement Stabilization	0	0	0	0		0		OK
	1700	55+00	72+00	Rubblize & Roll	0	0.37	0.5	0.27		0.04	85%	OK
	229	72+00	74+29	Cement Stabilization	0	0	0	0		0		OK
CSX Bridge												
	183	78+17	80+00	Cement Stabilization	0	0	0	0		0		OK
	1350	80+00	93+50	Rubblize & Roll	0	0.39	0.2	0.62		0.33	47%	OK
	232	93+50	95+82	Cement Stabilization	0	0	0	0		0		OK
Galehouse Bridge												
	4459	98+31	142+90	Undercut	0	0	0	0		0		OK
	510	142+90	148+00	Cement Stabilization	0	0	0	0		0		OK
1114	4750	148+00	195+50	Rubblize & Roll	0.09	3.67	4.1	2.89	30%	1.98	31%	2
	2475	195+50	220+25	Cement Stabilization	0	0	0	0		0		OK
1184	2375	220+25	244+00	Rubblize & Roll	0.88	6.9	5.52	4.07	26%	4.14	-2%	4.25
	1000	244+00	254+00	Cement Stabilization	0	0	0	0		0		OK
1724	4900	254+00	303+00	Rubblize & Roll	1.46	4.52	4.92	3.11	37%	2.91	6%	3
	467	303+00	307+67	Cement Stabilization	0	5.78	0	0		0		

TROUBLESHOOT

- Average CBR estimated from FWD
- Increased an average of 13%
- Design CBR=9

			NB Passing Lane	SB Passing Lane	SB Driving Lane			
Start	Stop	Treatment	7/9 NB	Initial SB	Initial SB	7/29 SB	8/13 SB	%
0+30	3+00	Cement Stabilization	8	9	9	11	10	11%
3+00	44+00	Rubblize & Roll	14	13	12	15	14	17%
44+00	46+34	Cement Stabilization	10	10	9	9	10	11%
Warwick Bridge								
48+09	49+90	Cement Stabilization	12	14	12	14	13	8%
Chippewa Creek Bridge								
52+81	55+00	Cement Stabilization	10	9	11	9	12	9%
55+00	72+00	Rubblize & Roll	8	8	8	8	8	0%
72+00	74+29	Cement Stabilization	10	9	7	8	8	14%
CSX Bridge								
78+17	80+00	Cement Stabilization	8	9	n/a	n/a	8	
80+00	93+50	Rubblize & Roll	7	8	9	10	11	22%
93+50	95+82	Cement Stabilization	6	11	9	11	12	33%
Galehouse Bridge								
98+31	142+90	Undercut	22	19	22	23	24	9%
142+90	148+00	Cement Stabilization	13	9	8	9	10	25%
148+00	195+50	Rubblize & Roll	10	12	10	14	14	40%
195+50	220+25	Cement Stabilization	12	12	11	13	14	27%
220+25	244+00	Rubblize & Roll	9	11	8	10	8	0%
244+00	254+00	Cement Stabilization	12	12	11	12	12	9%
254+00	303+00	Rubblize & Roll	11	12	12	9	9	-25%
303+00	307+67	Cement Stabilization	n/a	8	n/a	8	10	
								13%

CONCLUSIONS

- Construction water management is important
- We are addicted to global chemical stabilization – weatherproof
- Proof roll rubblized concrete
- If we FWD all of our new pavements, will some of them be deficient?
- Anticipate 10-25% of R&R will be unstable





CONCLUSIONS



POSSIBLE SOLUTIONS

- Geogrid QPL – Type 2
 - Tensar SQ2020
 - \$2.75/SY installed
- Interax NX750
 - \$9.13/SY installed
 - “We observed some slight waving / rolling...due to pore pressure”





**Department of
Transportation**

transportation.ohio.gov

THANK YOU