

## Indiana Standards for Infiltrator ATL Systems

These standards apply to Infiltrator ATL Systems manufactured by Infiltrator Systems, Inc.

### I. General requirements:

- A. Infiltrator ATL systems must be designed and installed according to the *Indiana Standards for Infiltrator ATL Systems, August, 2014* and in a manner that complies with 410 IAC 6- 8.3, Residential On-site Sewage Systems, or 410 IAC 6-10.1, Commercial On-Site Sewage Systems, whichever is applicable, for all requirements not described in the current *Indiana Standards for Infiltrator ATL Systems*.
- B. Infiltrator ATL Systems must comply with local ordinances, requirements and procedures.
- C. Any revisions to the manual must be approved by the department prior to publication and implementation.
- D. The owner, or agent of the owner, must obtain a construction permit from the health department having jurisdiction prior to the start of construction of the residence or commercial facility.

### II. Requirements for certification and oversight:

- A. Designers, installers, and all individuals involved in the permitting process must complete training on the Infiltrator ATL System presented by Infiltrator Systems, Inc., or its sanctioned representative, before they may design, install, or permit an onsite system containing an Infiltrator ATL System. Each individual shall receive a certification from Infiltrator Systems, Inc. that they have completed the training.
- B. Infiltrator Systems, Inc., or its sanctioned representative, must:
  1. Notify the department, at least ten (10) working days in advance, of each training and certification class offered in Indiana for which more than 3 trainees will be present;
  2. Offer field demonstrations of Infiltrator ATL Systems installations; and
  3. Provide health departments, designers and installers ongoing consultation, as needed.

### III. Requirements for recordkeeping:

Infiltrator Systems, Inc. must provide the department with records, on an ongoing basis, of individuals certified for the design, installation or permitting of Infiltrator ATL Systems in Indiana.

### IV. Requirements for local health departments, installers, and owners:


- A. Prior to construction of an Infiltrator ATL System, the installer must notify the local health department, according to written procedures developed by the local health department, as to the start date of construction;
- B. An Infiltrator ATL System must not be constructed during periods when the soil is sufficiently wet to exceed its plastic limit. **Before installation of the sand bed the soils must pass soil plasticity tests.** Soil plasticity tests of the sand bed site include the evaluation of soil samples throughout the sand bed site, both at the

surface and at the depth of installation, to assure that the plastic limit of the soil is not exceeded. The plastic limit of a soil is exceeded when the soil can be rolled between the palms of the hands to produce threads one-eighth (1/8) inch in diameter that do not easily break apart or crumble.

- C. Construction of the Infiltrator ATL System must proceed based on the approved plan. Any changes, alterations, or additions to the approved plan must be submitted by the installer to the local health department, or the Indiana State Department of Health, whichever is applicable, and approved prior to construction.
- D. After construction of the Infiltrator ATL System:
1. The owner must permit staff of the department and local health department to make observations of the system, and collect samples, at reasonable times.
  2. The owner must immediately notify the local health department if the system shows signs of failure as defined in *410 IAC 6-8.3-33*.

Approval for the use of the Infiltrator ATL System technology manufactured by Infiltrator Systems, Inc. under these standards does not constitute an endorsement of this product.

Approved: August 19, 2014  
Effective: August 19, 2014



MICHAEL METTLER, REHS, DIRECTOR  
ENVIRONMENTAL PUBLIC HEALTH DIVISION